

SPL needs for RF tests in SM18

Wolfgang Weingarten

21 January 2010

Outline

- ▶ Functionality of existing cryo-bunkers and their general parameters
- ▶ RF tests foreseen in SM18
- ▶ Cryogenic needs
- ▶ Schedule 2010-12 and related work
- ▶ Conclusion

Functionality of **SM18** vertical SRF test cryostats and bunkers

SPL related items in RED

<i>Vertical cryostat V3: dedicated to SPL study (704 MHz)</i>
Testing sample cavities
Test of individual cavities for SPL study
Extensive tests of individual cavities for SPL project, if approved
<i>Vertical cryostat V4: dedicated to quadrupole resonator (400 MHz)</i>
Test of quadrupole resonator (R&D for SPL and HIE-ISOLDE cavities)
<i>Vertical cryostat V5: dedicated to HIE ISOLDE project (101 MHz)</i>
Test of quarter wave resonator prototypes
Series tests of quarter wave resonators
<i>Vertical cryostat V6: dedicated to LHC cavities (400 MHz)/SOLEIL</i>
Soleil cavity
RF tests of LHC spare cavities
<i>Bunker 1: SOLEIL/LINAC4/SPL study (352/704 MHz)</i>
SOLEIL cryomodule test
SPL Cryomodule Test in horizontal cryostat in pulsed mode
<i>Bunker 2: LHC cryomodules (400 MHz) & HIE-ISOLDE (101 MHz)</i>
Series tests of quarter wave resonator cryomodules
RF tests of LHC spare cryomodules

General parameters for **SM18** vertical cryostats and bunkers


General parameter	V3	V4	V5	V6	B1	B2
RF frequency [MHz]	704	400 - 1200	100	400	352 – 704	101 - 400
Typical temperature range [K]	1.8 – 4.5	1.8 – 4.5	4.5	4.5	1.8 - 4.5	4.5
Nominal installed RF power (depending on whether power coupler is mounted or not)	300 W	200 – 400 W	600 W	300 W	300 W – 1 MW (pulsed)	300 W – 300 kW

SPL related items in RED

SRF tests foreseen in SM18

<i>Plan of SRF testing activities (SM18), version 19 Nov 2009</i>	Number of RF tests per semester								
	2-2009	1-2010	2-2010	1-2011	2-2011	1-2012	2-2012	1-2013	2-2013
Vertical cryostat V3: dedicated to SPL study (704 MHz) TOTAL	1	2	2	2	8	5	6	20	20
Testing sample cavities (e.g. $\beta = 0.5$)	1	2	2						
Test of individual cavities				2	3				
Extensive tests of individual cavities (test rate in full activity is at least 40 per year for 6 years)					5	5	6	20	20
Vertical cryostat V4: dedicated to quadrupole resonator (400 MHz) TOTAL	2	2	2	2	2	0	0	0	0
Test of quadrupole resonator (R&D for SPL and HIE-ISOLDE cavities)	2	2	2	2	2				
Vertical cryostat V5: dedicated to HIE ISOLDE project (101 MHz), test possibly in cryolab TOTAL	0	9	10	10	10	0	0	0	0
Test of quarter wave resonator prototypes (1 - 2 per month)		9							
Series tests of quarter wave resonators (10)			10						
Series tests of quarter wave resonators (20, not yet completely funded)				10	10				
Vertical cryostat V6: dedicated to LHC cavities (400 MHz)/SOLEIL TOTAL	2	2	0	0	0	0	0	0	0
Soleil cavity	1	1							
RF tests of LHC spare cavities	1	1							
Bunker 1: dedicated to SOLEIL/LINAC4/SPL study (352/704 MHz) TOTAL	0	1	0	0	0	1	1	3	3
SOLEIL cryomodule test		1							
SPL Cryomodule Test in horizontal cryostat in pulsed mode (1 MW per cavity)						1	1	3	3
Bunker 2: dedicated to LHC cryomodules (400 MHz) & HIE-ISOLDE TOTAL	1	1	1	1	0	2	2	2	0
Series tests of quarter wave resonator cryomodules (6)						2	2	2	
RF tests of LHC spare cryomodules	1	1	1	1					

SM18 Cryogenic needs for SRF




Average estimated cryogenic load (equivalent to 4.5 K) for the RF tests in SM18 for 2009 – 2014 (numbers beyond 2013 are estimations provided the SPL will be approved)

Schedule 2009

- ▶ *Manage and coordinate working group (Weingarten/Chel)*
 - ▶ Organize cavity design and construction WG/resources plan
 - ▶ Organize periodical coordination meetings
- ▶ *Ancillary equipment I (power coupler) (Montesinos)*
 - ▶ Conceptual specification
- ▶ *Surface analysis tools (Junginger)*
 - ▶ **Commissioning of quadrupole resonator for validating surface treatments**
- ▶ *Surface preparation and clean rooms (Calatroni)*
 - ▶ Ordering of electropolishing equipment
- ▶ *Design/Manufacture of cavities (Capatina)*
 - ▶ Mechanical optimization of cavity shape
 - ▶ Design of magnetic shielding of individual cavities (S. Sgobba, T. Junginger)
- ▶ *Ancillary equipment III (HOM coupler) (Glock)*
 - ▶ Conceptual specification

SMI8 related items in RED

Commissioning of quadrupole resonator for validating surface treatments



- ▶ Quadrupole resonator for testing SRF samples at 400, 800, 1200, ... MHz




Schedule 2010

- ▶ *Manage and coordinate working group (Weingarten/Chel)*
 - ▶ Organize periodical coordination meetings
- ▶ *Surface preparation and clean rooms (request by RF-KS)*
 - ▶ Ordering monitoring systems for assembly
- ▶ *RF testing at low temperatures (request by RF-KS)*
 - ▶ Refurbish low power RF layout, controls and cabling for vertical cryostat no. 3
 - ▶ Provision of magnetic shielding for vertical cryostat
 - ▶ Design of magnetic shielding for cryomodule
 - ▶ Testing sample cavities
- ▶ *RF power equipment (ref. to WGI)*
 - ▶ Order 704 MHz high power amplifier
 - ▶ Design and construct of pulsed power converter for the RF amplifier
- ▶ *Ancillary equipment I (power coupler) (Montesinos)*
 - ▶ Technical design specification
 - ▶ Start fabrication
 - ▶ Provision of warm conditioning test stand (Saclay)

SMI8 related items in RED

RF power equipment



$$V = E_a \cdot L$$

$$Q_{\text{ext}} = V / (R/Q \cdot I \cdot \cos\phi)$$

$$L = 1.065 \text{ m} \quad E_a = 25 \text{ MV/m}$$

beam $\phi = 15^\circ \quad I = 40 \text{ mA}$
 $\tau = 2 \text{ msec} \quad f_{\text{rep}} = 50 \text{ Hz}$

$$R/Q_{\text{linac}} = 566 \Omega$$


$$\Rightarrow Q_{\text{ext}} = Q_L = 1.2 \cdot 10^6$$

$$\Rightarrow P = V \cdot I \cdot \cos\phi = 1 \text{ MW peak}$$

- ▶ BUT: without beam $P = 250 \text{ kW}$
- ▶ \Rightarrow in SM18 we can feed 4 cavities simultaneously with a 1 MW klystron

Refurbish low power RF layout, controls and cabling for vertical cryostat no. 3

RF scheme for vertical tests




Design of magnetic shielding for cryomodule

Microwave Studio simulation

13

Clamp to range: (Min: 0/ Max: 1.15e-006)



Magnetic Shield

Area of Interest

Us/m²


- 1.15e-006
- 1.06e-006
- 9.88e-007
- 9.16e-007
- 8.45e-007
- 7.73e-007
- 7.01e-007
- 6.29e-007
- 5.57e-007
- 4.85e-007
- 4.13e-007
- 3.41e-007
- 2.70e-007
- 1.98e-007
- 1.26e-007

0

Type	B-Field
Component	Abs
Plane at x	0
Maximum-2d	0.0101551 Us/m ² at -1.42109e-014 / -241 / 686.579

$$\mu_r = 10890$$

Testing sample cavities



- ▶ 704 MHz monocell cavity ($\beta = 0.5$) manufactured by CEA/Saclay and available at CERN for validating surface preparation procedures and test equipment



Schedule 2010 cont'd

- ▶ *Design/Manufacture of cavities*
 - ▶ RF optimization of cavity shape/Definition of synergies across labs (with BNL (Calaga))
- ▶ *Ancillary equipment III (HOM coupler) (request by RF-KS)*
 - ▶ Validation of design with Cu cavity
- ▶ *Ancillary equipment IV (Inspection equipment for on-line and post mortem analysis) (request by RF-KS)*
 - ▶ Quench detection in Hell by "second sound" (possibly with Univ.'s Göttingen/Wuppertal)
 - ▶ Upgrade inspection equipment (Questar® type)
 - ▶ Design temperature mapping equipment
- ▶ *Cryogenics for RF tests (Vuillerme)*
 - ▶ Design cryogenic equipment for vertical and horizontal cryostats and helium distribution (4.5 and 2 K)
- ▶ *Surface preparation and clean rooms (Calatroni)*
 - ▶ Ordering processing systems (HPR)
 - ▶ Processing of sample sc cavities

SM18 related items in RED




Quench detection in HeII by "second sound"



Second sound
detection system in
use at Cornell
University
adopted from
Z A Conway
TTC report 2008-006

Design temperature mapping equipment



Temperature mapping
equipment
in use at DESY
adopted from D. Reschke, WD
MöCller
TTC meeting DESY Jan 2008

Schedule 2010 cont'd

- ▶ *Water rinsing stations (Calatroni)*
 - ▶ Ordering processing systems upgrade b. I18 (hardware and control)
- ▶ *Ancillary equipment II (Frequency tuner) (Capatina)*
 - ▶ Adaptation of CEA tuner to SPL cavity
- ▶ *Design/Manufacture of cavities (Capatina)*
 - ▶ Manufacture of Cu cavity model
 - ▶ Individual cavity tuning and field flatness tuning equipment
 - ▶ Purchase of niobium
 - ▶ Writing technical specification
 - ▶ Start fabrication of Nb cavities
- ▶ *Ancillary equipment III (HOM coupler) (Glock, Rostock)*
 - ▶ Technical design specification

SMI8 related items in RED



Schedule 2011

- ▶ *Manage and coordinate working group (Weingarten/Chel)*
 - ▶ Organize periodical coordination meetings
 - ▶ *Surface preparation and clean rooms (request by RF-KS)*
 - ▶ Upgrade of clean room equipment
 - ▶ Processing of sc cavities
 - ▶ *RF testing at low temperatures (request by RF-KS)*
 - ▶ Perform RF tests of individual cavities in vertical cryostat
 - ▶ *RF power equipment (ref. to WGI)*
 - ▶ Acquire and commission high power equipment for RF test in bunker
 - ▶ *Ancillary equipment I (power coupler) (Montesinos)*
 - ▶ Conditioning of power couplers
 - ▶ *Ancillary equipment III (HOM coupler) (request by RF-KS)*
 - ▶ RF test on sc cavity
 - ▶ Start fabrication
 - ▶ *Ancillary equipment IV (Inspection equipment for on-line and post mortem analysis) (request by RF-KS)*
 - ▶ Manufacture and commission temperature mapping equipment

SMI8 related items in RED

Schedule 2011 cont'd

- ▶ ***Cryogenics for RF tests (Vuillerme)***
 - ▶ Acquire and install cryogenic equipment for vertical and horizontal cryostats and helium distribution (4.5 K)
 - ▶ Acquire and install cryogenic equipment for helium pumping and purification (2 K)
- ▶ ***Surface preparation and clean rooms (Calatroni)***
 - ▶ Treatment of SPL cavities as requested
- ▶ ***Design/Manufacture of cavities (Chel, CEA)*** ***SMI8 related items in RED***
 - ▶ Manufacture of cavities by CEA (Saclay)
- ▶ ***Ancillary equipment II (Frequency tuner) (Chel, CEA)***
 - ▶ Fabrication of 8 (+1) tuners
- ▶ ***RF testing at low temperatures (Chel, CEA)***
 - ▶ Low power tests (validation) of externally built cavities in CEA (Saclay)
- ▶ ***Design/Manufacture of cavities (Olry, CNRS)***
 - ▶ Manufacture of cavities by CNRS (Orsay)
- ▶ ***RF testing at low temperatures (Olry, CNRS)***
 - ▶ Low power tests (validation) of externally built cavities in CEA (Saclay)

Schedule 2012

- ▶ *Manage and coordinate working group (Weingarten/Chel)*
 - ▶ Organize periodical coordination meetings *SMI8 related items in RED*
 - ▶ Preparation of design report and cost estimate
- ▶ *Surface preparation and clean rooms (request by RF-KS)*
 - ▶ *Assembling of complete cryomodule with 8 cavities in SMI8*
- ▶ *RF testing at low temperatures (request by RF-KS)*
 - ▶ *Extensive tests of sc cavities in SMI8*
 - ▶ *Perform RF tests of cryomodule in bunker*
- ▶ *RF testing at low temperatures (Chel, CEA)*
 - ▶ *High power tests in Cryholab CEA (Saclay)/cryomodule (CERN)*
- ▶ *RF testing at low temperatures (Olry, CNRS)*
 - ▶ *High power tests in Cryholab CEA (Saclay)/cryomodule (CERN)*

Conclusion

1. Available funding (for the SPL study) is taken as granted.
 2. This funding must very soon entail hiring additional personnel and acquiring equipment for tasks such as
 - ▶ *Surface preparation and clean rooms*
 - ▶ *RF testing at low temperatures*
 - ▶ *Ancillary equipment III (HOM coupler validation on cold cavity)*
 - ▶ *Ancillary equipment IV (Inspection equipment for on-line and post mortem analysis)*
- ▶ *With these two conditions satisfied we have a realistic chance to assemble and test the fully equipped SPL cryomodule in the first half of 2012.*