



---

# New plans for high power RF tests places at CERN

---

O. Brunner BE/RF/KS – January '10

---

# Scope of the presentation / framework

- ❑ A word on the RF/KS section
  - ❑ Existing infrastructures
  - ❑ Actual activities
  
  - ❑ Upcoming activities
  - ❑ What is the best we can do (I believe) to take over these activities, and where?
-

# RF /KS activities

- ❑ LHC RF system operation
- ❑ RF power
  - ❑ LHC
  - ❑ Linac4
  - ❑ CLIC&CTF3
  - ❑ Crab cavities in SPS
  - ❑ LEP RF equipment for external requests
  - ❑ SPL test stand
- ❑ SC cavities & “clean room assembly”
  - ❑ LHC (3 spare cavities to be built soon)
  - ❑ HIE Isolde
  - ❑ SPL (WW’s activities)
  - ❑ CLIC & CTF3 structures

- ❑ 6 Engineers
- ❑ 5 Technicians
- ❑ 1 Fellows (Linac 4 -1/12/09) + 1 Fellow ( $\frac{1}{2}$  SPL,  $\frac{1}{2}$  HIE Isolde)

# A5 – high voltage test facility



Equipment:  
-100kV – 15mA test station  
-overhead cranes  
-mechanical workshop



## Activities:


-mechanics  
-HV controls  
-HV tests (low power)

## -LHC HV RF


modulators  
HV switches  
HV cables  
thyratrons  
studies (repl. of tetrode)  
silicon oil comp. tests

## -Linac4 HV RF

phase shifters  
HV tanks



# B152 – 3MeV test stand, storage



**3MeV structure test place**  
-one Linac4 klystron  
-2 Hz modulator (prototype)

**Actual & Future use:**

- RFQ tests: 2011 - 2012
- No room for an additional power test place

**Storage area**  
-20 LEP klystrons  
-circulators  
-WG system


**No picture**

# B112



## LHC RF power (preparation and tests)

- klystrons, circulators, RF loads
- Main couplers
- Water cooling
- 60kV, 10A power converter



**Linac4 high power tests place??**  
...to be investigated....


## LHC & Linac 4 high power (low power tests, modification, prep)

- LEP klystrons
- WG
- Circulators & RF loads
- Chassis
- Water & air cooling systems




- Equipment from storage (klystrons, WG, circulators): B152
- A5
- External firms

# Sm18



# Sm18 – assembly of RF structures (incl. clean rooms)



Clean room assembly of RF structures (cavities, Main couplers, ...)  
-15meters class1000 and class10 clean rooms  
-"baldaquin" (clean 100)  
- Now being modified for HIE Isolde cavities

assembly of RF structures (cavities, Main couplers, ...)



## Actual activities:


- LHC cavities & modules
- LHC main couplers
- CLIC structures
- HIE Isolde cavities

## Future (new) activities:

- CTF3 structures?
- HIE Isolde cryomodule?
- SPL cavity or cryomodule?




# Sm18 – vertical test stands



Four vertical test places (4.5K, 2K)


- V3: SPL (not operational)
- V4: resonator (operational) – Tobias, W.W.
- V5: HIE Isolde (not operational)
- V6: LHC (operational) – Pierre



## **New future plans:**

- Upgrade of cryo distribution
- Upgrade V3 and V5 control system
- Construction, installation and test of HIE Isolde cryostat (who?)
- Test HIE Isolde cavities (matteo+fellow?)
- Test SPL cavities (?? + fellow?)

# Sm18 – high power tests facility



## Two bunkers:

- Bunker A: 352MHz
- Bunker B: 400MHz
- High power zone
  - 100kV, 40A modulator
  - HV bunker
  - 352MHz klystron
  - 400MHz klystron, circulator & RF loads

## Bunker B = LHC bunker

- >RF power system will not be moved
- Future Plan: host HIE Isolde modules tests?
  - Dimensions (height) to be checked
  - Control system to be built
  - Powering to be defined
  - Manpower required...



# Sm18 – high power zone modification

SPL klystron (linac4?)

## Actual equipment of Bunker A


- LEP klystron + circulator +WG
- CW operation (max 230kW)

Actual use:

- Linac4 RF structure tests

Extension of RF zone to be requested for SPL:

- Bunker
- HV (50Hz modulator)



Advantages:

- Cryo
- Re-use existing infrastructure (water cooling, bunker, etc)

To be studied:

- Linac 4 High Power test place in B112?
- Extension of the RF zone in SM18

# conclusions

- Several activities in parallel → priorities can change
- B112 would be, a good place to host the Linac4 high power equipment (providing it can be installed there!)
  - Requires minimum hardware modification
  - Makes best share of the existing infrastructure
- Would leave the possibility to install a dedicated high power RF test place in SM18 for SPL
  - Requires extending the existing RF zone
    - Bunker
    - High power zone
- To do list:
  - Feasibility study of the Linac 4 test place in B112
    - Will be installed in SM18 if not possible (also to be studied)
  - Detailed integration of the modification required in SM18 for the SPL high power tests (+Linac4 evt.)
    - 50Hz modulator footprint
    - Modulator – klystron cabling & max distance
    - Circulator, RF load, WG system
    - Control system
    - Extension of bunker
- Request for additional space