

Movable Helium Cryoplant for Crab Cavities testing at SPS BA6

Laurent Delprat
CERN, Geneva, Switzerland



With contribution from K. Brodzinski, S. Claudet, H. Derking

Research supported by the High Luminosity LHC project

laurent.delprat@cern.ch

OUTLOOK

- Introduction to High-Luminosity LHC project – HL-LHC
- Design principles and key features
- Timeline of procurement and installation
- Commissioning and operation
- Conclusions and perspectives



Introduction

- Goal of peak luminosity above $5.0 \cdot 10^{34} \text{ cm}^{-2} \cdot \text{s}^{-1}$
- Replacing the matching sections on both sides of ATLAS and CMS experiments
- New focusing quadrupoles
- Use of superconducting crab cavities



**Need for a new cryogenic infrastructure
for a superconducting RF test facility with proton beams
at CERN SPS accelerator**

Design principles and key features



Design principles and key features

Legend:


VB1 – valve box 1

VB2 – valve box 2

SB – service box

CCM – crab cavity module

Surface premises
& infrastructure



Design principles and key features

Movable helium cryoplant @ 4.5 K

- 4 major **constraints**: timeframe of the supply, guarantee of the required performances, accessibility of installation location, **movability** requirement
- **Liquefaction mode: 7 g/s of LHe @ 4.5 K + 750 W shielding @ 50 – 80 K**
- **Refrigeration mode: 700 W @ 4.5 K + 300 W shielding @ 50 – 80 K**
- **LN₂ precooling** in both modes
- **LR280** from Linde Kryotechnik AG® with liquefaction and refrigeration turbines




Cryogenic distribution system

- **2 valve boxes** – VB1 as interface to the cold box, VB2 to the Service Box
- **Sub-cooler in VB1 phase separator** to recondition supercritical helium supply stream
- **80 m long distribution line (TL)**: supercritical He for the supply and thermal shielding to minimize the losses
- Liquid helium produced at VB2 then sent to the Service Box



Service Box


- Main function: provide **adapted interfaces** between 4.5 K distribution, client cryostat and helium pumping system
- **Integrated subcooling heat exchanger** for supply helium stream precooling



Design principles and key features

Crab cavities cryomodule

- 4.5 K LHe sat and 2 K – 30 mbar abs operation
- 18 W (static) and expected 13 W (dynamic) @ 2 K
- **Integration in SPS** (same proton beams as in LHC)
- **Mobile platform to bypass it** when SPS serves as LHC injector




Helium pumping system



- Water bath heater, installed power 10 kW
- 2 Roots pumping units, total 2.3 g/s at 20 mbar abs




Simplified flow diagram



Design of the 4.5 K cryoplant



Principle of 2 K cooling system of the cavity




2 K operation:

- Saturated superfluid helium bath
- Integrated subcooling heat exchanger
- Water bath heater – installed power of 10 kW
- Helium pumping system – 2.3 g/s at 20 mbar abs

Integration requirement:

- Possibility to bypass the test cryostat when SPS serves as the LHC injector
=> installation on a mobile platform
=> use of specially designed beam vacuum « Y » chamber connected to the cryomodule and its bypass



Timeline of procurement

Package	Phase	2016				2017				2018				2019				2020				
		Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	
Infrastructure (warm piping / GHe / LN2)	Studies & Requirements	[Grey bar]																				
	Tendering	[Grey bar]																				
	Engineering & Fabrication																					
	Installation																					
	Comissioning																					
	Operation																					
	Consolidation																					
Movable helium cryoplant	Studies & Requirements	[Grey bar]																				
	Tendering																					
	Engineering & Fabrication																					
	Installation																					
	Comissioning																					
	Operation																					
	Consolidation																					
Cryogenic distribution	Studies & Requirements	[Grey bar]																				
	Tendering																					
	Engineering & Fabrication																					
	Installation																					
	Comissioning																					
	Operation																					
	Consolidation																					
2 K cryogenic sub-system	Studies & Requirements	[Grey bar]																				
	Tendering																					
	Engineering & Fabrication																					
	Installation																					
	Comissioning																					
	Operation																					
	Consolidation																					

2016: studies and procurements launched


2017: detailed engineering & fabrication

2018: commissioning and operation

LONG
SHUT-
DOWN
2



Commissioning and operation



Conclusions and perspectives

- The complete 2 K cryogenic infrastructure was **designed and built from scratch between 2016 and beginning of 2018**,
- The **reception test** was conducted **during Q1 of 2018** with direct operation afterwards,
- **First stable operation** of crab cavities in LHe successful in **spring 2018**, in superfluid helium from September 2018,
- **Long Shutdown #2** started with the stop of the cryogenic test facility, allowing for the required maintenance and consolidation,
- **Restart** of the whole facility **in 2020** to allow for completing performance assessment and further testing of the cavities with proton beams in SPS

Thank you for your attention !



www.cern.ch



GHe and LN2



Compressor station



Cold Box and LN₂ phase separator



CB, LN₂ ϕ -sep, VB1



VB1



Transfer line




VB2



Service Box



Crab cavities cryomodule



VB2, SB, CM

