

Research supported by the High Luminosity LHC project

With contribution from K. Brodzinski, S. Claudet, H. Derking

laurent.delprat@cern.ch

OUTLOOK


- Introduction to High-Luminosity LHC project – HL-LHC
- Design principles and key features
- Timeline of procurement and installation
- Commissioning and operation
- Conclusions and perspectives

Introduction to the High-Luminosity LHC Project

Towards higher collision rates

New discoveries or precision measurements need integrated luminosity !!!

$$\text{Luminosity} = f * N^2 / 4\pi \sigma^2$$




The most straight forward action: reducing beam size with a “local action”

To increase Luminosity

$(S\sigma_x, S\sigma_y, S\sigma_z)$ envelope for $\epsilon_x = 5.02646 \times 10^{-10}$ m, $\epsilon_y = 5.02646 \times 10^{-10}$ m, $\sigma_z = 0.000111$


LHC has better aperture
than anticipated: now all
margin can be used;
however is not possible to
have $\beta^* < 40$ cm



Smaller $\beta^* \Rightarrow$ larger IT aperture
With stronger gradients

Effect of the crab cavities

To compensate for the larger crossing angle



- RF crab cavity deflects head and tail in opposite direction so that collision is effectively “head on” and then luminosity is maximized
- *Crab cavity maximizes the lumi and can be used also for luminosity levelling: if the lumi is too high, initially you don't use it, so lumi is reduced by the geometrical factor. Then they are slowly turned on to compensate the proton burning*



Our need for cryogenics

- Use of superconducting crab cavities
- Operating in superfluid helium



**Need for a new cryogenic infrastructure
for a superconducting RF test facility with proton beams
at CERN SPS accelerator**

Design principles and key features



Layout

Legend:


VB1 – valve box 1

VB2 – valve box 2


SB – service box

CCM – crab cavity module

Surface premises
& infrastructure



Simplified flow diagram



Design principles and key features

Movable helium cryoplant @ 4.5 K

- 4 major **constraints**: timeframe of the supply, guarantee of the required performances, accessibility of installation location, **movability** requirement
- **Liquefaction mode: 7 g/s of LHe @ 4.5 K + 750 W shielding @ 50 – 80 K**
- **Refrigeration mode: 700 W @ 4.5 K + 300 W shielding @ 50 – 80 K**
- **LN₂ precooling** in both modes
- **LR280** from Linde Kryotechnik AG® with liquefaction and refrigeration turbines




Cryogenic distribution system

- **2 valve boxes** – VB1 as interface to the cold box, VB2 to the Service Box
- **Sub-cooler in VB1 phase separator** to recondition supercritical helium supply stream
- **80 m long distribution line (TL)**: supercritical He for the supply and thermal shielding to minimize the losses
- Liquid helium produced at VB2 then sent to the Service Box



Service Box


- Main function: provide **adapted interfaces** between 4.5 K distribution, client cryostat and helium pumping system
- **Integrated subcooling heat exchanger** for supply helium stream precooling



Design principles and key features

Crab cavities cryomodule

- 4.5 K LHe sat and 2 K – 30 mbar abs operation
- 18 W (static) and expected 13 W (dynamic) @ 2 K
- **Integration in SPS** (same proton beams as in LHC)
- **Mobile platform to bypass it** when SPS serves as LHC injector



Helium pumping system

- Water bath heater, installed power 10 kW
- 2 Roots pumping units, total 2.3 g/s at 20 mbar abs



First operational results of the cryoplant



Timeframe of the supply:



2-year-project started from scratch – deadline met for delivery, installation and commissioning in time with the final user need (the crab cavities cryomodule)



Guarantee of the required performances:



Liquefaction capacity already assessed up to 60% of the design, in line with water cooling restriction at the time of the performance test done in December 2018 – to be completed in 2020 after restart but already good hope to match the specified values



Refrigeration capacity will be evaluated as well in 2020 after restart of the whole facility



Accessibility of installation location:



90° tilting capability of the cold box, specific handling of the heat exchangers inside the vacuum vessel



Movability requirement:



2 iso-frame skids design for the compressor station



Special transportation frame for the cold box with wheels and drawbar





Interfaces regrouped in one single location per skid



Installed the two CP skids + the cold box in less than a week

Design of the 4.5 K cryoplant



GHe and LN₂

GHe storage

Handled by CERN – not in the scope of supply of the compressor station
2 * 35 m³, up to 15 bar abs



LN₂ facility

Handled by CERN – not in the scope of supply of the cold box
1*20 kL Dewar LN₂ for cold box precooling



Compressor station



Cold Box and LN₂ phase separator



CB, LN₂ ϕ -sep, VB1



Timeline of procurement

Package	Phase	2016				2017				2018				2019				2020				
		Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	
Infrastructure (warm piping / GHe / LN2)	Studies & Requirements	[Grey bar]																				
	Tendering	[Grey bar]																				
	Engineering & Fabrication			[Yellow]	[Yellow]	[Yellow]																
	Installation					[Brown]					[Brown]											
	Commissioning					[Green]					[Green]											
	Operation											[Blue]	[Blue]	[Blue]							[Blue]	[Blue]
	Consolidation												[Red]								[Blue]	[Blue]
Movable helium cryoplant	Studies & Requirements	[Grey bar]																				
	Tendering		[Blue]	[Blue]																		
	Engineering & Fabrication				[Yellow]	[Yellow]	[Yellow]	[Yellow]	[Yellow]													
	Installation										[Brown]											
	Commissioning										[Green]											
	Operation											[Blue]	[Blue]	[Blue]							[Blue]	[Blue]
	Consolidation																				[Blue]	[Blue]
Cryogenic distribution	Studies & Requirements	[Grey bar]																				
	Tendering		[Blue]	[Blue]																		
	Engineering & Fabrication		[Yellow]	[Yellow]	[Yellow]	[Yellow]	[Yellow]	[Yellow]	[Yellow]													
	Installation					[Brown]	[Brown]	[Brown]	[Brown]		[Brown]	[Brown]										
	Commissioning										[Green]											
	Operation											[Blue]	[Blue]	[Blue]							[Blue]	[Blue]
	Consolidation																[Red]				[Blue]	[Blue]
2 K cryogenic sub-system	Studies & Requirements	[Grey bar]																				
	Tendering		[Blue]	[Blue]																		
	Engineering & Fabrication				[Yellow]	[Yellow]	[Yellow]	[Yellow]	[Yellow]													
	Installation										[Brown]	[Brown]										
	Commissioning										[Green]	[Green]										
	Operation											[Blue]	[Blue]	[Blue]							[Blue]	[Blue]
	Consolidation																				[Blue]	[Blue]

2016: studies and procurements launched

2017: detailed engineering & fabrication


2018: commissioning and operation

LONG
SHUT-
DOWN


2




Commissioning / Operation at 4.5 K then 2 K



First tilting of the proton beam by a Crab Cavity! SPS 23 May 2018 at 1 MV (3.4 MV nominal)




Crabbing Voltage from Head-Tail Monitor
2018-05-30 14:14:46



10 slots of SPS
Machine
Development
foreseen in
2018

Crabbing Voltage from Head-Tail Monitor
2018-05-30 15:01:23



Conclusions and perspectives

- The complete 2 K cryogenic infrastructure was **designed and built from scratch between 2016 and beginning of 2018**,
- The **reception test** was conducted **during Q1 of 2018** with direct operation afterwards,
- **First stable operation** of crab cavities in LHe successful in **spring 2018**, in superfluid helium from September 2018,
- **Long Shutdown #2** started with the stop of the cryogenic test facility, allowing for the required maintenance and consolidation,
- **Restart** of the whole facility **in 2020** to allow for completing performance assessment and further testing of the cavities with proton beams in SPS

Thank you for your attention !



www.cern.ch



Spare Slides

VB1




Transfer line




VB2




Service Box



Crab cavities cryomodule




Cryomodule internal 3D preview



HOM
Se
Cold
Cryop
BI




VB2, SB, CM



LHC performance so far

Peak Luminosity


“The potential of the facility”



Performance

Integrated Luminosity


“What allows science” (statistics)



Time - Qualification
availability

Global

Principle of 2 K cooling system of the cavity



2 K operation:

- Saturated superfluid helium bath
- Integrated subcooling heat exchanger
- Water bath heater – installed power of 10 kW
- Helium pumping system – 2.3 g/s at 20 mbar abs

Integration requirement:

- Possibility to bypass the test cryostat when SPS serves as the LHC injector
=> installation on a mobile platform
=> use of specially designed beam vacuum « Y » chamber connected to the cryomodule and its bypass

