

Cybersecurity in the Cherenkov Telescope Array

<u>I. Oya</u> CTA Observatory

Introduction



- Disclaimer:
 - I am a SW team coordinator and not a security expert
 - CTA organization is being set up:
 - No security governance
 - System configuration not fully defined
- Goal: Present CTA project and some of its challenges in terms of security

The Cherenkov Telescope Array


- Consortium
 - Largest Cherenkov Telescope Installation ever built -Starting construction now
 - 100+ telescopes, 3 types
 - Many different technologies
 - Expected to produce ~ 5 Petabyte every year, to be archived in mainland
 - CTA Observatory supported by a the CTA


Cybersecurity in CTA


CTA Sites



CTA at Paranal & La Palma

















5

CTA at Paranal & La Palma



CTAO Legal Entity




- CTA Observatory gGmbH (2014) responsible of CTA implementation:
 - CTAO Staff: 30 persons (Jan 2019) Expect to arrive to ~80 staff
- The final legal entity for full construction, a *European Research Infrastructure Consortium* (ERIC), is being set up under European Union law (2020?)
- ~70% Construction based on IKCs to the CTA ERIC

The CTA consortium (CTAC)





CTAO OPERATIONS



Initial calib./reduction \rightarrow Transmission from site \rightarrow Bulk data archive \rightarrow Science data archive

Main CTA Systems



Science Operations

- Array Control and Data Acquisition (ACADA)
- Data Processing and Preservation System (DPPS)
- Science User Support System (SUSS)
- Science Operations Support System (SOSS)

Technical Infrastructure

- Telescope (TEL) [*]
- Safety System
- Auxiliary Instruments (AUX)
- Array Infrastructure Elements (AIE)

[*] 1 to N telescope systems, several types


Observatory Operations and Administration

- Technical Operations Support System (TOSS)
- Management and Administrative System (MAS)



Data

Science Data Archive Users (Scientists)









Main CTA Systems



Jtions and

SCADA **Science Operations**

- Array Control and Data Acquisition (ACADA)
- Data Processing and Preservation System (DPPS)
- Science User Support System (SUSS)
- Science Operations Support System (SOSS)

Technical Infrastructur, Device Control System

Control Systems

- Safety System
- Auxiliary Instruments (AUX)

Array Infrastructure Elements (AIE)


[*] 1 to N telescope systems, several types

Device Control System **Technical Operations Support** System (TOSS)

> Management and Administrative System (MAS)













11

CTA Project – Cybersecurity status



Main Issues


- There is no Cybersecurity concept in the project
- There is no person who feels responsible of cybersecurity at the level of organization
- System configuration & inventory of assets not yet defined

In place:

- Collaborating data centers (in mainland) have each their own wellstablished policies
- CTA-N IT Container delivered by Fujitsu, consultancy by DESY IT experts
- CTA observatory sites (ESO, IAC) with own policies

CTA Elements






Control systems- Specific issues



- Vulnerabilities in our control software could create safety risks
 - E.g. point the mirrors to burn the bushes
- Technology choices taken without considering security at all
 - Often chosen by the IKCs "bottom-up"
- Standardization on the way, but not consolidated
 - OPC UA proposed but not fully accepted yet
 - Many runtime environment: various PLCs, NI boxes, RPis, Arduinos, Xbee...., custom
- Inventory of computing equipment or technologies not yet existing
- Remote location expectations of remote operations incl. control systems
- During constructions: simultaneous deployment of various IKC teams, contractors, staff

Concept & Design for CTA On-Site ICT Infrastructure





Cybersecurity in CTA | I. Oya

Expected technologies on the sites (I)



Technologies not 100% consolidated

- Computer cluster with Red Had / CentOS
- Ethernet cable network with fibre, copper and InfiniBand
- Wireless access points around telescopes
- Siemens, Bosch-Rexroth, Beckoff, Panasonic, NI PLCs.
- Embedded machines:
 - Raspberry Pi
 - Arduino
 - NI Boxes
 - Compact desktop machines
 - ...
- Onboard Ethernet & wireless devices:
 - CCD Cameras
 - mirror actuators
 - calibration light sources
 - ...
- White rabbit for time sync + GPS clocks

Expected technologies on the sites (II)



- Java, C/C++, Python, JavaScript
- OPC UA (various vendors and embedded in PLC) •
- Alma Common Software (CORBA-based framework)
- ZeroMQ
- Low-level: UDP, TCP/IP sockets, raw Ethernet...
- Technologies not 200% consolidated Condition monitoring software boxes with "whatever-comes-inside". •
- Containers: singularity, docker
- VMs: Virtualbox, Vagrant •
- JavaScript-based user interface •
- Control rooms at each site
 - One at the site (100s m)
 - At low elevation (~40 km away)

1st internal workshop on CTA Cybersecurity

- Focused on control systems & on-site
- External consultants from GTD
- Experts from DESY Zeuthen, CTA Personnel, S. Lueders (CERN)
- Went over the project situation, analysed using NIST framework
 - Recommendations by GTD



Main action items




- Set-up cybersecurity Governance and roles
 - Planning to announce a CISO position
- Establish associated processes at each location: HQ, SDMC, CTA-N, CTA-S
- Build an asset Inventory. This will help us to organize
 - Consolidate technologies
 - Patch management
 - Malware protection
 - System hardening
- Architecture
 - network segregation and segmentation
- Prepare an A&A system
 - Aim for multi-factor Authentication
- Set up logging and monitoring
- IT/OT Dependency analysis
- Organize vulnerability scans and pentesting
- Awareness training program




BACKUP


Cybersecurity in CTA | I. Oya




The CTA System Structure




The CTA System Structure





Data Flow – From the Cameras to the User




Computer clusters at mainland

la

Concept & Design for CTA On-Site ICT Infrastructure - Scope







Concept Design for CTA On-Site ICT Infrastructure, 2018. 01/a

Currently at La Palma – Not yet accepted by CTAO






- Currently owned by a Telescope team, planned to be transferred to the CTAO
- It contains:
 - Control system of the 1st telescope
 - Some ACADA prototypes
 - Analysis prototypes



Telescope decomposition





Notes:

.

- Approximate decomposition, slightly differences in different telescope types
- Some auxiliary systems ٠ similar, others more simple