

# Cryomodule design, assembly and installation utilizing “KOACH” system




Kazunari Yamada

RIKEN Nishina Center

# Superconducting Riken Linear Accelerator (SRILAC)

- Superconducting booster linac of existing room-temperature linac
- Just commissioned in Jan. 2020
- 10 SC-QWRs stored in 3 cryomodules (CM1~3), arranged into groups of 4, 4, 2 units
- $f_0 = 73.0$  MHz,  $\beta_{opt} = 0.078$ , 4.5 K operation
- Energy: 3.6 MeV/u to 6.5 MeV/u for heavy-ions with  $m/q = 5$
- Focusing elements: RT quadrupoles




# Design of SRILAC cryomodule

- 3-piece vacuum vessel (upper vessel, center vessel, lower vessel)
- Compatible with high pressure gas safety act in Japan
- Stacking structure on base plate
- CM3 is the half type of CM1 and CM2



Design parameter of SRILAC cryomodule

Operating temperature	4.5 K
Operating pressure	0.126 MPaA
Number of cavities	4 or 2
Length (between GVs)	2200 or 1340 mm
Width	1060 mm
Total height with pedestal	3907 mm (Incl. valves)
Cold focusing element	None
Material for vessel	Carbon steel with electroless nickel plating
Local magnetic shield	Permalloy 1.5 mm (Inside the He jacket)
Thermal shield temperature	80 K (LN <sub>2</sub> cooling)
Static heat load	18 or 10 W to 4.5 K
Platform	Base plate
Cavity vacuum pump	IP + NEG(ZAO)
Insulation vacuum pump	TMP



# Components of cryomodule

- Thermal sensors (/CM): 12 CERNOX, 21 Pt-Co, 21 Pt100  
6 CERNOX, 10 Pt-Co, 15 Pt100
- Residual magnetic field inside the vessel: 10~14  $\mu\text{T}$



Upper vessel



Top plate



Base plate



Lower vessel and thermal shield of CM3

# Assembly procedure of cryomodule


- a) Mounting SC-QWRs on base plate
- b) Connecting bellows between QWRs
- c) Attaching beam pipes, GVs, and vacuum exhaust
- d) Assembling tuners, lower cryo pipings, and thermal sensors
- e) Mounting top assembly on cryomodule, piping, leak test, inspection, assembling thermal shield, thermal anchors, and SIs
- f) Attaching instrumentation, upper thermal shield, upper vessel, and safety elements

Assembling work was performed in each place

- ISO class 8 semi-clean room for a), d), e)

- ISO class 1 super clean room built in the semi-clean room (KOKEN Floor KOACH) for b), c)

- Installation site (very dirty) for f)




# KOKEN KOACH clean system

We introduced KOACH clean system for assembling work.

<https://www.koken-ltd.co.jp/english/product/clean/super/>

- ISO class 1 super clean environment
- High coherent side laminar flow (wind speed: 0.3~0.5 m/s)
- Short clean-up time
- Short construction period (~ 1 week) for clean room type
- Reasonable price
- Low running cost


## Room type for cryomodule assembly



KOACH F1050-F (Floor KOACH) + guide screen

Clean area: W1050 mm × H850 mm/one module  
< L20,000 mm

## Open zone type for connection in situ



KOACH C900-F (Stand KOACH)

Clean area: W900 mm × H700 mm × L1800~2300 mm

## Open tabletop type for VT connection




KOACH T500-F (Table KOACH)

Clean area: W496 mm × H310 mm × L700 mm

# Super clean room in RIKEN

- ISO class 1 super clean room built in ISO class 8 semi-clean room
- 4 × 3 arranged Floor KOACH



## Inspection record

清浄度検査記録表  
検査実施日 2017年 11月 16日  
実施者 和田 直也

納入装置名: KOACH Ez-F 3段×4列×12m

測定器	パーティクルカウンター-Lasair II-110(スペクトリス社製)			床面積: 52m <sup>2</sup>
測定器シリアル	NO.81008 NO.89025 NO.89210			
測定方法	クリーンルームの空気清浄度の評価方法(JIS B 9920)に準拠			
測定条件	測定点数	11点		
	対象粒径	0.1 μm以上		
判定基準	吸引流量	28.3L/min		
	清浄度がISOクラス1であること (すべての点が10個/m <sup>3</sup> 以下であること)			

測定点	結果(個/m <sup>3</sup> )	測定点	結果(個/m <sup>3</sup> )	測定点	結果(個/m <sup>3</sup> )	(個/m <sup>3</sup> )	
①	0	⑤	0	⑨	0		4.37 × 10 <sup>5</sup>
②	0	⑥	0	⑩	0		
③	0	⑦	1	⑪	0		
④	0	⑧	0				
総合判定		合格					



Rs: >18 MΩ·cm  
0.2 μm Particle: < 1/ml  
TOC: ~2 ppb

# Assembly and installation of cryomodule

Preparation of SC-QWR



Before connection



After vacuum connection



Assembly in semi-clean room



Transport to installation site



ISO class 1



ISO class 8



Installation site



Installation



After alignment






# Connection work in situ

One side of Stand KOACH was used with local antistatic-vinyl enclosure.



Connection of vacuum pump assembly



Connection between CM1 and CM2







Connection between differential pumping system and CM1



# Result of rf excitation test

- Successfully cooled down without any cold leak (Sep. 2019)
- Vacuum leakage from the FPC window (SC05) as reported by K. Ozeki, Feb. 04, WG2
- 9 SC-QWRs were excited with rf and X-ray emission was measured at each voltage from Dec. 2019
- Assembly order of cryomodule: CM2, CM3, CM1 (Gate valves have never been opened at this time)



- Last one (CM1) has the best performance → gained experience??
- Cavity with evacuation port seems to be dirty? (SC02) → contaminated during slow leak
- Performance of KOACH clean system is sufficient
- Further improvement of working procedure is required

# Summary



- 3 cryomodules were assembled and installed by utilizing KOACH clean system
- The first cooling down was successfully performed without any cold leak in Sep. 2019
- 9 SC-QWRs were excited with rf and X-ray emission was measured at each voltage from Dec. 2019
- Performance of KOACH clean system is sufficient
  
- First beam acceleration has successfully commissioned in Jan. 28, 2020 with 40Ar beam up to  $E = 6.2$  MeV/u
  
- We will investigate the effect of opening the gate valves and beam acceleration

## **Collaborators**

O. Kamigaito, K. Ozeki, N. Sakamoto, K. Suda  
**RIKEN Nishina Center**

E. Kako, H. Nakai, K. Umemori  
**KEK**

H. Hara, A. Miyamoto, K. Sennyu, T. Yanagisawa  
**Mitsubishi Heavy Industries Machinery Systems, Ltd.**