




Beam Dump Facility

including TauFV and PASSAT extensions

Y. Dutheil, on behalf of the BDF working group



Content

- Overview
 - Beam production from the SPS
 - Beam transfer
 - Target & target complex
 - Experimental hall
 - Radiation protection & environmental studies
 - Safety engineering & integration
 - Civil engineering
- TauFV experiment
- PASSAT experiment
- Costing & roadmap
- Conclusion


Overview

- The project integrates in the North Area complex
- Builds upon existing CERN expertise for high energy and high-power beam production and delivery
- Shorter than existing North Area experimental lines but challenging goals




Overview

- New beam transfer tunnels and buildings are required
- Branches off existing North Area extraction line
- Ensures concurrent operation with the existing North Area experiments
- Large detector hall initially to host the SHiP experiment (see last [SHiP Collaboration Meeting, 5-6 November 2019](#) [link](#))




Beam production



* Measured ~30h after shutdown at ~1 m from beam line, peak at ZS plotted.

- Existing North Area beam delivery performances
 - 400 GeV/c proton beam produced using slow extraction
 - 4.8 s uniform spill with up to 3.5×10^{13} protons/spill and 1.23×10^{19} protons extracted in 2018
- SHiP requirements
 - 1 s uniform spill with up to 4×10^{13} protons/spill and $\sim 4 \times 10^{19}$ protons extracted per year
- Challenges
 - SHiP + current NA requirements totals $\sim 5 \times 10^{19}$ protons extracted per year
 - Radiation & activation in the SPS extraction devices is proportional to the number of protons extracted
 - The BDF requires an increase in the slow extraction efficiency to maintain radiation and activation at current levels


Radiation reduction



Multiple groups and fields involved



Loss reduction efforts highlight

- Detailed LSS2 geometry and material inventory implemented in FLUKA with MADX-*pycollimate* source term:
 - To evaluate energy deposition maps and induced radioactivation
 - Benchmark with beam experiments and measurements
- Phase space folding
 - Use of octupole magnets to fold the extracted beam phase space and reduce the beam density at the ZS
 - Make use of Constant Optics Slow Extraction (COSE) to maintain the shape of the extracted beam during the spill




Loss reduction efforts highlight

- Diffuser upstream the extraction region
 - Incoherent scattering of particles to reduce the beam density where particles would be lost on the ZS
 - Prototype installed in 2018
 - Loss gain of ~15% in very good agreement with simulated behavior




- Crystal upstream the extraction region
 - Coherent scattering on the crystalline structure of a bent crystal
 - High efficiency and strong loss reduction
 - Prototype developed with UA9 installed in 2018
 - Loss gain of 20% in volume reflection regime and ~40% in channeling regime



Beam production


- Parallel work on several aspects of the slow extraction process to increase efficiency
 - Smart & automatic alignment of the electrostatic septa (ZSs)
 - Comprehensive FLUKA modeling of the extraction region and comparison with measured radiation/activation levels
 - New control of the SPS beam dynamics during the spill (COSE)
 - Passive and coherent scattering of the beam upstream of the ZSs
 - Horizontal phase space folding to reduce beam density at the ZSs
 - New equipment materials to reduce losses and activation
- Efficiency gain of a factor 3-4 demonstrated during on November 1st 2018
- Next steps
 - Beam tests preparations in 2020 to demonstrate slow extraction efficiency gain for continuous operation
 - New LSS4 system for an optimised crystal shadowing
 - Upgraded beam loss monitoring in the extraction region
 - Improved design of ZS with new tank and anode material




Beam transfer

- New beamline branches off the existing TT20 line
 - New optics and powering scheme using the existing capabilities of the TT20 lines
 - Use of existing magnets available in CERN stores, almost 300 tons in total
 - Accounting for failure and accidental scenario to safely transport the beam
 - Dilution system to reduce material stress on the target
- New splitter design to shift the beam direction between the regular NA and BDF lines in consecutive cycles
 - Design is constrained by manufacturing capabilities
 - New splitting schemes are being investigated to reach higher efficiencies by building upon the slow extraction expertise of CERN
- Next steps
 - Detailed risk analysis and failure cases
 - Design of splitter and possibly improved splitting scheme

Possible beam dilution patterns



Splitter model



Transfer line design

- Integration studies



- Combines requirements from all sources, sometimes conflicting
- In particular safety, transport, beam dynamics, radiation protection, civil engineering and cooling-ventilation

- Status

- Comprehensive 3D model includes all requirements for the tunnel and associated surface buildings

- Next steps

- Layout consolidation, advance from layout towards TDR
- Integration, optimization at logistics & hardware for beam-lines and services



Target

- Requirements




- Target has to safely absorb the 400 GeV/c SPS proton beams
- High beam power on the target of up to 2.56 MW during the 1s spill and 320 kW on average

- Challenges

- High-Z material resilience to high flow of cooling water
- Target block cladding behaviour under thermo-mechanical stress
- Integrated design of target assembly for fully remote handling

- Next steps

- Continuing unirradiated materials studies on Ta2.5W, zircalloy, etc...
- R&D on target block cladding



TZM: 0.08% titanium – 0.05% zirconium – molybdenum alloy

Target prototype

• Requirements


- Reproduce experimentally the thermo-mechanical conditions of the final target
- Cross-check the Finite Element Model simulations performed
- Test target online instrumentation resilience
- Perform detailed post-irradiation experiments

• Status

- Beam tests in Fall 2018 with a total of 2.4×10^{16} protons target
- Overall good agreement between online measurements simulations

• Next steps

- Target dismantling preparation
- Post irradiation experiment to characterise target blocks condition and integrity



Target Complex

- Requirements



- Heavy shielding and complex Helium passivation system
- Comprehensive FLUKA modelling
- Account for all possible accident scenario at the design stage

- Status

- Civil engineering and integration designs of the target building with support system such as cooling and ventilation

- Next steps

- Crane remote target handling concept development
- Ramping up studies toward TDR
- Helium passivation prototype for TDR



Experimental complex

• Requirements



- SHiP experiment is ~120 m long
- Comprehensive FLUKA simulations
- Inputs from civil engineering, transport and handling, electrical network system, power converters, cooling and ventilation, survey, radioprotection, safety, fire system, and access system
- Account for assembling, installation, and operation of the detector

• Status

- Preliminary integration layout of the buildings and infrastructure based on the SHiP requirements (details can be found in EDMS 2032322 - [link](#))

• Next steps


- In depth study of the detector assembly and installation sequence and layout consolidation




Radiation protection & environment

- Radiation protection
 - Critical involvement for every aspects of the BDF project
 - Guiding of building and system designs using comprehensive FLUKA studies
 - Tritium out-diffusion experiments at the target prototype
- Environmental impacts
 - Needed to ensure strict respect of legislations
 - Water and soil activation around the target complex and experimental hall
- Next steps
 - Finish H-3 out-diffusion experiments
 - Continued studies towards TDR
 - Preparation of host states legal approval


Prompt dose rates in Target Complex



BDF reference groups




Muon dose rate at CERN fence $[\mu\text{Sv/y}]$



Safety engineering & integration

- Involved in all the aspects of the project
- Safety engineering
 - Identify hazards and optimise design
 - Fire safety, compartmentalisation and intervention
 - All risks physical, chemical, environmental, etc...
- Integration
 - Compiles all the requirements and builds a comprehensive 3D model of the whole project
 - Critical at the design stage for all the groups, from beam dynamics to civil engineering



Civil engineering

- Requirements



- New beam transfer tunnel, target complex and experimental hall
- Near existing lines and building
- Open existing TDC2 tunnel to branch off the TT20 line

- Status

- Comprehensive construction plan, reviewed by an external company
- Soil activation measurements done in 2018


- Next steps

- Consider more granular look at installation and what is included to ensure nothing is overlooked
- Detailed review and optimisation required following discussion of best way forward
- Ground investigations in the area



TauFV experiment

- Strong physics case (see <https://indico.cern.ch/event/755856/contributions/3263687/>)
- Possible addon with minimum modification of the BDF project
- Requirements
 - Interception of ~2% of the beam delivered to the BDF target
 - Beam transverse RMS profile of >4 mm in one plane and <1 mm in the other
 - Space for detector of around 7.5 m long by 3 m wide
- Potential siting identified ~100 m upstream the BDF target requiring minor modification of the layout and a single additional quadrupole



TauFV experiment

- Target system



- 5 tungsten blades of $40 \times 2 \times 0.4 \text{ mm}^2$
- Cooled by the circulation of Helium
- Target maximum temperature and mechanical stress well below material limits

- Radiation aspects

- Full FLUKA model of the target, detector and shielding
- Prompt and activation losses require careful design of shielding


- Next steps

- Shielding of radiation optimisation
- Detailed study of the target configuration including installation handling concepts for a realistic assembly and operation plan
- Integration with the BDF 3D drawings



PASSAT experiment

- Particle Accelerator helioScopes for Slim Axion-like-particle deTection (PASSAT):
 - Utilizing the principle of the axion helioscope but replaces ALPs produced in the Sun with those produced in a target material
 - ALP conversion in magnetic field allows probing of light (slim) ALPs, otherwise inaccessible by laboratory-based experiments which rely on ALP decay
- Potentially complements astrophysics studies with a different reach
- Physics case discussed in detail at the last SHiP collaboration meeting
<https://indico.cern.ch/event/854346/contributions/3604231/>



Cost estimates


- Developed over the last 5 years
- Now includes all the aspects of the project
 - TauFV and PASSAT extensions not included

Work package	Estimate [MCHF]
Civil engineering	68.2
Work Package 1	31.7
Work Package 2	16.5
Work Package 3	10.9
Work Package 4	7.3
Work Package 5	1.3
Site investigation	0.6
Extraction and beamline	9.6
Magnet refurbishment	0.7
Switch/Splitters	2.1
Dilution system (MDX)	0.52
Power converters	3.0
Beam instrumentation	0.8
Vacuum system	0.6
Interlocks	0.2
DC cabling	1.62

Target and target complex	45.5
Target assembly & annex equipment	5.6
Instrumentation package	0.9
Bunker iron shielding & US1010	14.0
Concrete shielding	0.85
Magnetized coil for US1010 shield	1.0
Target & coil handling system	19.1
Target and coil shielding casks	0.2
Helium vessel (HW)	2.3
Integration	0.6
Beam window(s)	0.6
Collimator(s)	0.5
Infrastructure and services	31.5
Cooling	7.4
Ventilation	6.3
Electrical distribution	5.6
Survey and alignment	1.1
Access system	1.4
Fire safety system	3.5
Radiation monitoring	0.4
Transport (inc. cranes and lifts)	5.1
Controls infrastructure	0.7
Integration and installation	3.6
Installation	2.6
Installation, design support	0.6
Preparation, dismantling	0.4
Total	158.4

Roadmap

- Continued efforts in 2019 and 2020
- Includes
 - Post Irradiation Examination (PIE) of the prototype target tested in 2018
 - Tritium tritium out-diffusion experiments
 - Helium vessel design and preparation for prototyping
 - Construction and testing of the prototype laminated switch/splitter magnet
 - Intermediate iteration of system integration
 - Development and possible prototyping of the hadron absorber magnetisation system
 - Continued studies of loss reduction techniques during slow extraction in the SPS and the deployment of these techniques onto operational beams (planned for the SPS run starting in 2021)
 - Revision of experimental area along with updated information about SHiP assembly and installation
 - Site investigation required for a definitive civil engineering study
- By 2020, strong position to seek approval to work towards a TDR for delivery by 2022



Roadmap

- Ideal timeline assumes approval to go ahead with TDR next year
- 2023 - 2024 : CE pre-construction
- 2023 - 2025 : Component production
- 2025 - 2027 : Underground CE
- 2026 - 2028 : Surface CE
- 2026 - 2028 : Installation
- Overall goal is to commence data taking as soon as early as reasonably possible in Run 4

Publication list (non exhaustive)

- BDF ,SHiP and physics cases
 - W. Bonivento et al., *Proposal to Search for Heavy Neutral Leptons at the SPS*, CERN-SPSC-2013-024/SPSC-EOI-010, 2013
 - SHiP Collaboration, M. Anelli et al., *A Facility to Search for Hidden Particles (SHiP) at the CERN SPS*, Technical Proposal, CERN-SPSC-2015-040, SPSC-P-350, 2015, [arXiv:1504.04956].
 - S. Alekhin et al., *A facility to Search for Hidden Particles at the CERN SPS: the SHiP physics case*, Rept. Prog. Phys. 79 (2016), no. 12 124201, [arXiv:1504.04855].
 - SHiP Collaboration, C. Ahdida et al., *The experimental facility for the Search for Hidden Particles at the CERN SPS SHiP Collaboration*, JINST 14 (2019) no.03, P03025.
 - C. Ahdida et al., *SPS Beam Dump Facility Comprehensive Design Study*, CERN-PBC-REPORT-2018-001, submitted for publication as CERN Yellow Report,.
- Beam production and delivery
 - H. Bartosik et al., *SPS Operation and Future Proton Sharing scenarios for the SHiP experiment at the BDF facility*, CERN-ACC-NOTE-2018-0082, 2018
 - M.A. Fraser et al., *Demonstration of slow extraction loss reduction with the application of octupoles at the CERN Super Proton Synchrotron*, submitted to Phys.Rev.Accel.Beams , 2019
 - B. Goddard et al., *Reduction of 400 GeV/c Slow Extraction Beam Loss with a Wire Diffuser at the SPS*, submitted to Phys.Rev.Accel.Beams , 2019
 - V. Kain et al., *Resonant slow extraction with constant optics for improved separatrix control at the extraction septum*, Phys.Rev.Accel.Beams 22 (2019) no.10, 101001, 2019
 - F.M. Velotti et al., *Septum shadowing by means of a bent crystal to reduce slow extraction beam loss*, Phys.Rev.Accel.Beams 22 (2019) no.9, 093502, 2019
- Prototype target, target & target complex
 - Busom Descarrega, J., Calviani, M., Hutsch, T., López Sola, E., Pérez Fontenla, A. T., Perillo Marcone, A., Sgobba, S., Weißgärber, T.. *Application of hot isostatic pressing (HIP) technology to diffusion bond refractory metals for proton beam targets and absorbers at CERN*, *Mat Design Process Comm.* 2019; 1– 11. <https://doi.org/10.1002/mdp2.101>
 - K. Kershaw et al, *Design Development for the Beam Dump Facility Target Complex at CERN 2018 JINST 13 P10011* (<https://doi.org/10.1088/1748-0221/13/10/P10011>)
 - P. Avigni et al, *Design of a Helium Passivation System for the Target Vessel of the Beam Dump Facility at CERN*, <https://arxiv.org/abs/1910.00333>, submitted to JINST
 - E. Lopez Sola et al, *Design of a high power production target for the Beam Dump Facility at CERN*, <https://arxiv.org/abs/1904.03074>, accepted by PRAB
 - E. Lopez Sola et al, *Beam impact tests of a prototype target for the Beam Dump Facility at CERN: experimental setup and preliminary analysis of the online results*, <https://arxiv.org/abs/1909.07094>, submitted to PRAB

Conclusion

- Strong effort over the past few years to perform in-depth examination of all aspects
- The studies are well advanced as evidenced by the Yellow Report CERN-PBC-REPORT-2018-001, submitted for publication
- The BDF project initially supports the SHiP experiment
 - Possible additional experiments such as TauFV & PASSAT
 - Gives access to new levels of beam power
- Many achievements over the last few years that already benefit the existing complex, such as the improvement of beam extraction efficiency
- Strong support from all CERN departments and outside collaborations
- Critical support is needed over the next few years to productively continue the studies in preparation for deployment

Thank you

