

# Status of the LHC Machine

Steve Myers

(on behalf of the LHC team)

RRB 19<sup>th</sup> April, 2010

# Topics

1. 2010 Technical Stop
2. Beam Operation March-April 2010
3. First Collisions at 7TeV cm March 30, 2010
4. Where we are “today”
5. Strategy for Performance Evolution 2010-2011

Technical Stop and Hardware  
Commissioning in  
January-February 2010

# Technical Stop

- nQPS connectors completed as schedule
- CMS repair of water cooling finished on time
  
- BUT! A few scares
  - CMS vacuum chamber
  - PS Motor generator set
  
- Hardware Commissioning finished a few days late.
  - 2 sectors late (S78 and S81): oil leak on a transformer:
  - 50 magnet quench (perverse set of conditions for nQPS)

# S12: RQF and RQD pyramids to 2kA and 5kA





Maya  
Pyramid

Timeseries Chart between 2010-02-06 00:00:00 and 2010-02-07 10:42:57 (LOCAL\_TIME)

RPHE-UA23.RQD.A12.I\_MEAS






$R_{excess} = R_{bus} - N_{splice} * R_{splice}$   show excess?



busSegmentResistanceSorted

	signalName	spliceNum	resistance	delta.Res
1	DCQDQ.12L2.R	18	5.57E-9	2.76E-10
2	DCQFQ.12L2.L	18	6.31E-9	2.81E-10
3	DCQDQ.14L2.R	8	2.38E-9	1.76E-10
4	DCQFQ.14L2.L	8	2.49E-9	1.80E-10
5	DCQDQ.16L2.R	8	2.30E-9	1.79E-10
6	DCQFQ.16L2.L	8	2.68E-9	1.89E-10
7	DCQDQ.18L2.R	8	2.84E-9	1.89E-10
8	DCQFQ.18L2.L	8	2.60E-9	1.80E-10



excess


# bins 3 40



$R_{excess} = R_{bus} - N_{splice} * R_{splice}$   show excess?

busSegmentResistanceSorted

	signalName	spliceNum	resistance	delta.Res
1	DCBB.8L2.R	2	1.06E-9	2.89E-11
2	DCBB.9L2.R	3	7.10E-10	4.50E-11
3	DCBB.10L2.R	3	9.01E-10	4.57E-11
4	DCBB.11L2.R	3	1.16E-9	4.62E-11
5	DCBB.A12L2.R	4	1.32E-9	6.36E-11
6	DCBB.B12L2.R	2	4.86E-10	4.67E-11
7	DCBB.13L2.R	3	9.42E-10	5.62E-11
8	DCBB.A14L2.R	3	9.69E-10	5.61E-11



excess

# bins 3 40

# Hardware Commissioning

- New QPS fully deployed and tested
  - Massive job, limited resources, very tight schedule
- All magnet circuits qualified for 3.5 TeV
  - Main bends and quads to 6000 A
- Outstanding problem – discovered in final stages of HWC
  - Multiple induced quenches during power off - related to power converter switch off at same time as a fast discharge
  - **new QPS** – problem solved by a change of thresholds
  - **old QPS** – problem still there
  - Solution involves delaying one of the transients – requires modification of cards in tunnel
  - Solution will be fully tested and deployed after initial beam operation
  - **di/dt of MB limited to 2 A/s in the meantime – system tested in this configuration**



Beam Operation early in 2010


# Beam milestones 2010

27 <sup>th</sup> Feb	First injection
28 <sup>th</sup> Feb	Both beams circulating
5 <sup>th</sup> March	Canonical two beam operation
8 <sup>th</sup> March	Collimation setup at 450 GeV
12 <sup>th</sup> March	Ramp to 1.18 TeV
15 <sup>th</sup> - 18 <sup>th</sup> March	Technical stop – bends good for 6 kA
19 <sup>th</sup> March	Ramp to 3.5 TeV
26 <sup>th</sup> March	Set-up for 3.5 TeV collision under ‘stable’ beam conditions in progress

# Overall Progress with Beam (1)

- **Successful ramps with beam** to 1.18 TeV.
- **Injection and capture** of both beams & **beam dump** set up for safe beam.
- **Machine tunes** adjusted and controlled to nominal values routinely.
- **Chromaticity** measured and adjusted. **Optics** verified and corrected.
- **Closed orbit** adjusted to an **rms of  $\sim 0.45$  mm** (about  $\pm 2$  mm peak to peak)  $\rightarrow$  factor 2 better than design orbit.
- **Dispersion** measured and verified (in vertical plane: **3 cm rms**).
- **Spectrometer and compensators** set up and corrected with beam.
- **Nominal separation bumps** set up and included to corrected closed orbit.
- **Golden reference orbit** defined for collimation and **machine protection**.
- **Collimation** system (all ring collimators) set up. Efficiency: **> 99.9%**.
- **Beam feedback** commissioning partially completed, still ongoing.
- **Luminosity separation knobs** tested.
- **Grazing events** to ATLAS and CMS. **Splash events** to all experiments.


# LHC Availability (Week 10)



All technical systems contribute to **very promising LHC availability!**


One golden period for availability: Saturday-Sunday 13/14 March 24h00. 100% availability

# Tune feedback



# Collimation after beam based set up

November 29, 21:55:51 - First ramp to 1.18 TeV - Beam 1 - Highest loss in 1.3 s integral




# Magnet model

- The knowledge of the magnetic model of the LHC is remarkable and has been one of the key elements of a very smooth beam commissioning
- Huge parameter space, mistakes made, lessons learnt etc but...
- Tunes, energy matching, optics remarkably close to the model already
- Bodes very well for the future.

# Beam dump

Beam dumping systems working very well  
Systematic and very thorough testing and set-up in progress






# Collimation

Excellent initial beam based commissioning following careful preparation and tests

- Full program of beam based positioning
- System works as designed.
  - Expected cleaning and leakage processes seen.
- Possible to verify passive protection: losses at primary collimators.
- Hierarchy established and respected in tests
- Collimation setup remained valid over days, relying on orbit reproducibility and optics stability


# Beam 2, 3.5 TeV beta-beating



**20% beating!**

# Dispersion


Dispersion B2 at 3.5 TeV



First Collisions at 7TeV cm  
March 30, 2010


### ATLAS IP Separation

H = 4.173 mm : V = 0.035 mm




### CMS IP Separation


H = 0.130 mm : V = 3.925 mm



### ATLAS Coll Rate Evol



### CMS Coll Rate Evol



# 30/3/2010

11:15 injected again  
12:38 : At 3.5 TeV

OP Vistars - Mozilla Firefox

http://op-webtools.web.cern.ch/op-webtools/vistar/vistars.php?usr=LHC1

Most Visited Scientific Linux CERN CERN IT Departme... CERN Home Page Linux distributions

CERN - AB - OP eLogbook - Vi... CERN - AB - OP eLogbook - Vi... CERN - AB - OP eLogbook - Vi... CERN - AB - OP eLogbook - Vi... OP Vistars

LHC1 OP Vistars

LHC Page1 Fill: 1005 E: 3500 GeV 30-03-2010 13:24:16

## PROTON PHYSICS: STABLE BEAMS

Energy: 3500 GeV I(B1): 1.88e+10 I(B2): 1.68e+10

FBCT Intensity Updated: 13:24:16

Intensity

Time

Comments 30-03-2010 13:22:57 : Stable beams!

BIS status and SMP flags	B1	B2
Link Status of Beam Permits	true	true
Global Beam Permit	true	true
Setup Beam	true	true
Beam Presence	true	true
Moveable Devices Allowed In	true	true
Stable Beams	true	true

LHC Operation in CCC : 77600, 70480 PM Status B1 ENABLED PM Status B2 ENABLED

Done

Where we are “today”

# Easter Week-end; 21 hours colliding run at 7TeV cm


05-Apr-2010 21:47:42    Fill #: 1022    Energy: 0.0 GeV    I(B1): 1.54e+08    I(B2): 6.79e+07

	ATLAS	ALICE	CMS	LHCb
Experiment Status	STANDBY	STANDBY	STANDBY	STANDBY
Instantaneous Luminosity	3.157e-05	0.000e+00	0.000e+00	0.000e+00
BRAN Count Rate	2.000e-323	1.402e-16	--	3.485e-06
BKGD 1	0.002	0.014	0.002	0.150
BKGD 2	0.000	0.000	0.002	0.002
BKGD 3	0.000	0.005	0.003	0.051


  

LHCf	STANDBY	Count(Hz): 0.000	LHCb VELO Position	OUT	Gap: 58.0 mm	TOTEM:	STANDBY
------	---------	------------------	--------------------	-----	--------------	--------	---------


Performance over the last 12 Hrs



Background 1



Background 2





# Fill 1022

- Single beam lifetimes:

- Beam 1: 990 hours

- Beam 2: 730 hours

- Very good beam-gas, negligible luminosity burn, negligible diffusion

- Luminosity lifetime

- 40 – 50 hours

- Mainly from gentle beam blow-up ( $\tau \sim 40$  hours for B2V)

- Beam tune shift  $\sim 0.0015$  (one plane, 2 real collision points, reduced emittances)


# A very good 48 hour period!

06-Apr-2010 17:27:13    Fill #: 1023    Energy: 297.4 GeV    I(B1): 1.55e+08    I(B2): 7.01e+07


	ATLAS	ALICE	CMS	LHCb
Experiment Status	STANDBY	NOT READY	STANDBY	STANDBY
Instantaneous Luminosity	0.000e+00	0.000e+00	0.000e+00	8.989e-04
BRAN Count Rate	3.229e-07	4.059e-32	2.086e-11	1.635e-32
BKGD 1	0.002	0.014	0.002	0.131
BKGD 2	0.000	0.000	0.002	0.002
BKGD 3	0.000	0.005	0.003	0.037

LHCf **STANDBY**    Count(Hz): 0.000    LHCb VELO Position **OUT**    Gap: 58.0 mm    TOTEM: **CALIBRATION**


Performance over the last 12 Hrs




Background 1



Background 2




# Beam commissioning strategy 2010




# Tuesday 13.4.

- Q' measurement during 800 GeV ramp: Beam2 Vertical




# Tuesday 13.4.

- $\beta^*$  during squeeze to  $\beta^* = 2\text{m}$  in IR8:





# Tuesday 13.4.

- $\beta$ -beat for Beam1 @  $\beta^* = 2\text{m}$  after correction using IR5  
Q2:




## IP1&5 luminosity vs squeeze

- Raw (online) lumi plots on 10 apr 2010, during the squeeze to 2m in IP1 and IP5
- Factor gained (raw numbers):
  - $\sim 4.5$  in Pt5 (after min scan)
  - $\sim 4$  in Pt1
- Not corrected for lumi decay over the  $\sim 5$ h of squeeze and mini scans



# FMCM Beam Tests for D1 IR1/5

- ❑ Low intensity beam test.
- ❑ Trajectory evolution after OFF send to RD1.LR1, [with FMCM masked](#).
- ❑ Beam **dumped by BLMs in IR7**.




- Trajectory over 1000 turns at a BPM.
- Position change of  $\sim 1.5$  mm over last 250 turns.



# FMCM beam tests

- ❑ Low intensity beam test.
- ❑ Trajectory evolution after OFF send to RD1.LR1, with [FMCM active](#).
- ❑ Beam **dumped by FMCM**.



- Trajectory over 1000 turns at a the same BPM.
- No position change visible within resolution.


>> The redundant protection is working

# Thursday 15.4.

- Higher intensity
  - Switching between PROBE and INDIV in the SPS is now working smoothly: adjusted some settings for the SPS rephasing.
  - Over-injection working well in IR2 (only one dump from pilot send to TDI).
  - Over-injected  $1.1E11$ , collimators at nominal 4.5 sigma settings.
  - Emittance at  $1E11$ : 2.5  $\mu\text{m}$  H, 2,3  $\mu\text{m}$  V.
  - The losses in the injection region do not scale with intensity: above  $5E10$ , the losses go down (in absolute!).

# Strategy for Performance Evolution 2010-2011

# Time lines (Preliminary)



# Instantaneous Luminosity

$$L = \frac{N^2 k_b f}{4\pi\sigma_x \sigma_y} F = \frac{N^2 k_b f \gamma}{4\pi\epsilon_n \beta^*} F$$

- Nearly all the parameters are variable (and not independent)

- Number of particles per bunch
- Number of bunches per beam
- Relativistic factor ( $E/m_0$ )
- Normalised emittance
- Beta function at the IP
- Crossing angle factor
  - Full crossing angle
  - Bunch length
  - Transverse beam size at the IP

$N$

$k_b$

$\gamma$

$\epsilon_n$

$\beta^*$

$F$

$\theta_c$

$\sigma_z$

$\sigma^*$

} Intensity

– Energy

} Interaction Region

$$F = 1 / \sqrt{1 + \left( \frac{\theta \sigma_z}{2\sigma^*} \right)^2}$$

# LHC performance drivers/limiters

Machine Protection is super critical

Intensity

Collimation  
Injector chain  
Electron cloud effect  
Machine protection

Nominal

Start


Energy

Interconnects  
Training  
Machine protection

Interaction region ( $\beta^*$ , F)

Optics  
Aperture  
Machine protection

Presently we are here!!



# Beam Energy; Chamonix

## Decision from Management following Chamonix

- Run at 3.5 TeV/beam (or slightly higher e.g. 4TeV) up to a predefined integrated luminosity ( $1\text{fb}^{-1}$ ) with a date limit (end 2011).
- Then consolidate/repair the whole machine for 7TeV/beam.

# Interaction Regions $\beta^*$ and F in 2010

- Lower energy means bigger beams

$$\varepsilon_n = \varepsilon\gamma \quad \sigma = \sqrt{\varepsilon\beta}$$



- Less aperture margin
- Higher  $\beta^*$  (lower  $\beta^{\text{peak}}$ )

At max

- $> 150$  bunches requires crossing angle (beam-beam)
  - Requires more aperture
  - Higher  $\beta^*$
- Targets for 3.5TeV
  - 2/2.5 m without/with crossing angle in 2010
  - 2m with crossing angle in 2011



# Interaction Region - F



Relative beam sizes around IP1 (Atlas) in collision

With > 150 bunches per beam, need a crossing angle to avoid parasitic collisions

# Machine Protection Strategy for intensity increase


Presentation (Jorg Wenninger) to LMC on 17 February

or Why are we so diligent about  
increasing the LHC intensity?

# The Energy of the LHC beams

Nominal LHC design:

$3 \times 10^{14}$  protons accelerated to 7 TeV/c  
circulating at 11 kHz in a SC ring




At less than 1% of nominal intensity LHC enters *new territory*. Collimators must survive expected beam loss...


# The Energy Density of the LHC beams

Transverse energy density is a measure of damage potential ...

... AND proportional to **luminosity!**



*In terms of damage potential, LHC advances the state of the art by **3 orders of magnitude!***



TT40 transfer line quadrupole vac. chamber  
2.2 MJ @ 450 GeV

SPS dipole vacuum chamber  
2 MJ @ 400 GeV

# Strategy for Increasing the Beam Intensity

- The magic **number for 2010/11 is  $1 \text{ fb}^{-1}$** . To achieve this, the LHC must run flat out at  $1\text{-}2 \times 10^{32} \text{ cm}^{-2}\text{s}^{-1}$  in 2011,
  - Correspond to  $8 \times 10^{10}$  ppb, 700 bunches, **with a stored energy of 35 MJ** (with  $\beta^* = 2 \text{ m}$  and nominal emittance).

# Intensity increase – Summary

- Maximum intensity increase versus stored energy:
  - Up to 0.25 MJ                      typical factor ~2, max 4
  - Up to 1-2 MJ                        max. factor ~2
  - Above 1-2 MJ                        ≤ ~2 MJ per step

# Summary

- To reach a peak of luminosity of  $2 \times 10^{32} \text{cm}^{-2} \text{s}^{-1}$  in 2010 there must be a rapid progression in stored beam energy **in parallel to a lot of commissioning activities.**
  - Much faster than in previous machines, with the potential to cause damage !
  - Coupled to an excellent machine uptime.
- Progress will depend on confidence in MPS.
  - Tests ... + operational experience.



# 2010

Step	E [TeV]	Fill scheme	N	$\beta^*$ [m] IP1 / 2 / 5 / 8	Run time (indicative)
<b>1</b>	<b>0.45</b>	<b>2x2</b>	<b><math>5 \times 10^{10}</math></b>	<b>11 / 10 / 11 / 10</b>	<b>Weeks</b>
<b>2</b>	<b>3.5</b>	<b>2x2</b>	<b>2 - <math>5 \times 10^{10}</math></b>	<b>11 / 10 / 11 / 10</b>	
<b>3</b>	<b>3.5</b>	<b>2x2*</b>	<b>2 - <math>5 \times 10^{10}</math></b>	<b>2 / 10 / 2 / 2</b>	
<b>4</b>	<b>3.5</b>	<b>43x43</b>	<b><math>5 \times 10^{10}</math></b>	<b>2 / 10 / 2 / 2</b>	<b>Weeks/Months</b>
<b>5</b>	<b>3.5</b>	<b>156x156</b>	<b><math>5 \times 10^{10}</math></b>	<b>2 / 10 / 2 / 2</b>	
<b>6</b>	<b>3.5</b>	<b>156x156</b>	<b><math>9 \times 10^{10}</math></b>	<b>2 / 10 / 2 / 2</b>	<b>Months</b>
<b>7</b>	<b>3.5</b>	<b>50 ns - 144**</b>	<b><math>7 \times 10^{10}</math></b>	<b>2.5 / 3 / 2.5 / 3</b>	
<b>8</b>	<b>3.5</b>	<b>50 ns - 288</b>	<b><math>7 \times 10^{10}</math></b>	<b>2.5 / 3 / 2.5 / 3</b>	
<b>9</b>	<b>3.5</b>	<b>50 ns - 720</b>	<b><math>7 \times 10^{10}</math></b>	<b>2.5 / 3 / 2.5 / 3</b>	<b>Months</b>

\* Turn on crossing angle at IP1.

\*\*Turn on crossing angle at all IPs.

One month: 720 bunches of  $7 \times 10^{10}$  at  $\beta^* = 2.5$  m. gives a peak luminosity of  $1.3 \times 10^{32} \text{ cm}^{-2}\text{s}^{-1}$  and an integrated of about  $85 \text{ pb}^{-1}$  per month

# 2011

3.5 TeV: run flat out at  $\sim 100 \text{ pb}^{-1}$  per month


	No. bunches	ppb	Total Intensity	Beam Stored Energy (MJ)	beta*	Peak Lumi	Int Lumi per month [ $\text{pb}^{-1}$ ]
50 ns	432	7 e10	3 e13	17	2	1.3 e32	$\sim 85$
Pushing intensity limit	720	7 e10	5.1 e13	28.2	2	2.2 e32	$\sim 140$
Pushing bunch current limit	432	11 e10	4.8 e13	26.6	2	3.3 e32	$\sim 209$

With these parameters we should be able to deliver  $1 \text{ fb}^{-1}$

Thank you for your  
attention

# Hump

- Our friend the hump on the lifetime -  $\sim 7$  minute period



# Hump

- Our friend the hump on the lifetime, tune amplitude and size

