



Internal metrology and fiducialisation WP15.4.1

Review of HL-LHC alignment and Internal Metrology



Outline


- Definitions & Scope
- Internal metrology
- General Fiducialisation strategy
- Results, data storage & documentation
- Measurements by equipment type
- Tolerances
- Summary
- Next steps

Internal Metrology & Fiducialisation

- Internal metrology
 - All metrology measurements needed for the assembly of magnets, coldmasses and Cryo-assemblies....
- Fiducialisation
 - Transfer of the mechanical axis to the external fiducials on the vacuum vessel
 - Baseline is a best fitting mechanical axis for aperture optimisation
 - Done with a Laser Tracker and a self centering beam tube probe
 - Often combined with geometrical conformity control of extremities
 - Transfer of the magnetic axis measured by stretched wire is also possible



Internal Metrology





Metrology

Extremity flanges

Fabrication control of first Q1 vacuum vessel



Jack Interfaces



Cold feet support flanges

FSI flanges

Metrology

Construction metrology

- Coldbore alignment for QEP connection cryostat
- Flange adjustment
- Control after welding




Cryostating control
for 11T Dipole

Fiducialisation strategy

- Measurement of coldbore mechanical axis from both extremities for redundancy
- Laser Tracker & self centering probe pulled by a steel wire inside the coldbore
- Best fit on theoretical shape for the axis system definition
- Measurement of extremity lines
- Data acquisition with SpatialAnalyzer and scripts
- Calculation & Data analysis with CGC software



Fiducialisation strategy



- 6 AT930 Instrument stations
- 12 Network points
- 66 Points in each coldbore
- 15 Extremity flanges
- Internal precision of $30\mu\text{m}$ RMS

RST system definition
by Best Fit on nominal geometry

HCLBB_000-CR002377


Vertical Shape

Y-axis: -1.5, -1, -0.5, 0, 0.5, 1, 1.5

X-axis: -2000, 0, 2000, 4000, 6000, 8000, 10000, 12000, 14000, 16000

Legend: V1 tube (blue line with diamond markers), V2 tube (orange line with square markers)

X-axis	V1 tube	V2 tube
0	0.0	0.0
1000	0.4	0.1
2000	0.1	0.2
3000	-0.2	0.1
4000	-0.4	-0.1
5000	-0.3	-0.2
6000	0.1	0.0
7000	0.4	0.2
8000	0.1	0.0
9000	-0.2	-0.1
10000	-0.3	-0.2
11000	0.1	0.0
12000	0.4	0.2
13000	0.1	0.0
14000	-0.2	-0.1
15000	-0.1	0.0



HCLBB_000-CR002377


Race track

Legend:

- V1 trials (blue dots)
- V2 trials (orange dots)
- trial (grey oval boundary)

Documentation

- Raw measurement files and Excel reports are stored in MTF



- Connection side (Values expressed in local coordinate system)									
X (mm)					Z (mm)				
ID	Measured X	Nominal X	Delta X	Tolerance X	Measured Z	Nominal Z	Delta Z	Tolerance Z	
E	-269.43	-270.00	0.57	2	-269.70	-269.00	-0.30	2	
M1	-139.80	-140.00	0.20	1.15	145.00	145.00	0.00	1.15	
M2	140.35	140.00	0.35	1.15	145.06	145.00	0.06	1.15	
M3	-144.82	-145.00	0.18	1.15	-144.96	-145.00	0.04	1.15	
N	309.85	310.00	-0.15	2	-70.67	-70.00	-0.67	2	
X	0.61	0.00	0.61	1.15	180.58	180.00	0.58	1.15	
W	2.03	0.80	1.23	2	-79.81	-80.00	0.19	2	

- Lyra side (Values expressed in local coordinate system)									
X (mm)					Z (mm)				
ID	Measured X	Nominal X	Delta X	Tolerance X	Measured Z	Nominal Z	Delta Z	Tolerance Z	
E	-269.35	-270.00	0.70	2	-269.23	-269.00	-0.67	2	
M1	-139.56	-140.00	0.44	1.15	145.07	145.00	0.07	1.15	
M2	140.10	140.00	0.10	1.15	144.67	145.00	-0.33	1.15	
M3	-145.06	-145.00	-0.06	1.15	-144.39	-145.00	0.61	1.15	
X	0.32	0.00	0.32	1.15	179.86	180.00	-0.15	1.15	
W	1.25	0.80	0.45	2	78.95	-80.00	1.05	2	

Main Made of Equipment data Manufacturing Operation Non-conformities Documents History Map

Actions: [Back to list](#) | [Edit](#) | [Detach results doc](#) | [Attach non-conformity](#) | [Repeat step](#)

Step Generic Data

Step ID

R 19.2

Other name

Description

WP08 Fiducialization

Status

Done

Result

Ok

Completed on

2018-05-16

Provided by

Expected by

Responsible

D. Missiaen

Executed by

P.Valentin

Comments

Step Documents

Applicable Standard

[LHC-G-TP-0001 \(ver.1.0\)](#)

Chapter

Results

[1974155 \(ver.1\)](#)

WP08 Fiducialization - HCLBB_000-CR0023...

Non Conformity

Audit

Created on

2018-05-11

Last modified on

2018-05-16

by

PVALENTI

- Automatic comparison with tolerances
- Geometrical Non-Conformities are created
- Fiducial parameters will also be stored in the MTF database for an automatic dataflow towards the survey Database

Measurements by Type

- Triplet Magnets Q1,Q2,Q3
- CP, D1, D2
- 11T Dipole
- LEP Connection cryostat
- QEN Cryobypass & Collimator

Triplet Magnets

■ Q1 & Q3

- Coldmass metrology made by FNAL
- Vacuum vessel controls at CERN
- Delivered cryostated & fiducialised to CERN
- Full fiducialisation after transport at CERN

Available Procedures

Vacuum Vessel:


<https://edms.cern.ch/document/2168890/1>

Coldmass:

<https://edms.cern.ch/document/2168888/1>

Fiducialisation:

<https://edms.cern.ch/document/2168886/1>




■ Q2

- Coldmass build at CERN
- Assembly metrology by MSC with support from 15.4
- Full fiducialisation at CERN

Extended control needs
for FSI integration

Triplet Magnets


- Discussions with FNAL colleagues converging to final procedure
- First measurements at FNAL will be made with CERN assistance
- CERN will provide:
 - The methodology (defined and agreed on)
 - The procedures (under approval)
 - The beam tube probe (drawings under approval)
 - Metric reflector supports (to be purchased)
- Mechanical coldbore axis is measured with large diameter probe
- Best fit axis calculation, but field direction is needed for the orientation
 - Obligatory from previous magnetic measurements via endcover references
- All extremity flanges will be measured and controlled as well



136.7mm beam tube probe
<https://edms.cern.ch/document/2141786/1>



D1 Magnets

- First contact & discussions with KEK colleagues
- Very well defined production procedure
- Fully compatible with planned metrology measurements
- Access to lamination until last moment for field direction





D1 Fiducialisation

- Mechanical coldbore axis is measured with large diameter probe
- Best fit axis calculation, but field direction is needed for the orientation
 - either from lamination plane also via endcover references
 - or from previous magnetic measurements via endcover references
- All extremity flanges will be measured and controlled as well



D2 Fiducalisation

- Build at CERN by MSC
- Assembly measurements are made by MSC
- Mechanical coldbore axis is measured with large diameter probe
- Best fit axis calculation, but field direction is needed for the orientation
 - Obligatory from previous magnetic measurements via endcover references
- All extremity flanges will be measured and controlled as well





94mm beam tube probe

<https://edms.cern.ch/document/2141794/1>


11T + LEP Fiducialisation

- Very similar to standard LHC Dipole process
- Procedure to be finalized
- Mechanical coldbore axis is measured with probe
- Best fit on theoretical shape for the axis system definition
- Measurement of extremity lines
- Standard dataflow




Cryo-bypass & Collimator

- QEN Bypass
 - Alignment of cold-warm transitions
 - Fiducialisation with 4 extremity flanges only
 - After cold-warm transition and beam screen installation
 - The reference plane is defined by the 4 points
 - The axis as a best fit axis
 - Procedure to be prepared
- TCLD Collimators
 - Standard Collimator Fiducialisation
 - Procedure is ready



Fiducialisation summary

- All procedures in preparation or control state
- Measurement hardware is ready
- Waiting for more inputs from the Workpackages concerning acceptance criteria, tolerances & naming conventions



Fiducialisation summary


- All magnets will be fiducialised after cold test at CERN
 - By definition for magnets produced at CERN (LEP, 11T, D2 and Q2)
 - Produced by the collaboration as check for movements and integrity
- Procedures are derived from existing LHC Cryomagnet procedure
 - LHC-G-IP-0015 v.1.2
 - In order to be as universal as possible the naming conventions are extremely important
 - Introduction of a universal report template
- Need to clarify magnetic measurement needs
 - Will be defined with the assembly workflows by the WP
 - During constructions, cold test and final Fiducialisation
 - Transfer measurements are done by Survey

Tolerances

- We need to separate position tolerances of extremity flanges and coldbore from the fiducialisation
- There is no tolerance for a fiducialisation!
- At the present state of the project the evaluation of conformity of a given magnet shape for a particular slot is the responsibility of the MEB
- There is a document specifying the geometrical tolerances for the qualification of the LHC magnets from 2007
<http://cds.cern.ch/record/1038087/files/lhc-project-report-1007.pdf>
- Additional documents are under preparation covering the HL-LHC aspects
 - Tolerances are different along the assembly process and the WP will define those tables for the different elements
 - A common specification for the interfaces with tolerances will be approved

Further Metrology

- The assembly procedures are being compiled at the moment
- There is some need for further metrology after the fiducialisation
 - Beam screen alignment & control after welding
 - Beam Position Monitor alignment & control after welding
 - Cold WarmTransition alignment & control after welding
- So far nothing exceptional, but we need a full picture
- Need to approve the references & tolerances



Next steps

- Need to finally approve baseline mechanical fiducialisation strategy
- Define needs of additional magnetic axis & field direction transfert
- Define and approve cold warm correlations for all assemblies
- Tolerances
 - Need to have approved tolerance tables for each assembly type
- Some survey procedures are to be finalized
- Dataflow & exchange with colleagues
 - The detailed workflows are being defined right now, we need to ensure
 - Uniform reference frame definition
 - Uniform naming conventions
 - Standard templates
 - MTF as common platform
- Documentation
 - As usual, all measurements are documented with raw data, reports and travellers in MTF
 - Implementation of a new approach to store fiducial parameter data in MTF for an automatic dataflow towards the survey Database is ongoing



