ELECTRONS FOR THE LHC

Chavannes de Bogis, Confédération des Helvètes, 24-25 octobre 2019



F. Méot Collider-Accelerator Department Brookhaven National Laboratory

With numerous slides from a number of earlier presentations, by S. Brooks, G. Hoffstaetter, R. Mishnoff, D. Trbojevic & others

All details about CBETA, here: https://arxiv.org/pdf/1706.04245.pdf



All details about ER@CEBAF, here: https://technotes.bnl.gov/PDF?publicationId=40234

Origins of CBETA prototyping

The FFLAG (Fixed Field Linear Alternating Gradient) single-arc concept has been developed as part of the **Linac-Ring** design of the eRHIC EIC project at BNL.


Why an ERL for an EIC:

 Single e-bunch collision == no consideration of beambeam on e-beam == greater tolerance on disruption of ebunch == lower operating and building cost == energy recovery == beam dumped at injection energy

Why an FFAG channel for an ERL:

a single beam line for many energies.


eRHIC Design Study An Electron-Ion Collider at BNL



September 2014

CBETA objectives

- First 4-turn SRF ERL
- Large (x4) momentum aperture.
 Only one linear FFAG so far: EMMA ring at Daresbury, achieved x1.7 energy range
- Halbach-style magnet channel (cheap)
- Largest electron beam power in an ERL (40 mA @ 150MeV)
- Constructed & operated by a Cornell-BNL collaboration, at Cornell
- Commissioned with world-wide support, including JLAB, KEK, , ASTEC, HZ-Berlin, TU-Darmstadt, etc.



Genesis, brief recall

2005 - Start construction of DC photo-emitter gun; world record current (75mA).	2000-on - Linear FFAG R&D: NuFact design, EMMA prototype.
 2012 - Pre-Design on a hard x-ray 5GeV Cornell ERL. 2013 - Cornell's 6 MeV 	2010s - eRHIC ERL design. CBETA design. Halbach quads design and tests.
injector achieves world record brightness.2014 - 75MeV SC linac completed.	2016 - prototype CBETA-style FFAG arc test at BNL ATF, 20- 80MeV energy range.

2014- White paper by Cornell - BNL collaboration.

2016 - Construction funding by New York State NYSERDA

2017 - CBETA Design Report

2018 - Fractional arc test: 1st beam through SRF chain, S1 spreader line and 4-cell FFLAG.

2019 - 1st energy recovery, 1 recirculation, 42 MeV.

CBETA Design Report


Cornell-BNL ERL Test Accelerator

Principle Investigators: G.H. Hoffstaetter, D. Trbojevic

Editor: C. Mayes


arXiv:1706.0

Contributors: N. Banerjee, J. Barley, I. Bazarov, A. Bartnik, J. S. Berg, S. Brooks, D. Burke, J. Crittenden, L. Cultrera, J. Dobbins, D. Douglas, B. Dunham, R. Eichhorn, S. Full, F. Furuta, C. Franck, R. Gallagher, M. Ge, C. Gulliford, B. Heltsley, D. Jusic, R. Kaplan, V. Kostroun, Y. Li, M. Liepe, C. Liu, W. Lou, G. Mahler, F. Méot, R. Michnoff, M. Minty, R. Patterson, S. Peggs, V. Ptitsyn, P. Quigley, T. Roser, D. Sabol, D. Sagan, J. Sears, C. Shore, E. Smith, K. Smolenski, P. Thieberger, S. Trabocchi, J. Tuozzolo, N. Tsoupas, V. Veshcherevich, D. Widger, G. Wang, F. Willeke, W. Xu



Starting in 2020, CBETA will be available for R&D on high power beams.

FFLAG lattice design, magnet prototyping stages




1/2 OD

E [MeV]

Return-arc FFLAG cell parameters are obtained from magnet modeling in OPERA

Field map approach allows to prove that linear superposition hypothesis does hold.
This makes field contribution by any individual magnet a free knob in the design optimizations, in spite of substantial field overlapping between neighbor magnets.



This results from

(i) PMs' µ~1.03,

(ii) only weak corrector-to-corrector cross-talk

Eventually, CBETA arc cell parameters




Figure 2: A schematic diagram of the FFAG doublet cell





Figure 3: The cross sections of the (QF) a pure focusing Halbach magnet (left), and the (BD) a defocusing quadrupole

Table 2: Parameters for the arc cell

BPM block length (mm)	42
Pipe length (mm)	402
Magnet offset from BPM block (mm)	12
Focusing quadrupole length (mm)	133
Defocusing magnet length (mm)	122
Single cell horizontal tune, 42 MeV	0.368
Single cell vertical tune, 150 MeV	0.042
Integrated focusing magnet strength (T)	-1.528
Integrated defocusing magnet strength (T)	+1.351
Integrated field on axis, defocusing (Tm)	-0.03736

Halbach magnet prototyping and measurements at BNL. Vertical correction coils in place here.



Dejan Trbojevic, ERL2019 Helmholtz Zentrum Berlin


12 proof-of-principle magnets (6 QF, 6 BD) built as part of CBETA R&D. Iron wire shimming applied on 3 QFs and 6 BDs with good results.



PoP QF

Jan. 2017 - Stephen Brooks, CBETA Technical Review

Iron Wire Shimming



12 CBETA prototype permanent magnets assembled in an FFAG Arc Test at BNL, total bending 40°. Successful operation at ATF, 2017. Electron energies in the experiment: 18, 24, 36, 54, and 72 MeV



Electron
$$p_{\text{max}} = 18 \text{ MeV} / c \frac{\Delta p}{p} = -60\%$$


Electron $p_{cent} = 45 \text{ MeV} / c$

Electron
$$p_{\min} = 72 \text{ MeV} / \alpha \frac{\Delta p}{p} = +60\%$$

After Dejan Trbojevic, ERL2019 Helmholtz Zentrum Berlin

More Halbach lattice: dispersion suppressor,

adiabatically merge 4 orbits from arc to common long straight axis.



Progressive transition from arc to long straight includes: expanding cell lengths, zeroing the D/F magnet offset, zeroing the reltaive D/F tilt.

The FFLAG return loop ends up featuring 5 different Halbach permanent magnet cross-sections:

QF

BD

BDT2

BDT

OD


- the same QF throughout
- a single BD in the arcs
- a single QD in the long straight
- BDT1, BDT2 in the two transitions



Permanent magnet and corrector tally


subsection	Focusing (F) Quad	Defocusing (D) Quad	BPM	Corrector (H)	Corrector (V)
FA	16	17	16	16	16
ТА	24	24	24	24	24
ZA+ZB	27	27	27	27	27
TB	24	24	24	12	12
FB	17	16	16	16	16
Total	108	108	107	107	107

More lattice: conventional SX and RX design




Magnets:

 Dipole Ouade



- Splitter/combiner design FFAG pass 2 FFAG pass 1 FFAG pass 3 FFAG pass 4 uses conventional 78 MeV 114 MeV 150 MeV 42 MeV electromagnets $\beta_{\chi^{*}} \beta_{y} (m)$ Vertical Correctors s (m) η_{y} (m) 0.2 -0^{-1} - includes a TOF-adjustment 150 MeV chicane, remote-command. 6 MeV +36 MeV +36 MeV +36 MeV +36 MeV \$2 53 **S**1 **S**4


Campaigns of start-to-end tracking studies support design options



Let's conclude - CBETA design parameters:

Parameter	Value	Unit
Top energy	150	MeV
Injector energy	6	MeV
Energy gain	36	MeV
Injector current	≤ 40	mA
Linac passes	4 accel. + 4 decel.	
Arc energies	42, 78, 114, 150,	
	114, 78, 42	MeV
RF frequency	1300	MHz
Bunch frequency	\leq 325	MHz
Harmonic number	343	
Rms x/y emittances	2	$\mu { m m}$
Bunch length	3	ps
Typical arc $\beta_{x/y}$	0.4	m
Typical splitter $\beta_{x/y}$	50	m
Rms bunch size	52 to 2806	$\mu { m m}$
Bunch charge (min)	1 to 123	pC

CBETA construction at Cornell (1/3) Towards "Fractional Arc Test"



Hall LOE before CBETA

LOE contained approximately 7,000 square feet of Lab and Shop space until 2014



Spring 2015

70% of the existing technical-use space was emptied for the initial phase





Magnet work at BNL, then transport to Cornell



CBETA windowframe correctors at BNL





September 12, 2018

2017

S1 and 4-cell FFLAG arc are ready for FAT



First beam to FFLAG arc: FAT

- Fractional Arc Test -

April-May last year

The CBETA Fractional Arc Test brought

together for the first time elements of all of

the critical subsystems required for the project:


- Injector
- Main Linac Cryomodule (MLC)
- Low energy (S1) splitter line with many new components
- A first prototype production permanent magnet girder featuring
 4 cells (8 quads) of the FFA return loop with its own corresponding
 vacuum system and BPM design

·Vomodule (ICM)

Diagnostics

Linac (MI

nal Arc



Frist beam

spot do


Completing the test required:

- characterisation of the injection beam calibration and phasing of the main linac cavities
 - demonstration of the required 36 MeV energy gain

measurement of S1 splitter line horizontal dispersion and R56

- develop a procedure for measuring cell tune in the 4-cell FFLAG

CBETA construction (2/3) Towards 1-pass ER





CBETA, February 2019

February 2019




First ER'ed beam:

1 pass up to 42 MeV / 1-pass down to 6 MeV and dump


March-June 2019


Optics measurements




Orbit Response. Here at 42 MeV, along S1:


- Response data served live using the on-line model "CBETA-V"
- Detailed measurements help refine the model off-line






Tune Measurements vs. Energy, in FFLAG






Orbit Correction, along FFLAG

Orbit correction uses response matrix and SVD solver



Dispersion and R56, complete loop

Measure and compare with CBETA-V virtual machine simulation




High acceptance lattice

• Permanent magnet region is very clean - beam losses are hardly measurable, by far dominated by other regions.

First Recirculation

 June 2019, first circulated beam, acceleration to 42 MeV, back to 6 MeV through the MLC into the beam stop




Beam on first viewscreen in dump line: first energyrecovered beam spot @CBETA ,June 24th, 2019


1-pass energy Recovery




- Transmission 99.6 ± 0.1% ; energy recovery > 99.8%
- Measured up to 8 µA
- Each cavity accelerates beam without receiving external power



CBETA construction (3/3) Toward 4-pass ER Was this summer: July-September











¿Where is the beam (today) ?

10/09/2019: MLC Initial RF Turn On

10/14/2019: MLC successfully brought to 36 MeV. Beam makes it through to entrance to R1.



10/23/2019: Got beam around FFLAG loop on 2nd pass



CONCLUSION

The way is open for CBETA program completion

#	Milestone	Baseline	Actual
	Funding start date		Oct-16
1	Engineering design documentation complete	Jan-17	
2	Prototype girder assembled	Apr-17	
3	Magnet production approved	Jun-17	
4	Beam through Main Linac Cryomodule	Aug-17	
5	First production hybrid magnet tested	Dec-17	
6	Fractional Arc Test: beam through MLC & girder	Apr-18	
7	Girder production run complete	Nov-18	
8	Final assembly & pre-beam commissioning complete	Feb-19	
9	Single pass beam with factor of 2 energy scan	Jun-19	
10	Single pass beam with energy recovery	Jun-19	
11	Four pass beam with energy recovery (low current)	Dec-19	
12	Project complete	Apr-20	



Most recent news,

and they are very positive...

ER@CEBAF: 7 GeV, 10-pass, ER experiment proposal, as part of LR-eRHIC EIC R&D

12 Ge\

East

South linad 1.09 GeV

Add dump line

(ERL2017, CERN - WEIACC003.pdf)

North linac

1 09 GeV

Four main dipoles from Cornell light source upgrade save \sim \$300k on cost! Will be installed

as Arc10 chicane, plan is May 2020.

• A spare beam dump is available at CEBAF. will be installed too.

Demo requires

< 1 week of beam


We're soon there!

Detailed project report & costing: https://technotes.bnl.gov/PDF?publicationId=40234

Machine/Lattice Parameters of ER@CEBAF						
$f_{ m RF}$	1497	MHz	RF frequency			
$E_{ m linac}$	700	MeV	Gain per linac (baseline)			
$E_{ m inj}$	79	MeV	$=E_{\mathrm{linac}} \times 123/1090$			
$\phi_{ m FODO}$	60	deg	Per cell, at first NL pass and last SL pass			
M_{56}	<90	cm	Compression, Arc A			
Extraction	8	deg	Angle to dump line			
Dump power	20	kW				
$\Delta \phi_{ m tol}$	0.25	deg	Req ^{ed} path-length control			


Beam Parameters						
$f_{ m beam}$	31 - 499	MHz	Bunch rep. freq., CW			
	7.485	MHz	Bunch rep. freq., tune mode			
$I_{ m beam}$	100	μA	Max. CW beam current			
$q_{ m bunch}$	0.2	pC	Bunch charge at 100 μA			
σ_l	90 - 150	$\mu { m m}$	Bunch length, high energy			
σ_{t}	0.3 - 0.5	ps				
$\epsilon_{\mathrm{x,y}}$	$\sim 10^{-8}$	m	Geom. emitt. at injection			
dp/p	$< 10^{-4}$		Energy spread at injection			
$\epsilon_{\rm x,y}$	$O(10^{-8})$	m	Geom. emitt., after ER			
dp/p	2-3	%	At extraction			






Jefferson Lab

CEBAF Energy Recovery Experiment: ER@CEBAF



THANK YOU FOR YOUR ATTENTION


Backup slides




75MeV Main Linac Cryomodule (MLC) and its solid-state amplifier cabinets (under injector bench of klystrons).

BPMs


160 BPMs / 12 VME chassis Based on BNL design VMEbased "V301 BPM board"



A single beam/energy is measured at a time by triggering acquisition on peak of bunch, through energies.




 $Figure \ 0.2.2: \ {\rm Fractional \ Arc \ Test: \ Technique \ for \ measuring \ beam \ positions \ at \ the \ peak \ of \ each \ bunch$



BPMs - CBETA bunch pattern

Up to 8 different energies (4 accelerating, 4 decelerating) must be independently measured.



BPM systems at BNL, Rob Michnoff, Joint ARIES Workshop on Electron and Hadron Synchrotrons, 12-14 Nov 2018, /Zurich

Parameter	Unit	KPP	UPP
Electron beam energy	MeV	452	150
Electron bunch charge	pC		123
Gun current	mA	1	40
Bunch rep. rate	MHz	42	325
RF frequency	MHz	1300	1300
Injector energy	MeV	6	6
# of turns		1	4
Energy aperture of arc		2	4