## **ELENA Ion Source Status**



D. Aguglia, C. Carli, <u>D. Gamba</u>, B. Lefort, C. Machado, L. Ponce, F. Wenander, R. Gebel

12th Sep. 2019




- Insulation Transformer Investigations
- Beam Instability Investigations
- Plans

### **Insulation Transformer**



- Unfortunately, still problems with (new) transformer (arrived and installed in 2019)
  - □ (designed and produced by an external company with constraints of tank size (and its viewport))



Several improvements by EPC




Still sparking + degradation: secondary to magnetic core

### **Insulation Transformer**




- After investigation by EPC, it looks like last turn of secondary winding is to close to magnetic core: possibly a <u>construction error</u> – design maybe good.
- **Present plan** is to **build a new transformer** (for free?) with optimized distances.

 $\Box$  (Not "possible" to build a 50 Hz + 400 Hz transformer, at least not for free...)




## Trying to Cycle the HV @100keV






- 200 ms ramp from 56 kV to 106.6 kV
- Plateau of about 1 s before making beam



### It has been possible to cycle HV and have 100 keV beam in ELENA


### However:


- Had to program about **106.6 kV at HV PC** 
  - Tested only for a few hours!
- Only possible to arrive **@95 kV with Positive** HV (protons) (sparks in transformer)
  - Very little conditioning! To be redone!




### Trying to Cycle the HV: delay on HV in the source wrt PC – 85 kV example










Prove that despite PC acquisition is already at nominal voltage
 ~6 kV in 800 ms
 Gives estimate of D<sub>x</sub>:

 D<sub>x</sub> = ~213 [mm/(ΔE<sub>k</sub>/E<sub>k0</sub>)] = ~418 [mm/(Δp/p<sub>0</sub>)]

### **Trying to Cycle the HV:** delay on HV in the source wrt PC: verification




Quick test with HV probe at 3.3 kV pulses (from 0)



- EPC investigation: the delay is caused by the voltage regulation settings (internal to PC) combined with voltage delay due to stray capacitances.
  - □ Possible to "solve it" with modification of regulation circuit.


## From Source to Ring





### **Beam observations**





## Looking for More Signals

CERN ELENA ED

- Measurement of Arc Current with Pearson 150 installed in Faraday cage:
  - No major issues observed, but fast oscillation quickly dumped (<3 us): EM noise?

x10.000 amplifier by Marek Gasior installed on present Pearson 110A signal:

- Now possible to see shot-to-shot mean beam intensity
- Noise (of the amplifier) too high to discriminate intra-pulse oscillations
  - x100 more sensitive Pearson 5753 ordered expected to arrive soon
  - **Possible** to install **proper FCT** (but **15kCHF + integration study** needed)

Considered possibility to install movable Faraday Cup - presently postponed!

- Not possible in differential pumping section (all viewports occupied)
- Possible instead of a SEM, but too tight with timing and too little manpower
  - Use of **SEM as Faraday Cup** also considered, but **too risky** and **too little signal**

Use the **un-used plates** of ion switch **as Faraday Cup** (steering the beam on them)

Equipment available, just need (beam+people) time to do some test

Need to investigate if intensity oscillation on BTV

**Probably an artefact**, maybe possible to correlate BPM and BTV117 (one turn)

BPM amplifiers modified to see high intensity beams (x20 on BPM.H25; x5 on BPM.V25)

-- More ideas/thoughts (mainly by ABP-HSL) on our wiki page --

### Plans (proposal) for the rest of 2019



- Insulation Transformer:
  - **EPC to produce new 400 Hz transformer** by the **end Oct. 2019** 
    - They need input from us! Can we cycle @100 keV + and for ~days? [Sep.]
  - □ For the time being we can use the present one in cycle mode [Sep. Dec.]
    - at least for negative voltages, for a few hours
- Faraday Cage:
  - Add HV measurement via voltage divider [Sep. Oct.]
  - □ Optimise for **fast HV cycling** (need to modify HV PC? Cabling?) [Sep. Oct.]
  - □ Move to **Fug PC both pullers** (not priority, but will make some room in FC rack)

### Beam Transport:

- □ Install **new Pearson** in front of the source [Sep. Oct.]
- □ Measure instability on Pearson + Ion Switch + BPM (+ BTV) [Oct. Nov.]
- □ Investigate/optimize source parameters to find stable working point [Oct. Dec.]
  - So far no other sources of instability identified along the line...
- □ Transverse optics matching/control (dream) [Nov. Dec.]

### Circulating Beam:

 $\Box$  Given time constraint, and tune kicker repair, circulating beam possible only by ~Nov.



## Backup

### Voltage Divider






Maybe possible to add 0.3 MOhm resistor below last of those 100 MOhm resistors, next to ground.

(will give us  $\sim 100 \text{ V}$  for 100 kV?)


## **Change Pearson – probably easy**





### Vacuum quality in the source





Some concerns about vacuum quality and HV insulation due to possible evaporation of soldering material/bad cables

## Some logbook

# CERN ELENA ED

#### - 30/07/2019

- 11:59: Spark @ -90 kV DC after a few minutes of operation see logbook
- 13:31: Spark @ -85 kV DC after a few minutes of operation see logbook
- Managed to transport beam @-50kV DC to ELENA, but orbit fluctuations...
- Some more info available on logbook

#### \_\_\_\_\_ 31/07/2019

- Tested with triangular waveform, up to about 100 kV (6.7 V offset + 5 V amplitude, 4s waveform period, i.e. 46.2 - 101.2 kV, ramp up in about 3.6 seconds, ramp down in about 0.4 seconds. No spark observed.

Some pictures available on logbook

#### **—— 01/08/2019:**

- Set up with positive high voltage. Insulation transformer without 400 Hz, but warm oil.
- 10:30: spark @ +80 kV DC, after 2 minutes (from +70 kV)

- 11:09: spark @ AC (+95.7 -- +51.7 kV) after about one minute after ramping up slowly in steps of (2.2 kV)/(one minute), i.e. 200 mV on Offset set to waveform generator.

- Inverted back to negative HV polarity. same condition.
- 11:51 12:05: -80 kV DC. no spark.
- 12:24 12:42: AC (-95.7 -- -51.7 kV). no spark
- 12:46 13:33: AC (-100 -- -56 kV). no spark

For first AC test, waveform generator set with **period of 9.8s**. Ramp of 4 V amplitude (from a variable offset, e.g. 5.091 V for 100 kV; 4.7 V for 95.7 kV). ramp up in about 3 seconds, ramp down in about 1 second.

### Some pictures available on logbook

- 13:34: going to **period of 4.8 s**, with same waveform. Rump up in about 1.5 s, ramp down in less than 1 s. No spark observed for 10 minutes. Some pictures available on <u>logbook</u>

- 14:46: 600 ms pulse (200 ms ramp up, 200 ms flattop, 200 ms ramp down) in a 4.8 s cycle.
- ramping up slowly to about (-95 -- -50 kV) with no spark observed for a few seconds.