

Technical coordination of Machines at CERN

Marzia Bernardini *on behalf of Katy Foraz*
Accelerator Coordination and Engineering Group



ENGINEERING
DEPARTMENT

Main topics exposed


- Some words of introduction
- The LHC installation from the inside
 - Organization
 - Installation phases
 - Lessons learned on the installation
- Behind the scenes
 - Methodology
 - Lessons learned on project management
- LHC today
 - Change management
 - Long shutdown 2
- Conclusions

Main topics exposed

- Some words of introduction
- The LHC installation from the inside
 - Organization
 - Installation phases
 - Lessons learned on the installation
- Behind the scenes
 - Methodology
 - Lessons learned on project management
- LHC today
 - Change management
 - Long shutdown 2
- Conclusions

The LHC Project timeline

84: First studies of the LHC project



94: Approval of the project by the CERN Council

98: DUP & Start of civil engineering




08: 1st beam

09: Start of Physics


13-14: Long shutdown 1

19-20: Long shutdown 2

24-25: Long shutdown 3



First LHC beams




LHC Project as a Mega Project

Mega Project factors	Impact on the project
<p>Time Horizon</p> <ul style="list-style-type: none">• Multi-year• Multi-phase	<p>Risks had to be properly analysed</p>
<p>Chain of Command</p> <ul style="list-style-type: none">• Multi-layer organization• Matrix Structure	<p>Responsibilities had to be clear</p>
<p>High-degree of Specialisation</p> <ul style="list-style-type: none">• Subject Matter Expertise• Cutting-Edge Technology	<p>Coordination was crucial</p>
<p>Dispersed Teams</p> <ul style="list-style-type: none">• Virtual teams in multiple locations• Outsourcing to other countries	<p>As well as clear and transparent communication</p>


Main topics exposed

- Some words of introduction
- The LHC installation from the inside
 - Organization
 - Installation phases
 - Lessons learned on the installation
- Behind the scenes
 - Methodology
 - Lessons learned on project management
- LHC today
 - Change management
 - Long shutdown 2
- Conclusions

LHC Project Organization (2004)




IC group organization



LHC installation history

8 sectors considered as 8 machines



- Civil engineering and LEP dismantling
- General Services
- Cryogenics
- Machine
- Hardware Commissioning



Civil Engineering phase

- 4 main contracts to build:
 - Surface buildings: modification & construction
 - Underground
 - 2 injection tunnels ~5km
 - 2 ejection tunnels ~2km
 - 2 new experimental areas
 - Modification & consolidation of existing areas

240'000 m³



Civil Engineering phase

- Main issues encountered
 - From the Civil Engineering side
 - Modification of the contract envelop
 - Introduction of the 35 hour-week law in France
 - Impact on resources and schedule
 - Long discussions leading to the introduction of a fixed cost mechanism
 - From the Coordination side
 - Dust
 - Endless end !



General Services installation

- Cabling & general electrical devices

- More than 4'500 km of installed cables
- 2 Industrial services contracts





- Main problems encountered

- On the Electrical Service side
 - 3D integration not complete before the start of the installation, and late requests from users
 - Availability of cables (another contract)
- On the Coordination side
 - Lots of delays
 - Non-Conformities at the end of the works



General Services installation

- Optical fibres
 - Qualified contractor, very good follow-up
 - Fast installation
- Water cooled-cables
 - Unreliable schedule
 - Technical problems
 - Mechanical aspects under-estimated
 - A technical CERN «rescue» team set in place to solve the issues



General Services installation

- Cooling & Ventilation

- 160km primary cooling pipes & ~8km of flexibles

- Cooling and Ventilation systems

- in surface buildings & experimental areas,
- in electrical alcoves,
- modification of the control system

- Main problems encountered

- Nominal progress rate achieved from the 4th sector (/8)
- Size of the supporting devices for the lines
- Installation drawing not verified by the 3D integration team



Cryogenic installation

- Cryogenic islands

- Several contracts
- 5 islands for the 8 sectors
- Modification and new installation
- «Isolated» works – went smoothly



- Cryogenic line installation

- 1 contract for the 27km
- Started in June 03
- After several months of serious technical and schedule problems, works were stopped by the enterprise on July 04
- In order to progress with the installation , CERN set up another technical «rescue» team to repair and reinstall the faulty equipment already at CERN
- Works resumed on November 04, ended in December 06



Impact of the delay of the cryogenic line

- Risks

- QRL Systematic tests at cold cancelled
- Pilot sector on Beam 2 Injection cancelled

- Logistics

- Cryo-magnets storage
- Underground transport of cryo-magnets in // with other worksites

- Coordination

- Sequence of sectors changed
- Time-window dedicated to the machine installation reduced
- Time-window dedicated to the test phase reduced by a factor 2

➤ Search for additional human resources for the Hardware Commissioning



Cryo-magnet transport


- 95% of the total number of cryo-magnets lowered down through one single pit
 - Weight (34t) / load capacity of the crane
 - Dimensions: length ~17m
- More than 1'700 cryo-magnets transported at a speed of 3km/h max
- Huge scheduling constraint
- Main problems encountered
 - Crossing other worksites in narrow areas



Cryo-magnet interconnections

- Including more than 1'900 interconnections, vacuum tests, electrical tests
- Slow start due to missing adjacent magnets and co-activities
- Cruising speed reached at the 3rd sector

10'000 induction brazes
60'000 ultrasonic welds




Cryo-magnet interconnections

- Main problems encountered

- Nov. 06- the inner triplets crisis: defect on the exchanger tube
- Few weeks after their repair: the spiders broke
- «Task Force» set up to repair and analyse the design
 - First sector cool-down without Inner Triplets in order to gain experience for the following phases



- Sept. 07: during the warm-up of the 1st sector for the IT connection, a certain number of PIMs (Plug-In Modules) were broken
 - «RF balls» built to diagnose the number of faulty PIMs



Individual system tests

- Each system was individually tested
 - Power converters and associated equipment
 - Pressure and leak tests of the cryogenic line
 - Collimator tests
 - Interlock system tests
 - Extraction energy system tests
 - Beam Instrumentation tests
 - Ejection and dump systems tests
 - Leak and pressure tests of the continuous cryostat
 -
- Electrical Quality Assurance testing for the arcs and the individually powered magnets

Cool-down

- January 07: difficult start, but weak points quickly identified and compensatory measures set up:
 - On Cryogenics side
 - tuning of Cold compressors
 - tuning of magnets instrumentation
 - condensation and frost on the Current Leads
 - On General Services side
 - electrical cuts
 - network issues
 - tuning of the primary cooling



Hardware Commissioning & Powering tests




- Started in March 2007, difficult start due to a low «Mean Time Before Failure» and a high «Mean Time Before Recovery» !
- March 2008: with respect to the last delays and in order to comply with our commitments to have beam before summer, decision was taken to qualify all circuits to 5TeV (7TeV nominal)



2008, September 10th

First beams

Beam 1 threaded around the machine in 1h
Beam 2 threaded around the machine in 1h30



2008 incident


- On 19 September 2008, during powering tests, an electrical fault occurred producing an electrical arc and resulting in mechanical and electrical damage, release of helium from the magnet cold mass and contamination of the insulation and beam vacuum enclosures.



2008 incident

- In the days following the incident which occurred in sector 3-4 of the LHC, a **Task Force was set up using experts from the relevant LHC systems to:**
 - establish the sequence of facts, based on experimental observations and measurements
 - analyse and explain the development of events, in relation to design assumptions, manufacturing and test data and risk analyses performed
 - recommend preventive and corrective actions for Sector 3-4 and others.
- A fantastic and massive support CERN-wide!

The LHC repairs in detail



Lessons learned – on installation

- Maintaining **sufficient resources** in the home laboratory is necessary to cope with
 - tasks outside the interest and capabilities of industry
 - unexpected technical or commercial difficulties
- The **flexibility** and the **commitment** of our colleagues were the key competencies leading to success
 - But **freeze** the layout of the machine as soon as you can, it will help a lot...
- **Balance risks**: lack of competition for contracts can increase project costs and affect deadlines
 - 2 firms at least for a single adjudication on large/main contracts
 - the only times it was not done, it led to problems (2 out of 3)

Nota Bene
Hardware only
No Software
No Controls

Main topics exposed


- Some words of introduction
- The LHC installation from the inside
 - Organization
 - Installation phases
 - Lessons learned on the installation
- **Behind the scenes**
 - Methodology
 - Lessons learned on project management
- LHC today
 - Change management
 - Long shutdown 2
- Conclusions

Methodology (1/3)

- Quality Assurance Plan

Covers documentation and processes over the lifecycle

Quality Assurance



Quality Assurance Policy

QUALITY ASSURANCE POLICY AND PROJECT ORGANISATION

Table of Contents

1. PURPOSE	5
2. SCOPE	5
3. QUALITY ASSURANCE POLICY	5
4. ORGANISATION	6
4.1 PROJECT ORGANISATION	6
4.2 LHC PROJECT LEADER	6
4.2.1 LHC PROJECT MANAGEMENT AND PROJECT LEADER'S OFFICE	6
4.2.2 SUPPORTING DIVISIONS	7
4.2.3 COMMITTEE STRUCTURE	8
4.3 QUALITY ASSURANCE ORGANISATION	9
4.3.1 RESPONSIBILITIES	9
4.3.2 DEPUTY TO LHC PROJECT LEADER FOR QUALITY ASSURANCE	9
4.3.3 QUALITY ASSURANCE REPRESENTATIVES AND QA WORKING GROUP	9
5. QUALITY ASSURANCE PLAN	10
5.1 PROJECT DEFINITION	10
5.1.1 PARAMETERS AND LAYOUTS	10
5.1.2 LHC HARDWARE BASELINE	10
5.1.3 CONFIGURATION MANAGEMENT	10
5.2 DESIGN CONTROL	11
5.3 DOCUMENT AND DATA CONTROL	11
5.4 PURCHASING AND CONTRACTING	11
5.5 PRODUCT IDENTIFICATION AND TRACEABILITY	11
5.6 MANUFACTURING PROCESS CONTROL	12
5.7 INSPECTION, TESTING AND QUALITY RECORDS	12
5.8 CONTROL OF NON-CONFORMING PRODUCT	12
5.9 HANDLING, STORAGE, PACKING AND DELIVERY	12
5.10 INSTALLATION, OPERATION AND SERVICING	12
5.11 QUALITY AUDITS	13
5.12 TRAINING	13
6. SAFETY POLICY	13
6.1 GENERAL SAFETY	14
6.2 QAP FOR IMPORTANT SAFETY ELEMENTS	14
7. ANNEXES	14
8. REFERENCES	15

F1
Pa


'I say what I'll do and I do what I said'

Methodology (1/3)

- Quality Assurance Plan

Covers documentation and processes over the lifecycle

to ensure that all stakeholders are using the same processes




Methodology (1/3)

- Quality Assurance Plan

Covers documentation and processes over the lifecycle

to ensure that all stakeholders are using the same processes




- Configuration Management & 3D Integration

what | Hardware Baseline (aka Product Breakdown Structure)

where | Layout Database for Functional Positions – fully developed during the project times
| 3D Integration fed with the Digital Mock-Up – from Layout DB to 3D-CAD systems

Project/Product Breakdown

The responsibility of the Project Engineers is reflected by the organization in subprojects



The configuration is mirrored in a tree structure where all the documentation is contained

A set of approved and released documents that represents the definition of a product at a specific point in time

The LHC – understood as a project or a facility – is decomposed in terms of functions



- systems
- sub-systems
- main type units to be manufactured

Configuration Items fully under the control of the configuration management and on which the impact of the changes is analysed

Courtesy R. Saban

All of these documents are stored in EDMS and/or CAD PDM

With the exception of mails and scientific publications



Courtesy P. Bonnal – see openSE.web.cern.ch

Methodology (1/3)

- Quality Assurance Plan



Covers documentation and processes over the lifecycle


to ensure that all stakeholders are using the same processes

- Configuration Management & 3D Integration


Hardware Baseline (aka Product Breakdown Structure)

Layout Database for Functional Positions – fully developed during the project times
3D Integration fed with the Digital Mock-Up – from Layout DB to 3D-CAD systems






H.C. C4R5 | H.C. C5R5 | HALF-CELL C5R5 28.2200 m



Sequence of functional positions on the external beam


Top view


VACSEC ASRS.B	1067990	995641	173.343	1.98	13502.7846	13504.7646	VCDLB.SRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	0	E	B	1	INSTALLED
VACSEC ASRS.B	1068002	271848	175.323	0.3	13504.7646	13505.0646	VMAAB.ASRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	0	E	B	1	INSTALLED
VACSEC ASRS.B	1068001	996042	175.623	0.93	13505.0646	13505.9846	VCDLI.ASRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	0	E	B	1	INSTALLED
VACSEC ASRS.B	1068000	271848	176.853	0.3	13505.9846	13506.2946	VMAAB.BSRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	0	E	B	1	INSTALLED
VACSEC ASRS.B	1067999	995907	176.853	2.73	13506.2946	13509.0246	VCDLA.SRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	0	E	B	1	INSTALLED
VACSEC ASRS.B	1067998	271848	179.583	0.3	13509.0246	13509.3246	VMAAB.CSRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	0	E	B	1	INSTALLED
VACSEC ASRS.B	1067997	998042	179.883	0.93	13509.3246	13510.2546	VCDLI.BSRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	0	E	B	1	INSTALLED
VACSEC ASRS.B	1067996	606710	180.813	0.3	13510.2546	13510.5546	VAMFD.SRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	0	E	B	1	INSTALLED
VACSEC ASRS.B	1067992	998576	181.113	1.891	13510.5546	13512.4456	VACDR.SRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	180	E	B	1	INSTALLED
VACSEC ASRS.B	1067995	606728	183.004	0.52	13512.4456	13512.9656	VAMTA.ASRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	180	E	B	1	INSTALLED
103959	101837	183.524	1.48	13512.9656	13514.4456	TCL.SRS.B1	-0.097	-0.097	-0.097	-0.097	0	0	0	0	0	E	B1	1	06.06.2016	INSTALLED
VACSEC ASRS.B	1067993	606728	185.004	0.52	13514.4456	13514.9656	VAMTA.BSRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	180	E	B	1	INSTALLED
VACSEC ASRS.B	1067991	383927	185.524	6.6	13514.9656	13521.4656	VCDOK.SRS.B	-0.097	-0.097	-0.097	-0.097	0	0	0	0	0	E	B	1	INSTALLED




Sequence of functional positions on the internal beam

103959	101803	183.35	0.339	13482.7816	13502.1296	LOYCO.SRS	QMS	0	0.097	0	0.097	0	0	0	0	0	0	0	0	0	0	0	IE	1	15.05.2013	INSTALLED		
VACSEC ASRS.R	293206	571144	172.696	0.896	13502.1296	13502.7846	VASRTA.SRS.C	0	0.097	0	0.097	0	0	0	0	0	0	0	0	0	0	0	0	IE	1	15.05.2013	INSTALLED	
VACSEC ASRS.R	1067989	271170	173.343	0.896	13502.7846	13503.6796	VCDBR.SRS.R	0.097	0.097	0.097	0.097	0	0	0	0	0	0	0	0	0	1	1	1	R	1	INSTALLED		
VACSEC ASRS.R	1067988	271853	174.238	0.3	13503.6796	13503.9796	VMACB.ASRS.R	0.097	0.097	0.097	0.097	0	0	0	0	0	150	0	0	0	0	0	0	R	1	INSTALLED		
104668	102228	174.638	0.285	13503.9796	13504.2646	BPTX.SRS.B2	0.097	0.097	0.097	0.097	0.097	0	0	0	0	0	0	0	0	0	0	0	0	I	B2	1	06.06.2016	INSTALLED
VACSEC ASRS.R	1067984	271853	174.823	0.3	13504.2646	13504.5646	VMACB.BSRS.R	0.097	0.097	0.097	0.097	0	0	0	0	0	0	0	0	0	1	1	1	R	1	INSTALLED		
VACSEC ASRS.R	1067987	995655	175.123	5.69	13504.5646	13510.2946	VCDLC.SRS.R	0.097	0.097	0.097	0.097	0	0	0	0	0	0	0	0	0	0	0	0	0	R	1	INSTALLED	
VACSEC ASRS.R	1067986	607170	180.813	0.3	13510.2946	13510.5546	VAMED.SRS.R	0.097	0.097	0.097	0.097	0	0	0	0	0	0	0	0	0	0	0	0	0	R	1	INSTALLED	
VACSEC ASRS.R	1067983	999018	181.113	3.851	13510.5546	13514.5056	VCDRS.SRS.R	0.097	0.097	0.097	0.097	0	0	0	0	0	150	0	0	0	0	0	0	R	1	INSTALLED		
VACSEC ASRS.R	1067982	382428	185.064	0.4	13514.5056	13514.9056	VMAA.SRS.R	0.097	0.097	0.097	0.097	0	0	0	0	0	0	0	0	0	0	0	0	0	R	1	INSTALLED	
VACSEC ASRS.R	1067985	383557	185.464	6.56	13514.9056	13521.4656	VCDQJ.SRS.R	0.097	0.097	0.097	0.097	0	0	0	0	0	0	0	0	0	0	0	0	0	R	1	INSTALLED	
VACSEC ASRS.R	283212	571145	192.024	0.655	13521.4656	13522.1296	VABTB.SRS.C	0	0.097	0	0.097	0	0	0	0	0	0	0	0	0	0	180	IE	C	1	INSTALLED		
103960	101783	192.878	0.229	13522.1296	13530.3496	LONDA.SRS	QSR5	0	0.097	0	0.097	0	0	0	0	0	0	0	0	0	0	0	0	IE	1	15.05.2013	INSTALLED	







LayoutDB GIS portal

Methodology (1/3)

- Quality Assurance Plan

Covers documentation and processes over the lifecycle

to ensure that all stakeholders are using the same processes

- Configuration Management & 3D Integration





Hardware Baseline (aka Product Breakdown Structure)

Layout Database for Functional Positions – fully developed during the project times

3D Integration fed with the Digital Mock-Up – from Layout DB to 3D-CAD systems

to ensure that all stakeholders are working on the same version

to represent the accelerator in 3D in an automated way



Methodology (2/3)

- Manufacturing and Installation

Manufacturing follow-up from the early stages

Equipment delivery dates monitoring in the LSS –

Design Office and Central Manufacturing facility scheduling



Assembly Tree

- HCLBALA000-CR002342 - Arc Dipole LBALA
- [-] HCLBAL_000-IN002342 - Cryo Dipole LBAL
 - [-] HCBALA001-02000342 - Cold Mass MBAL
 - [-] HCMB_A001-02000342 - Collared Coil
 - [-] HCMB_A101-02000342 - Yoke assembly, type
 - [-] HCMB_A_S012-02000342 - Helium Shell Assem
 - [-] HCMCSMH001-KE001181 - MCS Magnet Asses
 - [-] **HCMCSMH001-KE001226 - MCS Magnet Asses**
 - [-] HCMCSMH002-KE001226 - Magnet Modul
 - [-] HCDQDBA002-11001352 - Dipole Diode Stack,
 - [-] HCMCDOA001-TE000375 - MCDO Magnet Ass
 - [-] HCMCDOA001-TE000382 - MCDO Magnet Ass
 - [-] HCQBACA101-IN002342 - Cryostat Assembly

Equipment Folder: Properties

Equipment Identifier: HCMCSMH001-KE001226
Other Identifier: MCS-MA-11226
Description: MCS Magnet Assembly (A2)


Actions : [History](#)

External Links
 Click here to view data on the external database

Property	Nominal Value	Value	Unit
Drawing Version		1	
Protection Resistor ID		MCS-PR-BOO1	
Shield Body ID		MCS-ES-I1332	
Shield End Cap ID		MCS-EC-I1333	
Connection Cover Plate ID			
I leak (4K)		0.21	µA
R dc (4K)		55.69	nohm
I leak (300K)		0.1	µA
R dc (300K)		0.102	ohm
Quench Current 1		1094.37	
Quench Current 2		1160.71	
Quench Current 3		1159.76	
Quench Current 4		1159.93	
Quench Current 5		1159.02	
Quench Current 6			

Courtesy S. Mallón – R. Saban

Late design – hence late manufacturing – on some equipment



Clear influence on the order of the sectors to close and to bake-out
 Manufacturing of replacement chambers in some cases

Methodology (2/3)

- Manufacturing and Installation


Manufacturing follow-up from the early stages

Equipment delivery dates monitoring in the LSS –

Design Office and Central Manufacturing facility scheduling

to trace all the important assets with their test results

to organise the order of vacuum sub-sectors to close and the bake-out activities



Methodology (2/3)

- Manufacturing and Installation


Manufacturing follow-up from the early stages

Equipment delivery dates monitoring in the LSS –

Design Office and Central Manufacturing facility scheduling

to trace all the important assets with their test results

to organise the order of vacuum sub-sectors to close and the bake-out activities



- Coordination meetings

Configuration, Integration, Planning,


Worksite follow-up & logistics – Hundreds of ad-hoc meetings

Analysis of co-activities and worksite safety organisation

Safety



SAFETY



- Safety is **1st** priority
- Delicate balance between host states & European & internal rules
- Description of the framework of any worksite is mandatory
 - “Plan de Coordination des Travaux et de la Sécurité” applicable organizational measures in matter of work planning and coordination, of general safety and radiation protection
- Additional procedures are edited to take into account our specific risks

CERN/TIS-GS/96-10
PGCSPS
LHC-PM-IP-001

Safety regulations applicable to the work of contractors at CERN

TISGS96.pdf

IS 5 Rev. Emergency stops
IS 7 Rev. Individual protection
IS 22 Rev. Rules for the safe use of
IS 23 Rev.2 Criteria for the selection
cables and equipment
fire safety and radiation
IS 24 Regulations applicable
installations
IS 25 Beryllium
IS 26 Electrical test bays
IS 27 Electronics laboratories
IS 28 Dangers due to electric
IS 32 Polychlorinated biphenyls
IS 33 Voltage domains according
IS 34 Glass windows
IS 36 Rev. Safety rules for the use
magnetic fields at CERN

A2 Rev. Reporting of accidents
A3 Rev. Safety colours and safety
A4 Rev. Confined spaces
A5 Safety of Experimental
A6 The two-person rule of
A7 Road traffic at CERN
A8 Protection against noise
B Chemical safety code

CERN
CH1211 Genève 23
Suisse

EDMS NO
978710

REV.
0.2

VALIDITE
Draft

REFERENCE
CERN-BE-Note-2009-008-ASR

Date : 2009-02-18

NOTE D'ORGANISATION

PLAN DE COORDINATION DES TRAVAUX ET DE LA SÉCURITÉ DE L'ACCÉLÉRATEUR LHC 2008-9 WORK AND SAFETY COORDINATION PLAN OF THE LHC ACCELERATOR 2008-9

Résumé Abstract
Ce document s'adresse à toutes les personnes amenées à intervenir sur les installations de l'accélérateur LHC, qu'il s'agisse de personnels CERN (titulaires et utilisateurs) ou d'entreprises contractantes. Ce document addresses all persons likely to intervene on the LHC Accelerator installations, either CERN members (staff and users) or staff.

CERN
CH-1211 Geneva 23
Switzerland

LHC Project Document No.
LHC-D-ES-0008 rev 1.0
CERN Div./Group or Supplier/Contractor Document No.
EN-MEF,TE-MPE,TE-CRG,TE-EPC,BE-OP
EDMS Document No.
1109116



Date: 2010-11-29

Engineering Specification

ELECTRICAL SAFETY FOR INTERVENTIONS ON, OR CLOSE TO SUPERCONDUCTING CIRCUITS DURING 2010-2011 XMAS BREAK

CERN
CH1211 Geneva 23
Switzerland

EDMS NO
1110268

REV.
0.1

VALIDITE
permanent

REFERENCE
LHC-OP-OSP-0023 v 0.1

Date : 2010-12-20

PROCEDURE

Access to the underground areas of point 7 and arcs 67-78 of LHC during the ODH and Fire central displacement at point 7

ABSTRACT

This document describes the procedure to grant access to personnel for urgent interventions in the underground areas of LHC Point 7 and arcs 67 and 78 during the ODH and Fire central displacement at point 7.

S37.pdf

S38.pdf

S39.pdf

S38_A1.pdf

S40.pdf

S41.pdf

S42.pdf


S43.pdf

S44.pdf


S45.pdf

3 levels of schedule


- Strategic schedule
 - Strategic goals and major milestones of the project




- Tactical schedule
 - Flow of installation following the main milestones of the master schedule
 - Logistics



- Operational schedules



Baseline schedule



The delay of the QRL imposed the reshuffling of some activities. Additional resources were added for the following phases **+3 months**

Major non-conformities during installation: **+2 months** because of the QRL, **+4 months** because of the interconnections

Id	Title	Created on
LHC-PM-MS-0005 v.4.0	LHC Construction/Installation General Coordination Schedule	2007-06-14
LHC-PM-MS-0005 v.3.1	LHC Construction/Installation General Coordination Schedule	2006-10-10
LHC-PM-MS-0005 v.3.0	LHC Construction/Installation General Coordination Schedule	2006-07-07
LHC-PM-MS-0005 v.2.0	LHC Construction/Installation General Coordination Schedule	2005-04-06
LHC-PM-MS-0005 v.1.7	LHC Construction/Installation General Coordination Schedule	2003-03-31
LHC-PM-MS-0005 v.1.6	LHC Construction/Installation General Coordination Schedule	2003-03-18
LHC-PM-MS-0005 v.1.5	LHC Construction/Installation General Coordination Schedule	2003-03-03
LHC-PM-MS-0005 v.1.4	LHC Construction/Installation General Coordination Schedule	2002-04-19
LHC-PM-MS-0005 v.1.3	LHC Construction/Installation General Coordination Schedule	2002-03-27
LHC-PM-MS-0005 v.1	LEP Dismantling and LHC Construction/Installation General Coordination Schedule	1999-04-06

Hardware commissioning was included

Interconnection non conformities + Inner Triplet Crisis **+7 months**


Courtesy R. Saban

Methodology (2/3)

- Manufacturing and Installation

Manufacturing follow-up from the early stages
Equipment delivery dates monitoring in the LSS –
Design Office and Central Manufacturing facility scheduling

to trace all the important assets with their test results
to organise the order of vacuum sub-sectors to close and the bake-out activities



- Coordination meetings

Configuration, Integration, Planning,
Worksite follow-up & logistics – Hundreds of ad-hoc meetings
Analysis of co-activities and worksite safety organisation

to keep all stakeholders on the same page and to reduce risk due to co-activities

Methodology (3/3)

- Deviation Handling

Changes are reported and approved – or not – by the Committees
Non-conformity reports on equipment and installation

Change Control

- Configuration baselines are established whenever it is necessary to define a **reference** configuration during the lifecycle of the product.
 - during project times, this was mainly driven by optics modifications or by heavy changes in the project (RF modifications, collimation project major review, etc.)
 - the baseline is used as a starting point for further activities until it is revised in a controlled way.
- All **changes** are **reported** to the Committees handling the project or the facility as soon as they get circulated
 - **approval** of Change Requests is done by the Committees,
 - other technical documents are mentioned at the start of the approval cycle and when released
- Between two baselines, all of the impacted documents are listed in **Release Notes** (also in EDMS)

Deviations handling


- From the nominal definition, deviations are treated in terms of documentation by

All stored in EDMS

- a simple update of the Engineering Specification of a product as long as there is no impact outside (e.g. updates on the list of cryo-dipoles types due to a new set of interconnections)
- an Engineering Change Request issued by any of the stakeholders of the project (and having an impact on the Form-Fit-Function of a product) if some parameters/design need to be modified
- or a Non-Conformity Report on an equipment or its installation (deviation from nominal positioning) – that forces the update of the Engineering Specification of the product
 - **equipment** non-conformities are traced within the Manufacturing and Testing Folder (MTF – Infor EAM). If the non-conformity is impacting other equipment an ECR could be generated.
 - **installation** non-conformities are often detected by 3D scans superimposed to the 3D-integration model

Installation non-conformities

- Is there enough space left after each installation stage?
 - 3D geo-referenced scans on the top of the 3D mock-up scenes
 - Installation non-conformities (~500 in total) treated by the Integration team and consequent modifications – if needed – done by the responsible teams




Methodology (3/3)

- Deviation Handling

Changes are reported and approved – or not – by the Committees
Non-conformity reports on equipment and installation

to trace the nominal machine and deviations

to trace the space left for the coming equipment installation




Methodology (3/3)

- Deviation Handling

Changes are reported and approved – or not – by the Committees
Non-conformity reports on equipment and installation

to trace the nominal machine and deviations

to trace the space left for the coming equipment installation




- Reports

Earned Value Management set up

Periodic reports to the Top Management, the Project Leader Office, the Committees

Scheduling reporting




Example of IC-group direct reporting to the DG on a every month basis

Broken line


Yellow line is today

Black line is "today's broken line"

Red line is "last month's broken line"



EVM in the LHC project







Member States asked CERN Management to set up an appropriate Project Control System

Earned Value Management

- Interfaced to accounting system → Actual Costs
- Interfaced to contract management system
- Interfaced to human resource management system
- In-kind contributions

EVM – schedule and cost variance



Courtesy P. Bonnal, P. Lebrun


Methodology (3/3)

- Deviation Handling

Changes are reported and approved – or not – by the Committees
Non-conformity reports on equipment and installation

to trace the nominal machine and deviations

to trace the space left for the coming equipment installation



- Reports

Earned Value Management set up

Periodic reports to the Top Management, the Project Leader Office, the Committees


to trace deviations on schedule/cost and to take corrective actions to keep the project on tracks

Lessons learned – on project management

- Achieving **quality** throughout the project involves the establishment and enforcement of a **comprehensive** and **solid** QAP
 - all stakeholders **adhered** to the message 'I say what I'll do and I do what I said'
 - the **weak** point was the Interface Specification between two Work Packages
- **Unique** methodology and common Project Management **culture**
 - methodology now in place for all new CERN projects (Elena, HIE-Isolde, LIU, HL-LHC, Awake, Physics Beyond Colliders,...) – **scalability**
 - 150 Project Engineers in the Accelerator Sector now trained with **OpenSE**
- **Granularity** on information and expectation levels was properly set
 - not too deep, not too light, not too heavy, well-balanced, **installation oriented**
- Project **investment** on people and tools – learning curve
- EVM should be carefully introduced, supported and assisted.
 - done in the middle of the project, but allowed some spotting out

Lessons learned – on project management


- **Central** organisation: A **dedicated** group was put in place gathering the key organisers
 - integration, configuration, coordination and scheduling, logistics, operational safety, hardware commissioning
- **Small** teams per topic
 - configuration – 6
 - integration – 6
 - scheduling – 3
 - logistics – 1
 - operational safety – 5
 - hardware commissioning – 2+6
 - site management – 8
 - transport – 40
 - assistance to installation – 3+10



Corresponding **tools** and **services** were handled **centrally** for all the groups (equipment and service groups)

Lessons learned

- Soft skills :
 - **Communication** is crucial
 - The **flexibility** and the **commitment** of our colleagues were the key competencies leading to success




Source: ©2013 Project Management Institute, Inc. *Pulse of the Profession In-Depth Report: The High Cost of Low Performance: The Essential Role of Communications*, May 2013. PMI.org/Pulse

Main topics exposed

- Some words of introduction
- The LHC installation from the inside
 - Organization
 - Installation phases
 - Lessons learned on the installation
- Behind the scenes
 - Methodology
 - Lessons learned on project management
- LHC today
 - Change management
 - Long shutdown 2
- Conclusions

Change management




Management of the configuration relative to the machines (*Space reservation, Engineering Change Request, Functional Specification, Engineering Specification, Installation Procedure, Tests Procedure etc...*)
Update of the layout databases

Central information of the 3D models between all design office (*services, mechanical etc...*)
Identification of the interferences
Non-conformities of installation

Central information of the activities to schedule taking into account the logistic and operational safety aspects
Follow-up of the documentation (*Space reservation, Engineering Change Request, Functional Specification, Engineering Specification, Installation Procedure, Tests Procedure etc...*)
Follow-up of the Non-conformities of installation

Change management



Management of the configuration relative to the machines (*Space reservation, Engineering Change Request, Functional Specification, Engineering Specification, Installation Procedure, Tests Procedure etc...*)
Update of the layout databases

Central information of the 3D models between all design office (*services, mechanical etc...*)
Identification of the interferences
Non-conformities of installation


Central information of the activities to schedule taking into account the logistic and operational safety aspects
Follow-up of the documentation (*Space reservation, Engineering Change Request, Functional Specification, Engineering Specification, Installation Procedure, Tests Procedure etc...*)
Follow-up of the Non-conformities of installation

Changes: Layout database evolution

Management of different parallel configuration and layout

- ▶ a clear view of future runs (space, optics...)
- ▶ to cope with projects needs

- ▶ LHC Complex (under construction)
 - ▶ LHC Hardware Baselines
 - ▶ LHC Hardware Baseline Run 2017
 - ▶ LHC Hardware Baseline Run 2018
 - ▶ LHC Hardware Baseline Run 2021
 - ▶ LHC Hardware Baseline Run post-LS3



Changes in the tools – EDMS

- Configuration documentation in EDMS needed to be changed to allow an easy forking on structures.
 - Structures needed to be separated
 - Documents need their validity to be re-affirmed for a given configuration

Changes in the tools – EDMS

- The EDMS portal reflects the forking of the structures and follows the Engineering Lifecycle
 - Studies – Projects – Operation – Dismantling
 - Allows a better view on the baseline forking

Project Selection

Accelerators	Studies (on-going)	LHC Complex (in operation)	LHC Hardware Baseline
CERN Departments	Studies (completed)	SPS Complex (in operation)	LHC Hardware Commissioning (HC)
Computing	Projects (on-going)	PS Complex (in operation)	LHC Design - Parameters & Layouts
Design & Equip. Catalogues	Projects (completed)	Other Facilities (in operation)	I.O - LHC Design Report
EU Projects	Facilities (in operation)		LHC Equipment Codes
Experiments	Facilities (under construction)		
LHC Machine	Facilities (archived)		
HL LHC - High Luminosity LHC	LHC Complex		
LIU - LHC Injectors Upgrade	SPS Complex		
Management & Committees	PS Complex		
Operation	Other Facilities		
Health, Safety & Environment	Secondary Beams & Areas		
External Collaborations			
Others			
Accelerators-OLD			

You've selected: LHC Hardware Baseline

Go Cancel

LHC Complex (in operation)

- ▶ LHC Hardware Baseline
 - ▶ LHC Hardware Baseline Run 2016
- ▶ LHC Hardware Commissioning (HC)
- ▶ LHC Design - Parameters & Layouts
- ▶ I.O - LHC Design Report
- ▶ LHC Equipment Codes
- ▶ LHC Equipment Catalogue - by Family
- ▶ LHC Operation
- ▶ LHC Safety

- Accelerators
 - ▶ Studies (on-going)
 - ▶ Studies (completed)
 - ▶ Projects (on-going)
 - ▶ Projects (completed)
 - LHC Complex Projects (completed)
 - ▶ I.O - LHC Design Report
 - LHC Hardware Baseline Past Runs
 - ▶ LHC Hardware Baseline Run 2015 and
 - ▶ LHC Project (completed)
 - ▶ LHC Magnet Tests Operation in SM18: 20
 - ▶ LHC Test String Project
 - ▶ LHC Controls Project
 - ▶ LHC DFB Interfaces
 - ▶ LHC IR Upgrade Phase I Project
 - ▶ Radiation To Electronics (R2E)
 - ▶ LHC Collimation Upgrade
 - ▶ SPS Complex Projects (completed)
 - PS Complex Projects (completed)
 - ▶ EU Projects (completed)
 - ▶ Other Facilities Projects (completed)
 - Facilities (in operation)
 - LHC Complex (in operation)
 - LHC Hardware Baseline
 - ▶ LHC Hardware Baseline Run 2016
 - ▶ LHC Hardware Commissioning (HC)
 - ▶ LHC Design - Parameters & Layouts
 - ▶ I.O - LHC Design Report
 - ▶ LHC Equipment Codes
 - ▶ LHC Equipment Catalogue - by Family
 - ▶ LHC Operation
 - ▶ LHC Safety
 - ▶ SPS Complex (in operation)
 - ▶ PS Complex (in operation)
 - ▶ Other Facilities (in operation)
 - Facilities (under construction)
 - LHC Complex (under construction)
 - LHC Hardware Baselines
 - ▶ LHC Hardware Baseline Run 2017
 - ▶ LHC Hardware Baseline Run 2018
 - ▶ LHC Hardware Baseline Run 2021
 - ▶ LHC Hardware Baseline Run post-LS3
 - ▶ HL-LHC Nodes in the LHC Hardware Baseline
 - ▶ I.O - LHC Design Report
 - ▶ SPS Complex (under construction)
 - ▶ PS Complex (under construction)
 - ▶ Other Facilities (under construction)

Changes in the tools – EDMS

- The EDMS portal reflects the forking of the structures and follows the Engineering Lifecycle
 - Studies – Projects – Operation – Dismantling
 - Allows a better view on the baseline forking

Project Selection

Accelerators	Studies (on-going)	LHC Complex (under construction)	LHC Hardware Baselines
CERN Departments	Studies (completed)	SPS Complex (under construction)	HL-LHC Nodes in the LHC Hardwa...
Computing	Projects (on-going)	PS Complex (under construction)	I.0 - LHC Design Report
Design & Equip. Catalogues	Projects (completed)	Other Facilities (under constr...	
EU Projects	Facilities (in operation)		
Experiments	Facilities (under construction)		
LHC Machine	Facilities (archived)		
HL LHC - High Luminosity LHC	LHC Complex		
LIU - LHC Injectors Upgrade	SPS Complex		
Management & Committees	PS Complex		
Operation	Other Facilities		
Health, Safety & Environment	Secondary Beams & Areas		
External Collaborations			
Others			
Accelerators-OLD			

You've selected: LHC Complex (under construction)


Go

LHC Hardware Baselines

- ▶ LHC Hardware Baseline Run 2017
- ▶ LHC Hardware Baseline Run 2018
- ▶ LHC Hardware Baseline Run 2021
- ▶ LHC Hardware Baseline Run post-LS3

- Accelerators
 - Studies (on-going)
 - Studies (completed)
 - Projects (on-going)
 - Projects (completed)
 - LHC Complex Projects (completed)
 - I.0 - LHC Design Report
 - LHC Hardware Baseline Past Runs
 - LHC Hardware Baseline Run 2015 and
 - LHC Project (completed)
 - LHC Magnet Tests Operation in SM18: 20
 - LHC Test String Project
 - LHC Controls Project
 - LHC DFB Interfaces
 - LHC IR Upgrade Phase I Project
 - Radiation To Electronics (R2E)
 - LHC Collimation Upgrade
 - SPS Complex Projects (completed)
 - PS Complex Projects (completed)
 - EU Projects (completed)
 - Other Facilities Projects (completed)
 - Facilities (in operation)
 - LHC Complex (in operation)
 - LHC Hardware Baseline
 - LHC Hardware Baseline Run 2016
 - LHC Hardware Commissioning (HC)
 - LHC Design - Parameters & Layouts
 - I.0 - LHC Design Report
 - LHC Equipment Codes
 - LHC Equipment Catalogue - by Family
 - LHC Operation
 - LHC Safety
 - SPS Complex (in operation)
 - PS Complex (in operation)
 - Other Facilities (in operation)
 - Facilities (under construction)
 - LHC Complex (under construction)
 - LHC Hardware Baselines
 - LHC Hardware Baseline Run 2017
 - LHC Hardware Baseline Run 2018
 - LHC Hardware Baseline Run 2021
 - LHC Hardware Baseline Run post-LS3
 - HL-LHC Nodes in the LHC Hardware Base
 - I.0 - LHC Design Report
 - SPS Complex (under construction)
 - PS Complex (under construction)
 - Other Facilities (under construction)

Change management Refer to Yvon's presentation



Management of the configuration relative to the machines (*Space reservation, Engineering Change Request, Functional Specification, Engineering Specification, Installation Procedure, Tests Procedure etc...*)
Update of the layout databases

Central information of the 3D models between all design office (*services, mechanical etc...*)
Identification of the interferences
Non-conformities of installation

Central information of the activities to schedule taking into account the logistic and operational safety aspects
Follow-up of the documentation (*Space reservation, Engineering Change Request, Functional Specification, Engineering Specification, Installation Procedure, Tests Procedure etc...*)
Follow-up of the Non-conformities of installation

Change management



Configuration
Layout

Coordination
Scheduling
Safety

Integration
Studies

Management of the configuration relative to the machines (*Space reservation, Engineering Change Request, Functional Specification, Engineering Specification, Installation Procedure, Tests Procedure etc...*)
Update of the layout databases

Central information of the 3D models between all design office (*services, mechanical etc...*)
Identification of the interferences
Non-conformities of installation

Central information of the activities to schedule taking into account the logistic and operational safety aspects
Follow-up of the documentation (*Space reservation, Engineering Change Request, Functional Specification, Engineering Specification, Installation Procedure, Tests Procedure etc...*)
Follow-up of the Non-conformities of installation

Changes: Coordination & Scheduling

Coordinate and schedule activities in the respect of Safety and Quality



Changes: Coordination & Scheduling

- Participate from the feasibility studies to the realisation
- Enhance **team spirit** and ease information flow
- **Set and share** priorities across Departments
- Support Groups in the difficult **resource allocation** process
- Anticipate and solve conflicting situations, be **flexible**
- **Propose** solutions to solve issues
- Manage stressful situations
- **Report to management**

A screenshot of a complex software interface, likely a project management or resource allocation tool. It features multiple columns and rows of data, with some cells highlighted in yellow. The interface appears to be a Gantt chart or a similar scheduling tool.

*LHC Machine Committee, LS1 Committee, LS2 Committee,
LHC Injectors & Experimental Facilities Committee, Enlarged Directorate*

Changes: Coordination & Scheduling

COORDINATION of PROGRAMMED STOPS

- Participative approach

- Integration & work preparation meetings **with stakeholders and experts**

Work Package Analysis - WPA:


What, where, how, when...safety

Visite d'Inspection Commune - VIC


- Skeleton schedule ►
detailed resource levelled schedule
& **access constraints schedule**

- As Low As Reasonably Achievable meetings where needed

- Non Conformities detection eased with Scans



Changes: Coordination & Scheduling




Changes: Safety Coordination

- Anticipate, plan, declare, evaluate
- Safety integrated in different meetings
Coordination, Work Package Analysis
- Organic unit responsible for the coordination of the stop
- One basic document as a reminder of the key Safety requirements
- Prior declaration (IMPACT) for each intervention
- Safety "evaluation" document per intervening entity
procedure, task list, or equivalent...
- "Visite d'Inspection Commune" VIC if requested/necessary
- To take into account all the risks, resulting from co-activity and successive activities
- To ensure that the general principles of prevention are implemented and that the "rules and regulations" are respected
- When risk occurs
 - Dedicated task force: correct expertise and appropriate experts !!
 - Being ready for the unexpected and determining your response to it

3. SÉCURITÉ ET COORDINATION DE LA SÉCURITÉ ■ SAFETY AND SAFETY COORDINATION.....	11
3.1 Catégories de travaux ■ Work Categories.....	11
3.2 Surveillance et contrôle ■ Monitoring and Control.....	12
3.3 Risques spécifiques ■ Specific Risks.....	12
3.4 Risque électrique ■ Electrical Risk.....	12
3.5 Risque d'incendie ■ Fire Risk.....	13
3.6 Risque lié à la présence de gaz inflammables ■ Risk due to the Presence of Flammable Gases.....	15
3.7 Risque d'explosion ■ Explosion Risk.....	16
3.8 Risque cryogénique ■ Cryogenics Risk.....	16
3.9 Masques auto-sauveteur ■ Self-Rescue Masks.....	17
3.10 Risque chimique ■ Chemical Risk.....	17
3.11 Risque lié au travail en espaces confinés ■ Risk due to Work in Confined Spaces.....	19
3.12 Risque lié au bruit ■ Risk Due to Noise.....	20
3.13 Risque d'exposition aux rayonnements ionisants ■ Risk of Exposure to Ionizing Radiation.....	20
3.14 Dosimètre individuel RADOS DIS-1 mis à disposition par le CERN ■ Personal Dosimeter RADOS DIS-1 provided by CERN.....	22
3.15 Dosimètre opérationnel MGP DMC-2000 mis à disposition par le CERN ■ Operational Dosimeter MGP DMC-2000 provided by CERN.....	23
3.16 Radiographies Industrielles par Rayons X ■ Industrial X-Ray Controls.....	23
3.17 Risque laser ■ Laser Risk.....	23
3.18 Risque lié au champ magnétique ■ Magnetic Field Risk.....	24
3.19 Risque lié au travail sur des réseaux enterrés ■ Risk due to Work with buried Networks.....	24
3.20 Risque lié au travail en hauteur ■ Risk Due to Working at Height.....	25
3.21 Risque lié à l'utilisation de matériels et d'équipements ■ Risk due to Use of Materials and Equipment.....	27
3.22 Risques sur l'environnement ■ Environment Risks.....	28
3.23 Organisation des secours ■ Emergency Rescue Organization.....	28
3.24 Sanctions et arrêt immédiat des travaux ■ Sanctions and Immediate Stop of Works.....	29

Changes: Safety Coordination

- The Safety Coordination should be involved from the **conception** stage and they should be consulted if there are **major modifications** to be carried out.
- The objective is to ensure that prevention is built in where ever possible.
- This will improve the working conditions, reduce risks, improve the quality of the work and therefore save time and money
- All work, tests, interventions, must be:
 - Planned
 - Prepared with a procedure and or a “fiche de taches”
 - Authorized including:
 - Visite d’Inspection Commune
 - As Low As Reasonably Achievable Principle- ALARA
 - Demande d’Intervention en Milieu Radioactive – DIMR
 - Lockout, hot work permit, IS 37 etc...
- All documentation respected



Unfortunate mixture of water and electricity

10 ALARA at CERN

CERN introduced a formalized approach to ALARA [23–25] at the end of 2006, as a result of collaboration between the former Accelerator and Beams department and the Radiation Protection Group. This approach was applied first to the SPS and LHC complex, and since 2009 has been applied to all CERN facilities. The goal was to optimize work coordination, work procedures, handling tools, and even the design of entire facilities. Consequently, all work in Radiation Areas has to be optimized. In particular, all work in Controlled Radiation Areas must be planned and optimized, including an estimate of the collective and individual effective doses to the workers participating in the completion of a task.

Five different criteria were established in 2006 and are used for the determination of the so-called ALARA level of an intervention. These five criteria are shown in Table 6. Depending on the level of the intervention, different means of optimization have to be applied. For example, level 3 interventions need formal approval from the ALARA Committee, which is chaired by the Director of Accelerators.

Table 6: ALARA criteria at CERN

Criteria: Ambient dose equivalent	50 μ Sv/h	2 mSv/h	
Level I	Level II	Level III	
Criteria: Individual dose	100 μ Sv	1 mSv	
Level I	Level II	Level III	
Criteria: Collective dose	500 μ Sv	10 mSv	
Level I	Level II	Level III	
Criteria: Airborne activity in CA values according to [26]	5 CA	200 CA	
Level I	Level II	Level III	
Criteria: Surface contamination in CS values according to [26]	10 CS	100 CS	
Level I	Level II	Level III	


Long shutdown 2: an example



Changes: Scheduling

- Multi level planning:
from Master Schedule to detailed installation schedule

Master schedule - Strategic




Changes: Coordination & Scheduling

ECR ID	Title	Authors	Status	Location	Group	Track It		
LHC-B-EC-0006 v.1.0	HL-LHC ECR - WP13. Modifications to the Scope of WP13. Action PSM	R. Jones	Released	Point 5 and 7	BE-BI	78191		
LHC-BGC-EC-0002 v.0.1	Installation of a Beam Gas Curtain (BGC) Demonstrator Instrument Stage 1	Gerhard Schneider	Approval Accepted	LSSL4	BE-BI	77906		
LHC-DQDB-EC-0001 v.0.1	Consolidation of the LHC Dipole Diode Insulation System	Christian Scheuerlein	Under Approval		TE-MS	10539		
LHC-EIOF-EC-0001 v.1.0	Distributed Optical Fibre Radiation and Temperature Sensing in parts of LHC	Diego di Francesco, Yacine Kadi	Released	IP1, IP5 and IP7	EN-EA	80054		
LHC-G-EC-0005 v.1.0	Total Magnet System Modifications in Points 3 and 6	Adrian Todor	Released	Points 3 and 6	EN-EA	80244		
ECR ID	Title	Authors	Status	Location	Group	Track It		
LHC-G-EC-0010 v.1.0	LHC-QI-EC-0009 v.1.0	Additional Cryogenic Instrumentation for Local Diagnostics of Beam-Induced Heat Loads	Released	S45 and S12	TE-CRG	82948		
LHC-G-EC-0011 v.1.0	LHC-QI-EC-0009 v.1.0	Additional Cryogenic Instrumentation for Local Diagnostics of Beam-Induced Heat Loads	Released	S45 and S12 sector 45 & sector 12	TE-CRG	82471		
LHC-HHAAS-EC-0003 v.0.1	LHC-QIF-EC-0001 v.0.1	Installation of cryogenic global mass flowmeters in the QUI and on the WRL	Approval Accepted	P18, P2, P6	TE-CRG	82948		
LHC-HHAAS-EC-0007 v.1.0	LHC-QQBI-EC-0001 v.1.1	Protective Half-Shell for the Vacuum Pumping Lines	Released		TE-VSC	79283		
	LHC-QRMP-EC-0001 v.1.0	New working platforms for pumping groups located at height in L2 and R8 of the LHC	Released	UJ22-UJ88	TE-VSC	77849		
	LHC-RF-EC-0002 v.1.0	FGClite Deployment - Phase 2 (RRs)	Released	RRs	TE-EPC	10707		
LHC-JS-EC-0001 v.1.1	LHC-RF-EC-0004 v.1.0	Deployment of the RegFGC3 electronics in TI2 (SR2) and TI8 (SR8)	Released		TE-EPC	81899		
LHC-LBH-EC-0001 v.0.2	LHC-RP-EC-0002 v.0.3	Installation of three new COMET 2p power converter for LIU-SPS TCDI	In Work	SR2	TE-EPC	78458		
LHC-LE-EC-0005 v.0.2	LHC-RPH-EC-0003 v.1.0	Change of LHC4-8-8kA power converters in the LHC RR13/17/53/57 areas	Released	RR13/17/53/57	TE-EPC	79739		
LHC-LJ-EC-0041 v.1.0	LHC-RPMBD-EC-0001 v.1.0	Change of RPMB Power Converters in the LHC RR13/17/53/57/73 and 77 areas	Released	RR13, RR17, RR53, RR57, RR73, RR77	TE-EPC	10682		
LHC-LJ-EC-0045 v.2.0	LHC-TANB-EC-0001 v.0.2	Installation of a TANB in A4R8 and A4L8 and Related layout Modifications	Under Approval	LSS8	EN-EA	10274		
ECR ID	Title	Authors	Status	Location	Group	Track It		
LHC-LJ-EC-0046 v.1.0	LHC-TC-EC-0011 v.1.0	LHC-VC1T-EC-0001 v.0.1	Modification of the VT retractable support system in the ATLAS experiment	Josef Sestak, Piotr Gebolis	Approval Accepted	Point 1	TE-VSC	79284
LHC-MKI-EC-0004 v.1.0	LHC-TC-EC-0012 v.0.1	LHC-VC2-EC-0001 v.0.1	UPGRADE of the LHC Vacuum Sectors A1L2.X, IP2.X and A1R2.X Within the LS2 ALICE Experiment Upgrade	Josef Sestak, Jerome Gilles Chaure	Approval Accepted	A1L2.X, IP2.X and A1R2.X	TE-VSC	78700
	LHC-TC-EC-0013 v.0.1	LHC-VC5-EC-0002 v.0.1	Upgrade of the IP5.X Beam Vacuum Sector	Josef Sestak	Approval Accepted	IP5	TE-VSC	78698
LHC-MKI-EC-0005 v.0.1	LHC-TC-EC-0014 v.0.1	LHC-VPG-EC-0003 v.1.0	Second Vacuum Upgrade of the Turbo Pumping System on LHC MKB Tanks	J. Finelle, G. Bregliozzi, E. Page, G.Pigny	Released	LSS6 dump lines	TE-VSC	79268
LHC-MW-EC-0002 v.2.0	LHC-TC-EC-0015 v.0.1	LHC-VSC-EC-0002 v.1.0	Amorphous carbon coating in standalone magnets of the LHC in IR2 and IR8 during LS2 2019-2020	Pedro Costa Pinto, Mauro Taborelli	Released	LSS R2, LSS L8, Q5, Q6	TE-VSC	79734
	LHC-TC-EC-0016 v.0.1	LHC-XAFP-EC-0005 v.1.0	Maintenance of the AFP Detectors in LS2	Michael Rijsenbeek	Released	LSS1	EP-UAT	82243
	LHC-TC-EC-0019 v.0.1	LHC-XRP-EC-0018 v.0.1	Removal of the PPS Horizontal Roman Pot 210 near and re-installation at 220 near	Joachim Baechler, Michele Arneodo, Mario Deile, Dmitry Druzhkin, Eris Page	Approval Accepted	LSS1	EP-CMT	82749
	LHC-TCAP-EC-0001 v.0.1	LHC-Y-EC-0013 v.1.0	LASS reliability and usability modifications during LS2	Timo Hakulinen	Released	6R5, 6L5	EP-CMX	79708
	LHC-TCDI-EC-0002 v.1.1	LHC-Y-EC-0014 v.1.0	LASS radiation veto modification in TI2 and TI8	Timo Hakulinen	Released	TI2 and TI8	BE-ICS	78620
	LHC-TDIS-EC-0001 v.0.2	LHC-Y-EC-0015 v.1.0	Access Door Supervision Modifications at PM18, PM12, SDX1, USA15, PM54, PX56, S28	Timo Hakulinen	Released	PM18, PM12, SDX1, USA15, PM54, PX56, S28	BE-ICS	78709
	LHC-V-EC-0011 v.1.0	LHC-Y-EC-0016 v.1.0	Replacement of UP25 MAD by an end-of-zone door	Timo Hakulinen	Released	UP25/UL26	BE-ICS	77867
	LHC-V-EC-0012 v.1.0	LHC-Y-EC-0017 v.1.0	New Maintenance Doors in PM18, UL55 and UX85	Timo Hakulinen	Released	PM18, UL55, UX85	BE-ICS	78906
	LHC-V-EC-0013 v.1.0	LHC-Y-EC-0018 v.1.0	Condemnation LHC Top-of-Pit Elevator Technical Area Trap Doors	Timo Hakulinen	Released	point 3, Point 2, Point 4, Point 6	BE-ICS	78707
	LHC-V-EC-0015 v.1.0	LHC-Y-EC-0019 v.1.0	LHC Access Control System upgrade	Timo Hakulinen	Released	All Access Points	BE-ICS	78911
	LHC-V-EC-0016 v.1.0	LHC-Y-EC-0020 v.1.0	Enlargement of MADs at PZ33, PZ45, PM56, and PM76	Timo Hakulinen	Released	all points	BE-ICS	78362
	LHC-VAZ-EC-0006 v.1.0	LHC-Y-EC-0021 v.1.0	LHC Safety System Modifications due to HL-LHC during LS2	Timo Hakulinen	Released	PZ33, PZ45, PM56, PM76	BE-ICS	10596
	LHC-Y-EC-0022 v.1.0	Modification of the Sectorisation of CMS Drainage Gallery (UP542-3529)	Released	Harry SHAKESHAF	Released	R1132-R1171, UJ53, R571	BE-ICS	10406
						UPRs galleries in Points 1 and 5 SD5	EN-ACE	78943
							EP-CMX	78765
								81450


Changes: Coordination & Scheduling

ECRs for LHC - December 2018



ECRs treated = 62


ECRs for LHC - October 2019



ECRs treated = 80
(5 still needed)




Integration studies for LHC



Studies in progress = 5




Differential Layouts




Changes: Scheduling

Master schedule - operational



Coordination & Scheduling


Detailed schedule



Scheduling follow up


- Specific coordination and follow up for major projects and activities on the critical path
 - Identify and follow up key performance indicators
 - React faster to find out technical solution
 - Ease the delay recovery
- General coordination
 - Global overview
 - Analyse on any deviation on the global schedule
 - Support the groups in ressource allocations and planning processes

LS2: Scheduling follow up



LS2: Scheduling follow up

LS2 Dashboard for CRG maintenance



CERN PLANNING CHANGES

- Maintenance P1 MR + P5 Postponed in 2020
- Mechanical cleaning of exchangers rescheduled
- Replacement of Molecular sieve in dryers P4A & B, P6A
- Reviewed scope for vacuum activities

MECHANICAL TEAM - GAP 500h = +1.5 week



- Gap remain stable since mid August
- ACTION PLAN 1:** recover cumulated time loss **PM méca 330h** :
 - Recover the full team + on extra resource effective **beginning of September**
 - Vacuum team mobilized on mechanical tasks **from mid-September till mid-October**
- Situation to be reviewed beginning of October
- ACTION PLAN 2:** recover cumulated time loss **EX cleaning 170h**
 - Critical EX done, scope of priority 2 will be reviewed end of October

ELEC & INSTRUM TEAM - On time (-200h)


- We get the return on investment on Beamex instrumentation collector

VACUUM - ON TIME - On time (-130h)

- Workload diminishing temporarily in the coming month




Equipment Readiness LHC



$\Delta = +4$ equipment


- New readiness
- Readiness in advance
- Readiness late



Changes: some tools - IMPACT

- One database grouping all the interventions in all the accelerator complex
- Approval process through the existing Electronic Document Handling (EDH)
- Linked to the Access Control System database
- Generation of safety forms: fire permit, DIMR...

Workflow



The screenshot displays the IMPACT web interface for the European Laboratory for Particle Physics. The main content area shows details for an activity titled "Inst. TCPF in L557 Left". Key information includes the responsible person (INGEO LAMAG GARCIA), activity number (78615, 161449), facility (LHC Machine), and activity type (Installation). The interface is divided into several sections: "What" (Description: TCPF replacement by TCPF proto), "Where" (Location: 2725 (R74)), "When" (Proposed Start Date, Intervention period, Duration: 60, Working time: Normal: Mon - Fri, 07:30 - 18:00), and "Scheduling" (Intervention period: EYETS-LHC-2016-17, Schedule start date: 30-Jan-2017, Access start date: 29-Jan-2017, Schedule end date: 14-Apr-2017, Access end date: 14-Apr-2017). A left sidebar contains navigation options like "What", "Where", "When", "Who", "How", "Safety", "RP Assessment", "Tests", "Comments", "Work Orders", and "Info Lines".


Changes: some tools - PLAN

Prior to the start of an LS, we need to define which works will be achieved and which are the potential options, based on priorities given to activities and the resources we have

PLAN = A unique repository gathering all activities for a certain period of time with a simple approval process

to harmonize the method to give decision makers and the support group a clear picture of the different requests, and their impacts.

Changes: some tools - PLAN



Changes: some tools - PLAN

CERN Accelerating science Signed in as: mabernar

Plan + Create Activity Search for activity ID or title

LS2
Version 2


- Versions
- Dashboard
- Activity list**
- Resource list
- Specific data
- Activity Workflow
- Action Log
- Plan Roles
- Reports

Activity list Status: Created, Prioritization, Resource Allocation, Under Approval, Approved, Approved if, Postponed, Finished

Reset Select a filter to load + Save as Bulk (1197) Export Show/Hide columns Refresh

ID	Title	Group	Responsible	Priority	WBS	Facilities	Group contribution	Status
id	Title	Departmen...	First name, last name, g...	Select a priority...	Work Breakdown Structure	Facility	Select the co...	Select a status...
11441	Modify LHC PPS (Personnel Protection System) - PZ65 Access point installation	BE-ICS	TIMO TAPIO HAKULINEN (BE-ICS-CSE)		LHC-MAC-UP	LHC Machine	EN-ACE-COS, EN-ACE-INT, EN-EL-EIC, EN-EL-FC, EN-HE-HH, EN-STI-ECE, IT-CS, SMB-SE-CEB, TE-ABT-EC, TE-EPC, TE-MSC-MNC	Created
11440	Modify LHC PPS (Personnel Protection System) - LACS	BE-ICS	TIMO TAPIO HAKULINEN (BE-ICS-CSE)		LHC-MAC-OP	Alice, Atlas, CMS, LHC Machine, LHCb	EN-HE-HM, IT-CS	Created
11439	Supply new converters for the consolidation of the PSB Shavers	TE-EPC	VALERIE MONTABONNET (TE-EPC-OMS)		BOOSTER-CONS	PS Booster		Created
11438	Building 103 extension projet: installation of services	TE-PPR	FABIO FORMENTI (TE-PPR)		B163-UPG	Buildings And Other Facilities	EN-HE-HM, IT-CS-DO, SMB-SE-HE	Created
11437	Building 163/165 upgrade projet: civil engineering for cryogenic system	TE-PPR	FABIO FORMENTI (TE-PPR)		B163-UPG	Buildings And Other Facilities	SMB-SE-DOP	Created
11436	Building 163/165 upgrade projet: drawing sample inserts	TE-PPR	FABIO FORMENTI (TE-PPR)		B163-UPG	Buildings And Other Facilities	EN-MME-EDM	Created
11435	Building 163/165 upgrade projet: Fresca 2 cryostat installation	TE-PPR	FABIO FORMENTI (TE-PPR)		B163-UPG	Buildings And Other Facilities	EN-ACE-SU, EN-HE-HH, HSE-SEE	Created

Changes: global picture



Conclusions

- A solid & common methodology of project and process management is crucial for a good technical coordination
- The tools must be adapted according to the evolution of the needs during the project, and after
- The on site and safety coordination is a key element
 - Tools to identify deviations must be set
 - Procedures and Work package analysis defined, to anticipate any potential issue
 - Flexibility is a key behavioural competency in our environment
- The bottleneck of technical coordination is often related to expertise and experts availability
 - Anticipate the critical activities to allocate resources accordingly
- In our environment our best resources are human resources
- Expertise, flexibility, accountability and communication are key success factors!

Our best resources are human resources
in addition to a
strong expertise,
flexibility,
accountability and communication !