Update on GEM - Panjab



Harjot Kaur (On behalf of PU-GEM Group)

> CMS GEM Workshop 01 Oct. 2019 CERN

Manpower



Faculty:

Vipin Bhatnagar, Jasbir Singh, Sushil S Chauhan and Sunil Bansal

Graduate Students:

- Currently 3-4 Graduate student (mostly entering into their 3rd year)
- 1-2 other senior students who will graduate soon but helping when needed.
- All of them have experience in assembly of GE1/1 chambers at PU

Technician:

- Shiv, Amarjeet*, Navjot, and Subhash*: In CERN for 2 Months
- They have experience in assembly and QC testing as well as preparing/providing of mechanical/electrical support for GE1/1


Quality Control (QC)



- All the QCs (2,3,4) are in working condition
 - Recently tested with one spare v5 generation GE1/1 chamber available at PU site







Clean Room Facility

Gas Leak Station

QC3/4 Test Setup

QC-5 Setup (1)



• For GE1/1 the QC5 was done at DU site for all assembled chambers but PU group already working to setup it at PU site

Copper box of similar size as at DU site is already available few

weeks ago


```
L x W x H:
1.57 m x 0.57 m x
1.15 m
```




QC-5 Status (2)



- SRS ordered in October 2018 after several delays it finally arrived at CERN in August
- SRS software is already installed on a system
 - FEC Firmware was loaded by RD51 expert Enraldo
 - Tested the setup last week (with the help of Mohit(DU))







Contd...



- Result for one of the channel





- Noise is due to grounding problem
- APV25 request process started
 - Dr Supratik(SINP) will provide more input for PU to follow
- Super Chamber assembly
 - Two student and 1 technical staff from PU are at CERN for Super Chamber assembly

Summary



- All the QCs upto QC5 could be done at PU site. All components (upto QC4) are working fine
 - For GE2/1 the QCs setup will be same
 - •QC5 Stage needs to ratified/approved (in due course of time)
- At present focus is to complete the QC5 setup asap:
 - Some preparation already done at PU and in September setup was tested here at CERN

Thanks!