




Assembly, quality checks and installation of the scintillator detector modules for phase I upgrade of the Tile Calorimeter of the ATLAS experiment


HEPP WORKSHOP 29-31 January 2020 University of Venda

Gaogalalwe Mokgatitswane

Crack and MBTS counters




- Occur in the gap region between the central and extended TileCal barrels
- During run 2, these counters were severely degraded by radiation and had to be replaced. (they are designed to be easily replaceable)
- Radiation hard plastic scintillators are ideal for high radiation environment
- WITS University was previously involved in the radiation qualification and selection of the scintillator material to be used in the counter production.



1: MBTS scintillators


2: Crack scintillators

Counters geometry optimization



<u>Details:</u>

https://indaico.cern.ch/getFile.py/access?contribId=6&sessionId=0&resId=0&materialId=slides&confId=29593



- The geometry of new counters extended up to 1.72 in pseudorapidity
- In the past there was a low electron reconstruction efficiency in the electromagnetic region (1.6<eta<1.72) -

Assembly of E3E4 counters

Procedure

- ✓ Prepare aluminum cans (gluing).
- ✓ Tyvek paper for tile wrapping.
- ✓ Place the fibers carefully along each tile and wrap with tyvek.
- ✓ Encapsulate wrapped tiles in Al cans.
- ✓ Seal the counter plastic (black) and Al tape.
- ✓ Check the quality with the Sr90 scan.




















> 128 counters were assembled for the EBA and EBAC.


Sr90 scans

- PMT inside the light tight scan box
- High voltage source for the PMT and a digital multimeter for readout
- Counter is connected to the PMT with a clear optical fiber cable.
- Sr90- beta source (25MBq)
- Fine scans (steps of 10 mm) and regular scans (200, 400, 600, 800 & 900, 950, 1000mm) were conducted.
- One fine scan after every 7 regular scans
- All EBA and EBC counters were certified











Signal output after subtracting pedestal

Summary of the slopes for each counter



Highest voltage for each counter



The overall response of counters to Sr90 is consistent


MBTS refurbishment

Green scintillator (inner counter) from IHEP Protvino + Orange fibers

Procedure:

- Open the can, remove old scintillator and fibers, clean
- Prepare the scintillators and Tyvek wrapping
- Put the fibers and wrap the plates in Tyvek one by one
- Put the wrapped plates in the can
- Seal the counter
- Total of 16 counters produced and tested with Cs137

PS scintillators (outer counter) and new green fibers




Cs137 scans: MBTS


- Each counter was tested with Cs137 system
- Counter is attached to the edge of the EB module, where the tubes are going out of the calorimeter module.
- The maximum amplitude with pedestal subtracted is used a metric.
- All EBA and EBC counters (16) were certified









Barrel module tube layout (inside view)




C PHI	Cs run	Inner	Outer
0	11316	1057	1387
1	11320	1154	1499
2	11322	1084	1457
3	11326	1093	1625
4	11328	0950	1409
6*	11330	1017	1354
5	11332	1036	1477
7*	11334	1028	1571
	0 1 2 3 4 6* 5	0 11316 1 11320 2 11322 3 11326 4 11328 6* 11330 5 11332	0 11316 1057 1 11320 1154 2 11322 1084 3 11326 1093 4 11328 0950 6* 11330 1017 5 11332 1036


* Phi positions had to be swapped





ADC ratio plots for inner and outer counters







Installation of counters on the ATLAS detector












Conclusion



Phase I upgrade completed with a strong contribution from South Africa

- During Run 2 (2015-2018),
 Crack and MBTS
 scintillators were severely
 degraded by radiation and
 had to be replaced.
- Crack and MBTS counters were assembled, qualified and characterized using radioactive sources (Sr90 and Cs137)
- All counters certified and installed on ATLAS.