




# The European Synchrotron



- 1) General presentation
- 2) The ESRF today
- 3) The ESRF-EBS Upgrade

Friday 31 January 2020  
JUAS 2020 Revol Jean-Luc


# A MODEL OF INTERNATIONAL COOPERATION: 22 PARTNER NATIONS

## 13 Member states:

France	27.5 %
Germany	24 %
Italy	13.2 %
United Kingdom	10.5 %
Russia	6 %
Benesync (Belgium, The Netherlands)	5.8 %
Nordsync (Denmark, Finland, Norway, Sweden)	5 %
Spain	4 %
Switzerland	4 %

## 9 Associate countries:

Israel	1.5 %
Austria	1.3 %
Centralsync (Czech Republic, Hungary, Slovakia)	1.05 %
Poland	1 %
Portugal	1 %
India	0.66 %
South Africa	0.3 %



**22 partner nations**

**Annual budget: 100 million euros**

**Staff: 630 people, 40 different nationalities**


**Legal status: Private civil company subject to French law**



# ESRF

## The European Synchrotron


The ESRF yesterday



# PRINCIPLE

- When a charged particle is deviated in a magnetic field, it loses energy by emitting electromagnetic radiation (photons), called synchrotron radiation, tangent to the trajectory.


$$P \propto \left( \frac{E}{mc^2} \right)^4 \frac{I}{\rho}$$





Large difference between electrons and protons !

Scale with the square of the energy!

# EMISSION OF SYNCHROTRON RADIATION IN CIRCULAR MACHINE




## Radiation spectrum




# FROM PARASITIC USE TO DEDICATED USER FACILITY

1947: First observation of synchrotron radiation



« Nina », first beamline at Daresbury in 1966 (synchrotron 6 GeV electron). 1st generation




1981: SRS (UK) 1st dedicated X ray light source 2nd generation



1994: Inauguration of the l'ESRF, The first X ray light source of the 3rd generation






# A TYPICAL USER FACILITY



Synchrotron SOLEIL

# PRINCIPLE OF INSERTION DEVICES

Insert permanent magnets to provide an alternative magnetic field to bend the trajectory.





Progress of X ray light sources are summarized in the evolution of the brilliance


**Brilliance =**  
 photons /s / mm<sup>2</sup> /mrad<sup>2</sup> /0.1% bande-passante

Number of photons per second


Size  
 horizontale\*verticale

Divergence  
 horizontal \*verticale

In a bandwidth of 0.1 %  
 around the considered energy.



# MORE THAN 50 SYNCHROTRON LIGHT SOURCES AROUND THE WORLD



# DIFFERENT TYPE OF SOURCES

Many Medium energy rings :2.7-3.5 GeV

SOLEIL, DIAMOND, CLS, ALBA, SSRF, TPS ,Australian Synchrotron, NSLS II, MAXIV ...



High energy rings ( $\geq 6$ .GeV)

SPRING 8




ESRF Upgrade



APS Upgrade



Petra III



X FELs (~~4<sup>th</sup> generation light sources~~)

- LCLS (Stanford)
- SACLA (SPRING8)
- Flash, European XFEL (Hamburg)
- Fermi@ elettra
- .....



LCLS

SACLA




European XFEL


Fermi



**Laser plasma acceleration: 5<sup>th</sup> generation light source**



# THE ACCELERATOR COMPLEX



# THE LINEAR ACCELERATOR




The Linac consists in one **TRIODE** (cathod – anod – grid) powered with 100 KV. Electrons produced have then an energy of 100 keV.

The electrons are then accelerated in 2 sections (each section = 6 meters), accelerating the beam by 100 MeV, i.e., a total of 200 MeV.



Operation mode	Long pulses	Short pulses
Peak current	25 mA	250 mA
Pulse length	1 $\mu$ s	2ns
Energy spread	+/- 1%	+/- 0.5%



# THE TRANSFER LINE FROM THE LINAC TO THE BOOSTER: TL1



- Length: 16 metres
- Main components: 2 bending magnets, 7 quadrupoles, 2 pairs of steerers
- Diagnostics: insertable screens + synchrotron radiation screens



# THE SYNCHROTRON (OR BOOSTER)




Goal: Accelerate the electrons from 200 MeV to 6 GeV

Cycle: period of 250 msec

Length: 300 metres

# THE TRANSFER LINE FROM THE BOOSTER TO THE STORAGE RING: TL2




Goal:

Transfer the 6 GeV electrons from the Synchrotron to the storage ring:


- 5 bending magnets (powered in serie with Booster dipoles)
- 14 quadrupoles
- 9 insertable screens
- Beam Position Monitors
- Synchrotron radiation screens (1 screen / dipole)
- Length: 65 metres



# THE STORAGE RING YESTERDAY





- Circumference: 844 metres
- 16 super-periods of 2 mirror cells → 32 cells
- Energy: 6 GeV
- Nominal intensity: 200 mA
- Emittance: 4nm rad
- Usual coupling : 0.1 %



# THE STORAGE RING BENDING MAGNETS

64 bending magnets (dipoles)



- Numbers : 64 (2 per cells)
- Bending angle : 5.625 °
- Magnetic field : 0.8612 Tesla
- Number of family : 1
- Nominal intensity : 714.993 A

$$E_{[\text{GeV}]} = 0.3 B_{[\text{T}]} \rho_{[\text{m}]}$$


$$B = 0.8 \text{ T} \quad \rho = 25 \text{ m}$$

**Energy lost per turn of ring by one electron**

$$\Delta E_{[\text{keV}]} = 88.5 \frac{E_{[\text{GeV}]}^4}{\rho_{[\text{m}]}} = 4.6 \text{ MeV}$$

**The power radiated around the length of the ring bending magnets by a current of 200 mA = 920 kW**

# GENERATION OF AN HORIZONTAL EMITTANCE BY RADIATION



Electron 2 emits  $\Delta E$  at the exit of the bending magnet.

- same energy when crossing the magnet
- stay on the reference trajectory


Electron 1 emits  $\Delta E$  at the entrance of the bending magnet.

- lower energy when crossing the magnet
- larger curvature

A horizontal beam size and divergence (or emittance) and an energy spread is created.

Angle or divergence or  $X'$  in radian

The beam emittance is the surface occupied by the beam in size and divergence.



$$\epsilon_{x[m \cdot \text{rad}]} = \frac{1}{\pi} \iint dx dx'$$

# THE STORAGE RING QUADRUPOLE MAGNETS

256 quadrupoles shared in 6 families




Name	Number
QF2	32
QD3	32
QD4	64
QF5	64
QD6	32
QF7	32

The goal of the **quadrupoles** is to focus the electron beam so as to maintain its size as small as possible


The quadrupole settings are also important for:

- the tune values,
- the beam size,
- the injection efficiency,
- the betatronic resonances, etc



# THE STORAGE RING SEXTUPOLE MAGNETS


224 sextupoles shared in 7 families



Name	Number
S4	32
S6	32
S13	32
S20	32
S19	32
S22	32
S24	32

Their settings are important for:

- the chromaticities,
- the betatronic resonances
- the dynamic aperture,
- and therefore the beam lifetime



A sextupole acts as:

- A focusing quadrupole for the electrons which have a higher energy
- A defocusing quadrupole for the electrons which have a lower energy

And steerers (3 power supplies to get a H or V field)


# THE ESRF STORAGE RING LATTICE

NUX = 36.435  
NUZ = 14.391

R = 134.3890  
ALPHA = 1.839E-04

OPTICAL FUNCTIONS


Ex/Gam\*\*2 = 2.694E-17



ESRF Horizontal emittance = 4 nm.rad

ESRF vertical emittance = 5pm

*Vertical emittance is determined by the coupling to the horizontal motion due to magnet or alignment imperfections.*



$$\sigma_x = \sqrt{\varepsilon_x \beta_x}$$

$$\sigma'_x = \sqrt{\varepsilon_x / \beta_x}$$


$$\sigma_y = \sqrt{\varepsilon_y \beta_y}$$

$$\sigma'_y = \sqrt{\varepsilon_y / \beta_y}$$


Taille

Divergence

# INSERTION DEVICES






Goal: produce X-rays with specific properties which are different from those emitted by the dipoles, for example, tuneable energy spectrum, polarisation, higher brilliance...




# INSERTION DEVICES

In-air length = 1.64 m



In-vacuum  
Length=2.4 m



(2.4 m flange to flange , 2m magnetic assembly)

Power generated by one undulator (1.6 m) = 3kW

Available power = 250 kW

But less than 100 kW is used!!

2kW/mm<sup>2</sup> at 200 mA


8000 kW of Electrical power is needed to produce it!!

Efficiency: 2% !



# IN-VACUUM UNDULATORS

The jaws of the in-vacuum undulators can be closed down to 5 mm





Permanent Magnets  
( $\text{Sm}_2\text{Co}_{17}$ ) + Cu-Ni sheet

RF Masks

Cooling Pipes

# THE STORAGE RING FRONT ENDS





Goal: Drive the X-rays produced either by the dipoles, or by the insertion devices, from the storage ring to the beam line.

# THE VACUUM SYSTEM

Goal: control and maintain an excellent vacuum level in the storage ring:


$10^{-10}$  mbar without beam (static pressure)  
 $10^{-9}$  mbar with beam (dynamic pressure)



- This vacuum level is ensured by the ionic pumps, NEG coating
- The pressure control is done with Penning gauges.

## ID chambers

Length = 5 metres et 6 metres




- Extruded aluminium

8 mm


- The internal side of these vacuum vessels is covered with a thin coat of NEG material (Non Evaporable Getter) made of an alloy of Titanium, Zirconium, Vanadium. The particularity of this alloy is to trap chemically certain molecules (mainly CO and CO<sub>2</sub>) acting as vacuum pumps.

# THE STORAGE RADIOFREQUENCY SYSTEM




Goal: compensate the energy loss turn / turn by the electrons, following the synchrotron radiation emission, i.e., 4.8 MeV (with all insertion devices)

# THE ESRF TODAY



ESRF

*Operation*



**Storage ring  
6GeV, 844 m**

<b>Energy</b>	<b>GeV</b>	<b>6.04</b>
<b>Multibunch Current</b>	<b>mA</b>	<b>200</b>
<b>Horizontal emittance</b>	<b>nm</b>	<b>4</b>
<b>Vertical emittance</b>	<b>pm</b>	<b>4</b>

**32 straight sections**

*DBA lattice*


**42 Beamlines**

**12 on dipoles**

**30 on insertion devices**

*72 insertion devices:*

*55 in-air undulators, 6 wigglers,  
10 in-vacuum undulators,  
including 3 cryogenic*




# OPERATION : MACHINE STATISTICS FOR 2015-2018



5442 hours of beam delivered out of 5527 scheduled in 2018.  
Overall 2018 availability of 98.47 %

	2015	2016	2017	2018
Availability (%)	98.53	99.06	98.28	<b>98.47</b>
Mean Time Between Failures (hrs)	93.6	93.8	64.27	<b>104.3</b>
Mean duration of a failure (hrs)	1.37	0.88	1.11	<b>1.6</b>

**2015: 59 Failures / 2016: 59 Failures / 2017: 85 Failures / 2018: 53 Failures.**



## JUNE – JULY 2016: long periods of deliveries without any failures







# OPERATION: FILLING MODES IN 2018

16 Bunch in top-up since 26 April 2016 → High brightness


$I_{max} = 90 \text{ mA}$ , Refill every 20 mins,  $\Delta I = 5 \text{ mA}$ , Vertical emittance: 10 pm

Top-up routinely in operation in 7/8+1 since 6 June 2018

Refill every 20 mins,  $\Delta I = 2 \text{ mA}$





# OPERATION : MACHINE



# OPERATION: MACHINE – TOP-UP OPERATION IN 7/8+1

Before 6 June

After 6 June



*Zoom on beam current*

# ESRF-EBS: The Extremely Brilliant Source Project



The European Synchrotron

# ESRF: MORE THAN 20 YEARS OF SUCCESS AND EXCELLENCE



- **1988** 11 member states sign the creation of the ESRF

- **1992** 1<sup>st</sup> electron beam in the storage ring

- **1994** Inauguration: 15 beamlines on time and within budget

- **1998** 40 beamlines on time and within budget



- **2009-2015** Upgrade Programme Phase I on time and within budget




- **2012** New design for the storage ring



- **2015** Upgrade Programme Phase II: ESRF-EBS

# ESRF UPGRADE PROGRAMME: AN AMBITIOUS PROGRAMME TO PREPARE THE FUTURE

Purple  
Book  
January  
2008



Orange  
Book  
January  
2015

**ESRF UPGRADE PHASE I  
180 M€ (2009-2015):  
ESFRI ROADMAP 2006-2016  
ON TIME – WITHIN BUDGET**

- 19 new beamlines, many specialised in *nano*-beam science
- Upgrade and renewal of facilities and support laboratories

**ESRF-EBS  
Extremely Brilliant Source  
150 M€ (2015-2022):  
ESFRI LANDMARK (2016)**

Revolutionary design  
for a new generation of  
synchrotron source storage rings



**ESRF-EBS**  
EXTREMELY BRILLIANT SOURCE



ESRF Extremely Brilliant Source  
 ESRF-EBS – 150 M€ (2015-2022)



ESRF-EBS  
 Extremely Brilliant Source




~100 times more brilliant and coherent X-rays



Programme to exploit the qualities of this new and unique extremely brilliant X-ray source:

- Creation of new beamlines
- Innovative detector programme
- « Data as a Service » strategy

**Budget for the source only: 104 M€**



Reduce the **horizontal** emittance from **4nm** to **0.14nm**




Beam-line experiments can benefit from :

an increase in brilliance  
an increase of coherence  
(the coherent fraction, in hor. plane)



# BRILLIANCE AND COHERENCE INCREASE


## Brilliance



Hor. Emittance [nm]	4	0.135
Vert. Emittance [pm]	4	5
Energy spread [%]	0.1	0.09
$\beta_x[\text{m}]/\beta_z [\text{m}]$	37/3	6.9/2.6


Source performances will improve by a factor 50 to 100

## 18mm Undulator spectrum




Undulator:  
CPMU18,  
 $K=1.68$   
 $L=2\text{m}$

## Coherence



# LOW EMITTANCE RINGS TREND



Courtesy Riccardo Bartolini

# DECREASING THE HORIZONTAL EMITTANCE

Low emittance:

Careful tuning of  $\beta_x$  and  $\eta_x$  in the dipoles (where the radiation occurs)

$\beta_x$ : envelope function

$\eta_x$ : dispersion

$\eta_x = 2.277$  1 period  
 $\eta_z = 0.837$  C= 52.774


How clever  
we are

Energy

$$\varepsilon_x = F(\text{Lattice}) \frac{E^2}{N^3}$$


Number of  
identical  
dipoles

**Emittance reduction  
→ large number of  
bending magnets**




- Increase the number of cells
  - Large circumference
- Put more dipoles per cell
  - Compact machine

# THE EVOLUTION TO MULTI-BEND LATTICE



## Double-Bend Achromat (DBA)

- Many 3<sup>rd</sup> gen. SR sources
- Local dispersion bump (originally closed) for chromaticity correction




## Multi-Bend Achromat (MBA)

- MAX IV and other USRs
- No dispersion bump, its value is a trade-off between emittance and sextupoles (DA)

# THE HYBRID MULTI-BEND (HMB) LATTICE

## ESRF existing DBA cell


- $E_x = 4 \text{ nm}\cdot\text{rad}$
- tunes (36.44, 13.39)
- nat. chromaticity (-130, -58)



## ESRF HMB cell

- $E_x = 140 \text{ pm}\cdot\text{rad}$
- tunes (76.21, 27.34)
- nat. chromaticity (-99, -82)


- Multi-bend for lower emittance
- Dispersion bump for efficient chromaticity correction => “weak” sextupoles (<0.6kT/m)
- Fewer sextupoles than in DBA
- Longer and weaker dipoles => less SR
- No need of “large” dispersion on the inner dipoles => small  $H_x$  and  $E_x$



# NEW LATTICE VS PRESENT ESRF LATTICE


## ▪ Present ESRF lattice

32 cells, Double Bend Achromat = (2 dipoles + 15 quad. sext.) per cell  
ID length = 5 m (standard) / 6m / 7m



## ▪ ESRF EBS lattice

Hybrid 7 Bend Achromat = (4 dipoles + 3 dipoles-quad + 24 quad., sext., oct.) per cell  
32 identical arcs 21.2 m long, ID length = 5 m



31 magnets per cell instead of 17 currently

Free space between magnets (total for one cell): **3.4m** instead of **8m** today !!

# EXTREMELY BRILLIANT SOURCE: ACCELERATOR UPGRADE


The Extremely Brilliant Source Project aims to:

- Substantially decrease the Storage Ring Equilibrium Horizontal Emittance
- Increase the source brilliance
- Increase its coherent fraction
  
- Must fit in the same tunnel: same circumference as much as possible
- Keep the electron energy (6 GeV)
- IDs at same locations: keep Beamlines where they are
- Maintain the existing bending magnet beamlines
- Preserve the time structure operation and a multibunch current of 200 mA
- Re-use injector complex
- Limit the downtime for installation and commissioning to less than 18 months

**Maintain standard User-Mode Operations until  
the day of shut-down for installation**

# OPERATION AND EBS PROJECT PLAN (2015-2020)


<b>October 2017</b>	<b>2017</b>	<b>Start of the girder assembly (12 months)</b>
<b>10 December 2018</b>	<b>2018</b>	<b>Start of the long shutdown (18 Months)</b>
		<b>Dismantling (3 months) and Installation (9 months)</b>
<b>8 November 2019</b>	<b>2019</b>	<b>Tunnel closed Equipment test</b>
<b>2 December 2019</b>	<b>2019</b>	<b>Accelerator commissioning</b>
<b>March 2020</b>	<b>2020</b>	<b>Beamline commissioning</b>
<b>25 August 2020</b>	<b>2020</b>	<b>Back to USM</b>




Today



# MAGNET SYSTEM: ALL DELIVERED



128 Dipoles  
*Assembled in house*



96 Dipole-quadrupoles



96 Correctors


**More than 1000 Magnets procured in less than 3 years**




512 Quadrupoles  
(128 HG, 384 MG)



192 Sextupoles






64 Octupoles



DC-DC converters  
in production to  
power each  
magnet individually

# DIPOLES WITH LONGITUDINAL GRADIENT [132]

- Each dipole based on 5 PM modules
- Strength 0.67-0.17 T &
- Iron length 1788 mm
- 25.5 – 30.5 mm GAP
- Iron: Pure Iron
- Permanent magnet  $\text{Sm}_2\text{Co}_{17}$



PM assembly tool

Around 6000kg of PM, 660 Iron modules,





Dipole assembly area



# SEXTUPOLES [196]


- 2 types
- 1700 T/m<sup>2</sup> gradient, 166 – 200 mm length
- 19.2 mm bore radius
- 0.5 kW power consumption
- Including additional correction coils



# QUADRUPOLES

## High Gradient [130]

- 2 types
- 89 & 87 T/m gradient
- 388 – 484 mm length
- 12.7 mm bore radius
- 1.9 & 1.7 kW power consumption







## Moderate Gradient [398]

- 4 types
- Up to 54 T/m gradient, 162– 295 mm length
- 16.4 mm bore radius
- 0.7 – 1.1 kW power consumption






# DIPOLE QUADRUPOLES [99]

- 2 types
- Nominal dipole 0.55 – 0.39 T
- Nominal gradient 36-39 T/m
- 1028-800 mm
- 18.6 mm bore radius
- 1.6- 1.2 kW power consumption
- Poles longitudinally curved




# OCTUPOLES [66]

- 36900 T/m<sup>3</sup> gradient, 90 mm length
- 18.6 mm bore radius
- 0.1 kW power consumption
- Allows the required stay clear for Synchrotron radiation fan




# CORRECTORS [100]

- Horizontal: 0.1 T.m
- Vertical 0.1 T.m
- Skew quadrupole: 0.12 T
- 25.5 mm gap mm bore radius



# GIRDERS




## Four identical girders per cell

Mass of:

- Magnetic elements
- Supports
- Vacuum equipments

6-7T/girder



5100mm




# GIRDERS

- Girder supported by 4 adjustable Z feet made of motorised wedges
- Y adjustment by 2 manual jacks pushing the girder

	HORIZONTAL (Y)	VERTICAL (Z)
Girder to girder	50 $\mu\text{m}$	50 $\mu\text{m}$

- **Motorized Z adjustment** resolution 5 $\mu\text{m}$
- **Manual Y adjustment** resolution 5 $\mu\text{m}$
- 1st natural frequency :
  - 50Hz (design criteria)
  - 49 Hz measured



# VACUUM CHAMBERS

14 Chambers per arc  
 Anti-chambers for discrete pumping  
 No NEG coating except CH1, CH14  
 In situ bake-out

High profile aluminum chambers (dipole magnets)

High profile stainless steel chambers



Low profile stainless steel chambers

High profile aluminum chambers (dipole magnets)



High profile stainless steel chambers

Low profile cross section

High profile cross section





High profile cross section



# PHOTON ABSORBERS

- ~391 absorbers (including crotch absorbers, without injection cell specials)
- Total power to be absorbed: 504.5 kW (30 x 15.795 kW + 2x 15.314) kW
- Power density: 10 to 110 W/mm<sup>2</sup> (normal to beam)
- => moderate power parameters compared to current ESRF
- Scattered radiation blocked in the absorber to avoid chamber cooling



Absorber flange mounted on the ante-chamber

Tight space constraints

- CuCr1Zr as an alternative to Glidcop
- Integrate the CF flange in the CuCr1Zr absorber body (Sharma Sushil idea)

# BENDING MAGNETS SOURCE: 1- POLE BM, 2-POLE & 3-POLE WIGGLERS

All new projects of diffraction limited storage rings have to deal with:


Increased number of bending magnets / cell => BM field reduction

Conflict with hard X-ray demand from BM beamlines



ESRF will go from 0.85 T BM to 0.54 T BM

The BM Sources will be replaced by dedicated 1-Pole short super bend, 2-Pole or 3-Pole Wigglers


- Field Customized
- Large fan with flat top field
- 2 mrad feasible for 1.1 T 3PW
- Mechanical length  $\leq 150$  mm
- Source shifts longitudinally by  $\sim 3$ m
- Source shifts horizontally by  $\sim 1$ -2cm



Half assembly



# COMPLETE GIRDER DISASSEMBLED VIEW



**Sept. 2017: One full cell** assembled including straight section, front-ends and services  
(Cables trays, connection boxes, cooling pipes, ....)

- ✓ Validation of the engineering prior series production
- ✓ validation of the assembling and installation procedures



# ASSEMBLY




- Week 1:
- Position girders
  - Install magnets & align
  - Open magnets

- Week 2:
- Install pre-assembled chambers
  - Align BPM's & chambers
  - Close magnets

- Week 3:
- Cooling installation
  - Final alignment
  - Move girder outside


- Each week:
- Vacuum chambers preparation



# GIRDER ASSEMBLY IN FULL SWING



- Assembly building delivered in October 2017
- 3 assembly lines + 1 vacuum preparation line
- 3 to 4 girders assembled per week
- 128/128 girders assembled with magnets
- 112/128 fully assembled with chambers







Storage and logistics are key issues for an upgrade



Assembled girders storage



# DISMANTLING + INSTALLATION: DEC 2018 – NOV 2019

Dismantling

Dec 2018

Nov 2019

Civil works

Girder entry  
Vacuum connection

Piping  
Cabling

FE  
Straights Sections  
Bakeout

IDs  
Equipment test

PSS test

Alignment &  
Global tests



Old machine storage building for radioprotection control

+ all the activities in the technical areas

# INSTALLATION


Name	Start
<b>MILESTONES</b>	<b>10-Dec-18</b>
* Start ESRF-EBS Big shutdown	10-Dec-18



11 months after ...




# INSTALLATION




# DISMANTLING PHASE : 11 WEEKS

2018										2019																																												
W50	W51	W1	W2	W3	W4	W5	W6	W7	W8	W9	W10	W11	W12	W13	W14	W15	W16	W17	W18	W19	W20	W21	W22	W23	W24	W25	W26	W27	W28	W29	W30	W31	W32	W33	W34	W35	W36	W37	W38	W39	W40	W41	W42	W43	W44	W45								
Dismantling phase																																																						

BEFORE



AFTER




1. Cables
2. Pipes
3. Girders & ALL


# DISMANTLING PHASE : CABLES



# DISMANTLING PHASE : FRONT-END PARTS REMOVAL



# DISMANTLING PHASE : AT THE END ...





# CIVIL WORK PHASE : 13 WEEKS

2018										2019																																																					
W50	W51	W1	W2	W3	W4	W5	W6	W7	W8	W9	W10	W11	W12	W13	W14	W15	W16	W17	W18	W19	W20	W21	W22	W23	W24	W25	W26	W27	W28	W29	W30	W31	W32	W33	W34	W35	W36	W37	W38	W39	W40	W41	W42	W43	W44	W45																	
Dismantling phase																																																															
						Civil work																																																									

# CIVIL WORK PHASE : IN PROGRESS




JUAS, 21 January 2020, ESRF operation -EBS project Jean-Luc Revol

# CIVIL WORK PHASE : PREPARATION FOR THE PAINTING



# CIVIL WORK PHASE : LOCATION OF THE GIRDERS PLATES




# CIVIL WORK PHASE : CASING OF GIRDERS PLATES




JUAS, 21 January 2020, ESRF operation -EBS project Jean-Luc Revol

# GIRDERS INSTALLATION : 10 WEEKS



# GIRDERS INSTALLATION : LIFTING

Girder lifted from the EXPH into SRTU    Girder inserted into the module  
Ready for its final destination



# GIRDERS INSTALLATION : ROLLING

No much space for the module during displacements






# GIRDERS INSTALLATION : RECORD






16/04/2019  
9 girders  
installed

# INTERCONNECTIONS PHASE : 11 WEEKS



# INTERCONNECTIONS PHASE : G1-G2 & G3-G4




# INTERCONNECTIONS PHASE : G2-G3 => DQ2 INSTALLATION


DQ2 ready to be inserted into the SRTU



DQ2 in place, alignment in progress



# PIPING PHASE : 17 WEEKS



# PIPING PHASE : PREPARATORY WORK AT THE SUBCONTRACTOR'S


Pipes pre-assembled and tested





Pipes packaged for delivery



# PIPING PHASE : INSTALLATION




# PIPING PHASE : COMMISIONING






# CABLING PHASE : 21 WEEKS




- Around 60 000 h of work
- 220 electricians all along with the project
- More than 100 electricians at the peak load
- Around 14 000 cables installed
- 360 km of cables pulled
- 15 500 connectors
- Less than 100 cables found faulty during the commissioning phase

# CABLING PHASE : INSTALLATION




JUAS, 21 January 2020, ESRF operation -EBS project Jean-Luc Revol

# CABLING PHASE : CELL COMPLETED





# STRAIGHT SECTIONS INSTALLATION : 12 WEEKS







# STRAIGHT SECTIONS INSTALLATION

4	G0	
5	RF cavities	RF
6	IVU01-CV2378	INVAC
7	RF cavities	RF
8	CV5073	
9	CV2378 + IVP02	INVAC
10	CV5073	
11	IV091 + IVR02	INVAC
12	CV5073	
13	CV2378 + IVP04	INVAC
14	CV5073	
15	CV2000-IVR03	INVAC
16	IVW1-CV2378	INVAC
17	CV5073	
18	CV5073	
19	CV5073	
20	CV5073	
21	CV5073	
22	CV2378-IV001	INVAC
23	CV5073	
24	CV5073	
25	RF cavities	RF
26	CV5073	
27	CV5073	
28	CV5073	
29	CV2378-IVP03	INVAC
30	CV5073	
31	CV1140-IV092-CV1140	INVAC
32	CV5073	
1	CV5073	
2	CV5073	
3	CV5073	

RF cavities installed in phase advance in April & May




# STRAIGHT SECTIONS INSTALLATION : 4 TYPES



JUAS, 21 January 2020, ESRF operation -EBS project Jean-Luc Revol

# BAKE-OUTS PHASE : 16 WEEKS




# BAKE-OUT PHASE : ARC READY TO BE BAKED





JUAS, 21 January 2020, ESRF operation -EBS project Jean-Luc Revol




# INSERTION DEVICES INSTALLATION : 15 WEEKS





# BEAM STORED: A MAGIC MOMENT!






## Optics commissioning results and plans

# 2019 NOVEMBER 28<sup>TH</sup> AT 19.00: FIRST TURNS IN EBS-SR





First 2.5 turns,  
steering TL2 and  
SR injection  
elements

First signal of losses in cell 23




# 2019 DECEMBER 6<sup>TH</sup> : BEAM STORED AT 12.30, PINHOLE LIGHT AND TUNE MONITOR

Signal at DL  
and  
DQ pinholes



# 2019 DECEMBER 15<sup>TH</sup> : FIRST ACCUMULATION



**FIRST e<sup>-</sup>  
ACCUMULATION IN  
THE EBS Storage Ring  
15<sup>th</sup> Dec 2019 @ 15.39**

Sun Dec 15 15:39:44

SR Current (c15) **0.57 mA**

Lifetime **03h 31mn**

Filling mode **1/3 multibunch**

ID			Bendings				
1	2	3	1	2	BP4		
BP5	6	BP7	5	BP6	7	8	
9	10	11	12	BP9	BP10	BP11	BP12
13		15	16	14	BP15	16	
17	18	19	20	BP17	18	BP19	20
21	22	23	24	BP21	BP22	23	
BP25	26	27	28	25	26	BP27	28
29	30	31	32	29	30	31	32


MDT MDT since 9/12 07:52

SB (c15)	Current	Lifetime
Tunes	Horizontal <b>0.14</b>	Vertical <b>0.27</b>
Orbit (rms)	<b>286.4 um</b>	<b>148.8 um</b>
Orbit (peak)	<b>2367.4 um</b>	<b>806.3 um</b>
Emittance	<b>308.25 pm</b>	<b>20.13 pm</b>
Energy Spread	-----	TL2 Dose
Average pressure	<b>1.6e-09</b>	<b>6.08 uC</b>
HQPS Output power	<b>3046 kW</b>	TL2 Dose (4H)
Site power	<b>5629 kW</b>	<b>0.38 uC/</b>

LINAC	PSS-LINAC	INJ-VAC	TL1-PS
SY-INJ	SY-INTLK	SY-RF	SY-PS
SY-SEXT	SYCO-PS	SY-VAC	SY-EXT
SY-DIAG	TL2-PS		
SR-INJ	INJ-PERM	PSS-INJ	RF-TRA
SR-ACORR	SRCO-PS	SR-PS	RF-CAV
SR-BPM	SR-ORBIT	SR-VAC	SR-INTLK
SCRAPER	SR-DIAG	PSS-VAC	ID
FEEDB	PSS-BEAM	COLLIMAT	SR-TH
ALGE	FLUIDS	CS-ROOM	
HVAC	BEAML	INFRA	
EL-THD	W-LEAK	HQPS	
VOICE	HDB	HOSTS	TIMING

Dec 12 11:12 MDT; Beam Commissioning


# PRESENT STATUS ON 30<sup>TH</sup> JANUARY



- 100 mA reached
- Delivery to beamline for alignment check

# CONCLUSION

- **EBS project running in parallel with ESRF operation**
  - No impact on user operation
  - **Continuation of the development of the existing machine**  
(injector upgrade, top-up, cryo-undulators, ...)
- **Project execution progression :**
  - **Engineering Design completed**
  - **Procurement completed**
  - **Delivery of main components completed**
  - **Mock-up cell completed**
  - **Assembly completed**
  - **Dismantling/installation completed**
  - **Commissioning well progress**
  - **Delivery to users close to be performed**
  - **No show stopper to be back to operation with users in August**





# MANY THANKS FOR YOUR ATTENTION



Facebook Live  
27 November 2pm CET



MANY THANKS FOR YOUR ATTENTION

