

Cryostat Internal Outfitting

Filippo Resnati (CERN)


The technology

Royalties owner: GTT (France)

Construction licensee: among several Gabadi (construction of ProtoDUNEs)

Applications:

- LNG carriers (>200000 m³ in 5 sub-tanks)
- Floating storages and re-gasification vessels
- Land storage tanks
- Fuel tank for vessels
- *Cryostats for liquid argon Time Projection Chambers*




www.gtt.fr

GTT Mark III technology


Primary membrane: in contact with the liquid. Flexible and elastic to accommodate wave impacts, vessel deformation, thermal expansion and contraction. Not self supporting.

Thermal insulation: passive, modular, in between and directly connected to the primary membrane and the *hull*.

Hull: the warm structure, sustains and support the entire system.




www.gtt.fr



GTT Mark III technology

Primary membrane:


Stainless Steel 304L, 1.2 mm thick, ~1 m x ~3 m 'tiles' (eventually welded together), with corrugation (acting as springs) along the two orthogonal directions (340 mm pitch). Highly standardised components, constructed in Korea. Special components for angle and corner pieces, Protego valves, and roof penetrations.



GTT Mark III technology


Insulation:

Two layers of polyurethane foam (90 kg/m³) separated by the secondary membrane.
Metal inserts on the plywood serve as welding points for the primary membrane.
No direct metal contact between warm structure and primary membrane.
Highly standardised prefabricated components, constructed in Korea.
Special components for angle and corner pieces, Protego valves, and roof penetrations.



The DUNE case

Thickness increased to 790 mm to meet the heat input requirements (same as ProtoDUNE).
Two layers of insulation panels (400 mm + 390 mm) installed subsequently.
The outermost panels contain the secondary containment system.
Improvements on the Mark III technology, developed from the ProtoDUNE experience:



Not to scale

ProtoDUNE experience

ProtoDUNEs:

In total ~40 workers (engineers, carpenters, welders, foreman, technicians, scaffolders):

- Gabadi for construction work, welding, and management
- GTT for quality control and supervision

NP04 (handover on 7th January 2017)

start date 9th of January

last welding 1st September (34 weeks)


Scaffolding removal 11th October

NP02 (handover on 13th March 2017)

start date 13th of March

last welding 22nd September (28 weeks)

Scaffolding removal 10th October



Scaling to DUNE

Allocated time to outfit the cold cryostat components: 12 months (excluding the TCO closure)

This includes, leak testing, cleaning and DSS installation. Specialised personnel:

- 25 people for the major installation

- 10 people for the TCO closure

It's very likely that external companies will want to work (1 or 2 shifts) 6 days per week.

		#	T-0										Time Units are in Quarters-3 months																											
Task	Group	Month	-10	-9	-8	-7	-6	-5	-4	-3	-2	-1	0	3	6	9	12	15	18	21	24	27	30	33	36	39	42	45	48	51	54	57	60	63	66	69	72			
Logistics Facility	DUNE										LF infra	Logistics Facility Operations																												
Excavation Cavern #1	CF	41	North Cavern & CUC										BSI	BSI																										
Excavation Cavern #3	CF	20									South Cavern		BSI																											
Install Warm Dec #1	CERN	15											Warm 1																											
CUC Infrastruc and DAQ	DUNE	20											CUC Infra	DAQ																										
Install Cold Dec #1	GTT	12															Cold Struct. #1																							
Det #1 Installation Setup	DUNE	13															Det #1 Setup																							
Assembly SP Dec #1	DUNE	10																				Detector #1 SP																		
TCO Closing	CERN	2																						TCO																
Complete Detector #1	DUNE	3																																						
Purge/Fill Dec #1	CERN	18																									Pur													
Install Warm Dec #2	CERN	9															Warm 1												Fill Det #1											
Install Cold Dec #2	GTT	12																				Cold Struct. #2																		
Det #2 Installation Setup	DUNE	12																					Det #2 Setup																	
Assembly Dec DP #2	DUNE	10																										Detector #2												
TCO Closing	CERN	2																																	TCO					
Complete Detector #2	DUNE	3																																						
Purge/Fill Dec #2	CERN	20																																			Pur	Fill Det #2		
Install Cryo Equipment	CERN	36																																						
Estimated Number if FTEs Underground per shift-Assume 2 shifts per day																																								
CF-Day			80	80	80	80	80	80	80	80	80	90	90	80	80	40																								
CF-Night			70	70	70	70	70	70	70	70	70	90	90	70	70	35																								
LBNF/CERN-Warm-Day													25	25	25	25	25	25	25	25	20	20																		
LBNF/CERN-Warm-Night													25	25	25	25	25	25	25	15	15																			
GTT-Cold-Day																	25	25	25	25	25	25	25	25	25	25							10							
GTT-Cold-Night																	25	25	25	25	25	25	25	25	25	25							10							
LBNF/CERN-Cryo																10	10	20	20	20	20	20	20	20	20	20	4	4	4	4	4	4	4	4	4	4	4			
JPO-Underground Day												11	28	28	28	28	30	30	30	30	30	30	30	30	30	30	30	30	30	30	29	29	29	29	29	29	29	29		
JPO-Underground Night												11	28	28	28	28	30	30	30	30	30	30	30	30	30	30	30	30	30	30	29	29	29	29	29	29	29	29		
DUNE-Consortia-Day														10	10	10	20	30	36	36	36	36	36	36	36	36	36	36	36	36	30	20	5	5	5	5	5			
DUNE Consortia-Night														10	10	10	20	30	35	35	35	35	35	35	35	35	35	35	35	35	30	20	5	5	5	5	5			
SURF-Day			15	15	15	15	15	15	15	15	15	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20	20			
SURF-Night			5	5	5	5	5	5	5	5	5	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10			
Total FTEs Underground per Day Shift			95	95	95	95	95	95	95	95	95	121	163	163	163	133	105	150	155	155	150	150	130	130	130	105	105	89	89	89	93	73	58	58	58	58	58			
Total FTEs Underground per Night Shift			75	75	75	75	75	75	75	75	75	###	###	###	###	###	85	###	###	###	###	###	99	99	99	74	74	74	74	74	79	59	44	44	44	44	44			

Construction sequence

Assuming no co-activity inside of the cryostat and *simple access* to the cryostat (may conflict in some occasions with the clean room construction):

- Survey of the walls/floor/ceiling of the warm structure
- Installation of the scaffolding
- Marking and positioning of studs on the warm structure
- Installation of the first insulation layer (time consuming) including, flat joint panels, temperature sensors, pipes for GN₂ circulation, ...
- Sealing with *triplex* bonding of the secondary membrane
- Test with vacuum boxes the secondary membrane
- Completion of the first insulation layer
- Installation of the second insulation layer (time consuming)
- Fitting of the corrugated membrane and weld it vacuum tight
- Test of the corrugated membrane (global vacuum test) and helium sniffing
- Same for the TCO closure, but in small and confined space

Needed equipment

Number and type defined by the company selected to construct the cryostat insulation and containment system.

The company is in charge of the procurement of this material.

Type of equipment used at ProtoDUNE:

- Standard equipment (grinders, jigsaws, planners, drillers, sanders, stud welding machines, TIG welding machines, ...)
- Scaffolding and electric hoists
- Pallet trucks and carts
- Mastic mixing machines
- Triplex bonding machines
- Lifting hoists on the scaffolding and lifting fixtures
- Vacuum pumps and pressure sensors

Scaffolding

Laying on the floor (at most 23 ton/m²)

3. SCAFFOLDING

In order to ease the erection of the containment system it is recommended to use scaffoldings. These scaffoldings are usually fitted with retractable legs and platforms and a minimum of 3m height between two floors. The scaffolding design can be arranged according to the Containment System components dimensions.





Figure 2 – Scaffolding

Important note:

Maximum pressure allowable on panels during erection of Containment system is 23 tons per m² (~2.3bars).

Retractable feet



www.gtt.fr

Allow to reach 100%
of surface at the same time:
Possibility to work in parallel
on different places



Mastic application

Humidity and temperature sensitive process: samples of actually used glue analysed for QC

Manual (ProtoDUNE)



Automatic

www.gtt.fr



Amount of mastic depends on the position:
defined from the survey of the warm structure

Mastic will be distributed onto the panels to
increase the impedance to the GN_2 flow.


Triplex bonding machine

Manual (needed for the corner pieces)



- 100% of the glued sections visually inspected by GTT experts.
- Samples of the actually used glue are analysed.
- 100% of the glued sections tested with vacuum bags technique.


Automatic machine (possibly within flat panels)




www.gtt.fr

Welding primary membrane

Manual (ProtoDUNE)



Depending on the contractor company, automatic machines may be a possibility. Probably is a mandatory tool to meet the schedule constraints (requirement). Internal cryo pipes should be installed during the welding of the corrugated membrane



Material list


		Volume (m ³)	40" container number
including packing Insulation pannels and pads	Flat pannels	3823.71	80.93
	Corner Pieces	449.56	9.51
	Bridge Pad	281.64	5.96
	Trihedre	107.77	2.28
	Erection on Board	5.62	0.12
Membrane		53.89	1.14
	Membrane	521.61	11.04
	Angle Piece	12.08	0.26
	End Corrugation	0.32	0.01
Glasswool elements	FJ	278.70	5.90
Plugs	PG	29.54	0.63
Secondary barriers	SB	7.18	0.15
Thermal Protection	TP	2.42	0.05
Load bearing Mastic	Mastic	47.94	1.01
Adhesive for primary blocks and TBP Bonding	Adhésif	10.39	0.22
Glue for secondary barrier	Glue	4.07	0.09
Studs	studs	26.04	0.55

TANK DIMENSIONS					
	S229				
	L (m)	I (m)	h (m)	surface (m2)	volume (m3)
Secondary	63.58	16.68	15.58	4,621.93	1,848.77
Primary	62.78	15.88	14.78	4,319.08	1,684.44
At membrane level	62.00	15.10	14.00	4,031.20	


Assuming a packing factor of 70%
(for ProtoDUNE it was 50%-60%):

- For the insulation: ~750 boxes 3x1.5x1.3 m³
- For the membrane: <150 boxes 3x1.5x1.3 m³

Together with Ladia, to evaluate an alternative transportation solutions, investigating the possibility to bring the panels underground in boxes 1.22 m (L) x 1.02 m (W) x > 3 m (H).



240 brown boxes for insulation (~30%)
192 orange boxes for primary membrane
Additional boxes for special parts and tools



Quality assurance

During construction, GTT is in charge of ensuring that the insulation and the containment systems are installed according to the specification:


- Controls of the gaps within the panels, adherence checks of panels and of secondary membrane, laboratory tests of samples of the glue actually used.
- Test of the tightness of the secondary and primary membrane.

In addition:

- Constantly monitor the insulation pressure (leaks developing during detector construction)
- Helium leak tests of all the penetrations, flanges, and feedthroughs
- Helium leak tests with vacuum bags of corrugated membrane
- Final pressure tests

Insulation space

During detector installation




$P_0 = \text{atm}$

$P_1 = P_2 \sim 800 \text{ mbara}$

Constantly monitor P_1 and P_2

During detector operation



$P_0 > P_1$ and $P_0 < 350 \text{ mbarg}$

$P_1 = P_2 \sim 5 - 15 \text{ mbarg}$

Pressures regulated with valves

Leak checks

Warm structure:

All the weldings were checked spraying helium from one side and sniffing from the other

Secondary barrier:

Under-pressure tests were performed before continuing the installation of the insulation

Primary membrane:

- Under-pressure tests of the primary and secondary insulation spaces
- Insulation spaces filled with helium and sniffing 100% of the welding (ProtoDUNE ~1 km/cryostat)
- Few welding imperfections found (very typical) fixed and inspected with dye penetrant
- Second round of He sniffing found no leaks
- He leak checking with 'vacuum bags' on most of the weldings (GTT will adopt this method)
- Sensitivity between 5×10^{-9} - 5×10^{-8} mbar l/s over a welding length of 40 cm
- No leak found in NP04 and NP02 with this method.



Cleaning campaign

Cleaning of the internal membrane once the leak check campaign is finished:

- Installation of a (partial) false floor in the cryostat and insertion of man-lifts
- Cleaning with pressurised demineralise water+solvents and acids
(need water -2 m³ for ProtoDUNE- and need to pump it up once the cleaning is finished)
- Remove sharpie marks, silicon traces, possible glue traces, clean weldings and degrease

After declaration of the cryostat as clean room:

- Maintain the cleanliness of the cryostat with regular cleaning campaign
- During detector installation, further cleaning and protection of parts difficult to reach

