# **Clean Room Layout**

Justin Freitag Installation Planning Feb. 4, 2020












### **Overall Clean Room**




# **Clean Room Footprint**



### **Overall Clean Room - Iso View**



#### **Overall Clean Room Dimensions**



- Clean Room:470m<sup>2</sup>


- Material SAS:  $64m^2$ 

- 4910L Personnel SAS: 47*m*<sup>2</sup>

- 4850L SAS: 25*m*<sup>2</sup>

**Footprints** 


#### Clean Room Areas 4910L




# Personnel SAS (4910L)

SAS for gowning up in preparation for entering clean room.

(11.6mx4mx3.5m)



# Personnel SAS (4850L)



#### **Material SAS**

Clean room doors sized for APA on carts. (4mx8m)


Removing APA protective covers and cleaning all other components prior to entering clean room.

(8mx8mx9m)



#### **PD** Installation

Lifts needed to access sides of APA and centers of front or back face




### **APA Assembly Towers/Platforms**


Assembly towers with 8 total stations for APA assembly.

Elevated platforms for installing electronic equipment.


APA fixtures with stabilizers.



# **APA Assembly Towers/Platforms Access**



# **APA Assembly Towers/Platforms**



# **APA Assembly Towers/Platforms**



### FC/EW Assembly Area

Space for field cage installation on carts

End wall assembly


Workspace and component delivery crates



# **CPA Assembly**

Storage area for CPA components crate


Specific tooling/ other hardware



### **CPA Assembly Tower**

CPA panels lifted onto CPA assembly tower with overhead crane/hoist


CPA assemblies moved to TCO beams




### TCO/DSS

Detector elements entering the cryostat


Used for assembly of FC/GP to CPA



# **Cold Boxes**




### **Cold Box Roof Access**



#### **General Comments**

- Bridging the gap
  - Cold Box & TCO beams from APA tower



#### **General Comments**

- Telescoping (projecting) bridge crane
  - Underhung crane with secondary bridge that extends beyond the end of main bridge
    - Eliminates need for installing splice beams

