



1/4


# Status of the Veto System of JUNO

João Pedro Athayde Marcondes de André for the JUNO Collaboration

IPHC/IN2P3/CNRS

July 30<sup>th</sup>, 2020

#### The JUNO Detector



### Top Tracker (TT)


- Precise  $\mu$  tracker
- 3 layers of plastic scintillator
- ullet  $\sim$  60% of area above WCD


## **Water Cherenkov Detector (WCD)**

- 35 kton ultra-pure water
- 2.4k 20" PMTs
- ullet High  $\mu$  detection efficiency
- Protects CD from external radioactivity
- $\rightarrow$  Central Detector (CD)  $\bar{\nu}$  target
  - Acrylic sphere with 20 kton liquid scint.
  - 18k 20" PMTs + 26k 3" PMTs
  - 3% energy resolution @ 1 MeV

### Water Cherenkov Detector status

- Ultra pure water system:
  - Keep temperature and water quality
  - Start to install water pipes this year
  - ▶ 100 t/h system to be ready in 2021
- Bird cage: under production
- Liner:
  - Keep rock and water separate
  - Prevent Rn contamination from rock
  - ► Finishing installation tests
- Tyvek: same as Daya-Bay, prep. bidding
- Earth Mag. Field compensating coils:
  - reduce B on PMTs to  $< 5 \mu T$
  - ready for production
- PMT: use 2.4k of JUNO's 20" PMT
- All components ready or in production







**Pool liner** 







Bird cage &Tyvek reflection film



EMF coils

# Top Tracker (TT) status

- TT refurbished from OPERA Target Tracker
  - ► Detector granularity 2.6 × 2.6 cm² in X–Y
    - ★  $0.2^{\circ}$  median resolution for  $\mu$  tracks
  - No aging of scintillator observed since OPERA
  - ▶ TT modules already delivered to JUNO site
  - Mechanical structure for TT re-designed
    - ★ ready to start mass production
  - New electronics chain
    - ★ FEB (w/ MAROC3): 1200 cards produced & tested
    - \* ROB: design being finalised, review in 2020
    - ★ Concentrator (L1 trigger): testing prototype
    - ★ L2 trigger card: design just started
- TT will be on time for JUNO



