


# BPMs for E-Coolers and E-Lenses at CERN

L. Søby

# Outline




- Status of Ecooler BPMs
- Status of CERN HEL BPM design
  - BPM
  - Acquisition system
- Proposal for Test stand BPM
- Summary

# A CERN E-cooler





Pbar (Pb) and electron beams in same direction

# AD E-cooler BPMs



Drift tube with bakeout equipment and coil

## AD e-cooling





Dismantling of AD ecooling 25112005 (jh)

# BPMs in CERN E-coolers


	LEIR		AD		ELENA	
	E-Beam	Pb beam	E-Beam	Pbar beam	E-Beam	Pbar beam
Current	1-2.5A	1E11 Ch	1-2.5A	4E7 Ch	2-5mA	1E7
Energy	2.3keV	4.2-72 MeV	27keV-3.1keV	3.5-0.1 GeV/c	355-55eV	5.3-0.1 MeV
BPM	Electrostatic; ~500 pF		Electrostatic, ~700pF		Electrostatic, 20pF	
Dimensions	ID=140mm	L=190mm	ID=140mm	L=190mm	ID= 51mm	L= 100mm
Front-end	High imp. voltage amp.		High imp. voltage amp.		Charge amplifier	
In Orbit acquisition	Yes		No, but on the way		Yes	
Ebeam modul.	(Intensity) and energy		Energy modulation only		Intensity and energy	
E-beam acq.	Yes, oscilloscope/OASIS		No, but on the way		Yes OASIS+APP	

- Electrostatic BPMs used everywhere.
- E-coolers works with un-bunched beams, but bunching of Pbar (Pb) beams needed to determine position inside the e-cooler.
- Modulation of E-beam needed to measure E-beam position.
- Measurements of two beams done separately, slow process.
- ELENA is at present, only system operational with intensity modulation (100kHz with transformer from LEIR)
- If intensity modulation on revolution frequency can be implemented, acquisitions can easily be integrated into acquisition systems of the 3 machines.

# 100kHz intensity modulation of E-beam in ELENA




# LEIR E-Beam BPM measurements (Intensity mod.)



Different scales

HOR CH01 (delta) and CH02 (sum) noise measurement and with electrons

# HEL BPM



2 BPMs for Hollow Electron Lens

Proton and electron beams counter rotating



# HEL BPM Specifications:

	Proton beam	Electron beam	Comments
Intensity	5E9 (2.1A) / 2.5E11 (63A)	1 / 5A	
Bunch / Pulse length	1ns	1-86us	P=4 $\sigma$ ; E_beam off 3us; tr = 200ns
Relativistic $\beta$	1	0.19-0.24	E <sub>Beam</sub> Low $\beta \sim 5 * \text{charge density}$
Resolution	100um / 20um	100um / 20um	
Relative accuracy	100um		Between beams
Absolute accuracy	500um	500um	
Max beam displacement	4mm	4mm	
Time resolution	>1s?	>1s?	
Inner diameter	60mm		
Max. outer diameter	120mm		


- **Functional specifications :**

- E\_beam on/off, 1 to 3 times per turn
- E-beam on/off either between LHC trains or within their internal structure coming from the SPS.
- Injection and on high energy stable beams
- **Single bunch and pilot**

# HEL BPM design

50 ohm strip line


- Profit from counter rotating beams and directivity.
- First simulations on 3D design done by Manfred.
- Improvements in RF performance needed.



# BPM signal summery


BPM	Electron beam on/off	Gaussian $2.5 \cdot 10^{11}$ , 0.25ns	Gaussian, $2.5 \cdot 10^{11}$ with $\sim 25$ MHz LP filter
Button	0.04vp	63Vp	$\sim 0.65$ V
Strip line (0.2m, $45^\circ$ )	0.22Vp	200Vp	$\sim 0.45$ Vp
Strip line (0.4m, $23^\circ$ )	0.2V	88Vp	0.2V
Electrostatic ( $75^\circ$ )	0.8Vp	$\sim 200$ Vp	$\sim 0.4$ Vp

# Hel Acquisition system with VFC+FMC




- Need to measure two beams simultaneously
- Frequency separation not possible
- Measure electrons when no Proton's.
- Need timing from gun

# Hel Acquisition system with DOROS



# Test stand BPM: LHC BPLX



- Two spares on stock
- Dimensions close to HEL design
- Acquisition with oscilloscope

# Summary:

- **Injector E-coolers:**
  - Use electrostatic BPMs
  - Only ELENA is operational with intensity modulation
  - Intensity modulation at revolution frequency would enable E-beam position acquisitions
    - Need to buy 2 more transformers
  - AD analogue acquisition system being completed
- **HEL BPM**
  - 3D design exist and has been simulated.
  - Needs to be improved
  - 2 Proposals for acquisition systems
- **Test stand BPM**
  - Spare LHC BPLX will be installed in March
  - Acquisition with oscilloscope