



### **ELENA Ring: test and preparation**



### From C. Carli@ECC March 2019



## First Ideas on Activities with Beam in LS2 (Input for a Discussion and instead of Conclusions)



- Aims of possible tests in 2019 mainly preparation of transfer line commissioning in 2020
  - $\hfill\square$  Demonstration of reliable source operation at 100 keV with upgraded isolation transformer
  - Investigations on intensity fluctuation along pulse: requires line to ring for observation on 1<sup>st</sup> ring pick-up (can one increase the pick-up saturation level for this pick-up?)
  - □ Increase of intensity from source (sufficient intensity of extracted bunches for line commissioning possibly with scraping to adjust emittances)?
  - $\Box$  H<sup>-</sup> injection matching (BTV after septum and possibly observation in SEMs)
  - □ Probably not possible (but would be of interest!): injection tests to optimize efficiency (even without RF), tests with beam on SEM in GBAR line
- Test period in autumn? (plus earlier tests with source alone at 85 kV)

- Aims for 2020
  - □ Commissioning of transfer lines to experiments in "old" experimental zone with H-
    - Profile monitors mandatory!!
    - Requires sufficient intensity H<sup>-</sup> within appropriate transverse emittances
    - Show control of beam along lines and arrival with expected characteristics at the last monitor
    - Magnetic stray fields and shielding: plans for investigations and, possibly ?
  - □ Possible other tests with H<sup>-</sup> and/or proton beams from source?
    - Electron cooling with protons or H<sup>-</sup>
    - Lattice control and understanding, (loss on ramp at low energy?) ...
    - Acceleration, deceleration ...

### **Christian Carli**



### Achievement

### First Ideas on Activities with Beam in LS2 (Input for a Discussion and instead of Conclusions)



- Aims of possible tests in 2019 mainly preparation of transfer line commissioning in 2020
- Demonstration of reliable source operation at 100 keV with upgraded isolation transformer
  - Investigations on intensity fluctuation along pulse: requires line to ring for observation on 1<sup>st</sup> ring pick-up (can one increase the pick-up saturation level for this pick-up?)
- Increase of intensity from source (sufficient intensity of extracted bunches for line commissioning possibly with scraping to adjust emittances)?
- □ H<sup>-</sup> injection matching (BTV after septum and possibly observation in SEMs)
- Probably not possible (but would be of interest!): injection tests to optimize efficiency (even without RF), tests with beam on SEM in GBAR line).
- Test period in autumn? (plus earlier tests with source alone at 85 kV)

ELEN/

CERN

- Aims for 2020
  - □ Commissioning of transfer lines to experiments in "old" experimental zone with H-
    - Profile monitors mandatory!!
    - Requires sufficient intensity H<sup>-</sup> within appropriate transverse emittances
    - Show control of beam along lines and arrival with expected characteristics at the last monitor
    - Magnetic stray fields and shielding: plans for investigations and, possibly ?
  - □ Possible other tests with H<sup>-</sup> and/or proton beams from source?
    - Electron cooling with protons or H<sup>-</sup>
    - Lattice control and understanding, (loss on ramp at low energy?) ...
    - Acceleration, deceleration ...

#### **Christian Carli**



## Planning for 2019-2020



ELENA

**ERN** 

# First Ideas on Activities with Beam in LS2 (as input for a discussion)





 Test with beam in 2019 delayed by HV transformer and mainly used for Profile monitors tests



### Plan for 2020



- Aim for 2020 did not changed:
  - First priority : commissioning of ALL transfer lines with Hminus
- Pre-requisite:
  - Installation of TLs completed: Profile monitor mandatory
  - Restart of the ELENA ring with RF
- Extra constraints on beam request:
  - Test of Profile monitors electronics V3 with Hminus before production
    - => test in LNE50 as in 2019 if needed
  - Availability of RF experts to test new LLRF to be deployed in AD



### **Restart of the source (April)**



- Operational conditions:
  - As soon as TL cabling is completed => unlock-out in April
  - Beam up to BTV => compatible with access in the machine with the same conditions as in 2019
- Aim: complete what is left over from 2019
  - Reliable operation of the source at 100 KeV
  - Increase intensity, reduce intensity fluctuations
- Test Plan:
  - Establish operation @ 100 keV in DC mode, test of the pulsed mode?
  - Test of the Profile monitors electronics V3 in LNE50?
  - Improve injection efficiency, Injection matching studies
  - HW test of the ring: B-train, pause, etc...



### **Restart of the ELENA ring**



- Operational conditions:
  - As soon as access system is validated (beginning of May)
  - Circulating beam in the machine with RF ON (bunched beam) and possibly accelerate => NOT compatible with access in zone
- Aim:
  - Prepare TL commissioning: establish cycle(s), test of instrumentation
  - Test new LLRF development (mandatory for AD restart)
- Studies:
  - Caracterisation of the beam at 100 keV: intensity, lifetime, emittance
  - Optics studies: kick response, working point optimization...
  - Debug of all software change...



### **ELENA ring: May-July**



- Establish the different cycles needed in 2020:
  - Extraction cycle for TL commissioning to optimize repetition rate: injection plateau length driven by ion switch pulsing time
  - Establish acceleration/deceleration cycle for LLRF test
  - Long plateau at 100 KeV for studies and debugging
- Restart/commissioning of instrumentation:
  - Intensity in the ring and in the TL: longitudinal pick-up
  - Orbit measurement, orbit correction, kick response
  - Tune measurement  $\rightarrow$  test of the repair
  - Beam emittance and shaping : scrapers
  - All RF diagnostics
    - => test, test, test







### **ELENA ring**



- Setting-up of the multi-bunch extraction:
  - Test of timings, synchronisation
  - => to be planned as soon as possible but need the SEM electronics
- Whenever possible:
  - Validation of new settings management
  - Lattice control and understanding: optics studies
  - Investigation of losses in the ramp
  - Test and implement beam properties measurements: coupling/chroma measurement and correction, injection oscillations with Hminus
  - E-cooling magnetic elements influence on beam orbit
- => OP tests that can be performed anytime no access in the machine



## **Planning and organization**



• The operation tem will be on duty in the ACR during working hours from May to end of the year:

- As soon as the machine switched to access with key

 Monday morning briefings when required from March, weekly from May on to handle co-activities

- Planning to be scrutinized to arrange different activities:
  - Priority is clearly TL commissioning
  - but :
    - Extraction towards LNE50 needed for profile monitors test in May
    - Couple of weeks with circulating beam are needed before July