


# Description of the DFX device, scope & interfaces


P. Cruikshank on behalf of the WP6a team 3 March 2020

Production Readiness Review of the DFX


# WP6a - DFX




Interface between **SC Link** and **Diodes Cold Module** of the **HL-LHC Inner Triplets** 




# Extract from DFX integration review June 2019





## DFX - WP6a



DFX CDR - xxxx DFX DDR - xxxx

#### 5 DFX & 5 DFM cryostats required:

- Connection of MgB2 SC link to NbTi leads of cryomagnets in LHC tunnel
- In-kind contribution from UK via collaboration with Southampton University (design & manufacture).
- Supply of DFX prototype within UK1
- 4 DFX series & 5 DFM series in UK2 (not yet signed)

#### DFX prototype usage at Cern:


- Prototype test of cold power system (SC link, DFHX)
- HL String
- Stored as HL operational spare.

#### Design & Manufacturing:

- According to harmonized standards EN 13445
- Compliance with PED 2014/68/EU.
- CE marking (not 'modified approach' cf HSE advice)
- All quality records to be put in MTF




# DFX planning – get latest from Amalia





## **DFX documentation for PRR**




All items shall be released prior to start of production



# **Interfaces overview**


- Tunnel, supports & BeamSCLink interface
  - Leads + Instru
  - Leads + instru
  - Jackets flanges
     DCM interface
  - Leads + Instru
    - Jackets flanges
  - QXL interface
    Vacuum jacket flange
  - Cryogenic lines
  - Instrumentation
  - Sensors supports + IFSSplices + bus bars support
  - External services
  - Vacuum equipment
  - Pressure relief devices
  - DFX interfaces
    - Outer & Inner jackets
    - Cryogenics
    - SupportsExternal accessories
    - Instrumentation & cables/splices





PRR DFX - 03/03/2020 - P.Cruikshank

## **SCLink interfaces**

- Vacuum & Helium jackets
  - LHCDHTLP1190
  - Helium jacket end
    - Ø200 x 700 mm + NbTi bus bars
  - Bus bars
    - Design of supports between bus bars descoped from prototype deliverables
    - DFX shall present mechanical interfaces in
      - helium vessel
        - LHCLDQD\_0003
- NbTi-NbTi splices
  - Fixed to helium vessel
    - LHCLDQD\_0003












### **DCM** interface

- D1-DFX Connection Module (DCM)
- Vacuum & Helium Jackets
  - ISOK-DN630 with standard O-ring
  - Lip weld
  - Interface Drawing: LHCLDQD\_0002
- Bus bars

De-scoped from prototype









#### **DCM** interface: Lambda Plate

- Bus bars overview (see dedicated talk)
- Λ-Plate design based on LHC experience:
  - ΔP=20 bar
  - Nominal operation 1.9K
  - Thermal cycle : 50
  - Insultation @ RT : 4.6 kV
  - Overall leak rate @ RT : 1.10<sup>-4</sup>mbar.l.<sup>-1</sup>


#### R&D activities:


- Demonstrator completed
  - 6 kA type plug manufacturing R&D complete
  - 18 kA similar type plug being qualified
- Plug Lab complete
  - Plasma treatment machine
  - Soldering post
- Thermo-mechanical results
  - 100% 6 kA plugs @ 1.10<sup>-10</sup> mbar.l.s<sup>-1</sup> after 10 Thermal cycle and Pressure test (electrical qualification pending)
  - 80% 18 kA demo plug @ 1.10<sup>-10</sup> mbar.l.s<sup>-1</sup> after 5 Thermal cycles
- Final configuration in progress
  - 6 kA manufacturing procedure complete
  - MQXF cable plug being developed
  - Manufacturing & qualification procedures being finalised
  - Final qualification with current during System test 2020



			Cable type		
	I <sub>cable</sub> [kA]	N <sub>cables</sub>	Triplet side	Plug	DFX side
MQXF	18	2	18 kA Nb-Ti round		
MBXF (D1)	18	2	13 kA Nb-Ti flat	2 x MQXF leads	See J.Fleiter talk Round
Trims	7	3	18 kA Nb-Ti round		Round
MCBXF%	2	12	6 kA Nb-Ti round	LHC 6 kA	See J.Fleiter talk







Courtesy S.Donche & E.Andrews

### **DCM** interface: Lambda Plate

#### Status:

- Plug prototype production is up and running (procedures, tooling & equipment)
- Integration constraints shall now be studied
  - Up to 6m long leads
  - MQXF cable (proto with 13 kA LHC cable)
- Qualification procedures for series to be finalised
  - Individual follow-up & results archiving in place
  - Manufacturing procedures uploaded to EDMS

#### Production Plan

- Prototype expected by end of 2019
- Injection moulds, Peek & SS parts sub-contracted
- Assembly & qualification (thermo-mechanical + insulation) at CERN

Traceability



Leak test <1.10<sup>-8</sup>mbar.l.s<sup>-1</sup>



Pressure test 1 h at 30 bara



Cable opening Cleaning Plasma treatment



Injection (800 mbar) under vacuum (<1mbar) of pre-heated parts (40°C)



Thermal cycles X10 to 77K






Demoulding

8603/tesy25. DoRohe WEXAMERWS

## **Cryogenics interfaces**


- Jumper interfaces
  - Cryogenic lines defined for DFX
  - Still discussions on DCM new module TS line
  - Jumper location above the QXL
  - DN250, longitudinal position TBC
- Temperature sensors supports
  - Interface long CERNOX
- Heaters Vishay® RH100 interfaces
- Level gauges interfaces
- DeltaP gauge pneumatic fittings to be agreed
- Pressure relief devices
  - See safety dedicated talk





## Insulation vacuum interface


- SCLink insulation vacuum volume
  - Pumping equipment :
    - valve + turbopump + primary pump
    - LHCVPGFY0001
  - Gauges interface
    - 3 gauges on one ISO DN100
    - LHCVA 0076
  - Relief plate interface
    - ISO-K DN100
    - LHCVV 0011
- DFX insulation vacuum volume
  - Pumping equipment
    - Valve + Turbopump + Primary Pump
    - LHCVPGFY0001
  - Gauges interface
    - 3 gauges pn pne DN100
    - LHCVA 0076
  - Relief plate interface
  - HILLHE PROJECT ST0705009\_01




#### Instrumentation interface

- Mechanical supports
- Wire Instrumentation Box (WIB)
- IFS
  - (CERN design & supply)
  - 3 Flanges
  - 5 tubes sorted by functions
    - 190 V-taps
    - 32 T-wires
    - 8 power wires
- Vacuum instrumentation feedthrough ISO DN100










# **Civil Engineering & Transport Interfaces**


- CERN responsible for supports design to ground/ceiling in the tunnel
- Conceptual proposal to ceiling and ground being discussed at CERN
- DFX interfaces
  - Civil engineering : threaded blocks
  - Transport : adequate lifting points compliant with design
  - Tooling not defined today



On going studies for load transfer to civil engineering











# **Assembly and P.Test configurations**

Need latest images/x-sections





- System fully assembled in UK to validate assimilability perform pressure test and all pressure configurations.
- To avoid welding/cutting operations at lip welds in UK, the design permits the closing of the helium vessel with elastomer seals prior to cable integration at Cern.
- CE marking is removed at Cern prior to the welding.



# **Summary**

