



Cryomodule alignment

AUP-Canada-CERN-UK meeting 2020.03.13

Vivien RUDE, Mateusz SOSIN

Outline

- **Reminder – Cryomodule alignment activities**
- **CRAB alignment – coordination between CERN and Canada/UK teams**
- **Current schedule discussion**
- **Summary**

Alignment activities

CRAB cryomodule alignment (based on SPS DQW prototype)




- **Measurement on the associated infrastructures (string trolley, cryostat assembly gantry, test sites)**
- **Workflow (Assembly of the Crab-cavity string)**
 - Determination of the mechanical axis → Capacitive plate of the cavities
 - Fiducialisation of the Dressed Cavities
 - String line assembly in clean room
 - (Installation of the others components on the string line)*
 - Final alignment of the string line
 - Installation of the top plate (supporting plate of the string line)*
 - Insertion of string line in the cryomodule
- **Installation of FSI system**
 - Calibration of FSI feedthrough
 - Installation of FSI feedthrough on the cryomodule
 - Installation of FSI targets
- **Validation at warm and cold conditions**
 - Validation at warm
 - (Impact of vacuum on the string line)*
 - (Impact of transport on the string line)*
 - Validation at cold condition

*To be discussed/agreed
if required

Reminder - Workflow (Assembly of the Crab-cavity string)




- Determination of the mechanical axis → Capacitive plate of the cavities
- Fiducialisation of the Dressed Cavities
- String line assembly in clean room
- Installation of the others components on the string line
- Final alignment of the string line
- Installation of the top plate (supporting plate of the string line)
- Insertion of string line in the cryomodule

Vivien RUDE, Review of HL-LHC Alignment and Internal Metrology
26-28 August 2019, CERN



Reminder – Installation of FSI system

- **Assembly measurements of the DQW prototype**
 - Measurement on the associated infrastructures
 - Workflow (Assembly of the Crab-cavities)
 - **Installation of FSI system**
 - Calibration of FSI feedthrough
 - Installation of FSI feedthrough on the cryomodule
 - Installation of FSI targets
 - Validation at warm and cold conditions
 - Installation of the DQW prototype in SPS tunnel



3D measurement of :


- Dressed cavities
- FSI targets

Reminder - Validation at warm and cold conditions


- Validation at warm (1)
- Impact of vacuum on the string line (2)
- Impact of transport on the string line (3)
- Validation at cold condition (4)




1 Radial position (relatif with respected to AT401 measurement)



2



4



CRAB alignment – coordination between CERN and Canada/UK teams



- **Needed contact with persons in charge, to agree the alignment know-how transfer / surveyors training**
 - **With help of CERN personnel in Canada/UK or Training in CERN?**
- **Dates of FSI interferometers readiness for Cryomodules FSI systems validation after assembly (1x for Canada; 1x for UK), including:**
 - **Interferometer operators training**
 - **FSI equipment handling Training**
- **Delivery of FSI equipment (Feedthroughs, Reflective targets, target supports) – according to current planning?**
- **1x PJAS for CRAB alignment related activities: mid 2021 – mid 2024**

Schedule

01/10/2019

Trainings/ know-how transfer?

WP4 - Baseline November 2019



Summary

- **Information on CERN, Canada and UK alignment team coordination needs to be agreed**
 - Dates of trainings and know-how transfer
- **FSI interferometers delivery to be confirmed (needed for in-CERN production coordination)**
- **Dates of FSI equipment production, testing, calibration and delivery**
 - Is current planning up to date?
 - Impact on CERN personnel work planning (tests, calibration)