



## Crab Cavities - current status

Marco Spitoni

HL-LHC / Work Package 9 / Heat Load Working Group

CERN, 05/May/2020

# Process Flow Diagram

EDMS 2013776 v.3.1

## Thermal shield (60-80 K)

Instrumentation plate  
Cold to Warm Transitions thermalization

## Beam screen (4.5-20 K)


Fundamental Power Coupler thermalisation  
Cold to Warm Transition thermalization  
Dedicated circuit for each cavity

## Warm-up line (60 K)

1 g/s for warm-up to 60 K in 1-2 h  
First proposal for valve size  $\rightarrow K_v = 0.05$

## Protection system

CV to header D  $\rightarrow$  recommended  $K_v = 1.5$   
SV to air  $\rightarrow$  recommended ID 10 mm  
BD to air  $\rightarrow$  100 mm for  $\sim 1$  kg/s




He II bath at 2 K ; 30 mbar

# Jumper cross-section

## Latest cross-section and pipes ID

| Pipe name                      | Chosen ID (OD) [mm] | Remarks            |
|--------------------------------|---------------------|--------------------|
| E <sub>H</sub> E' <sub>H</sub> | 14 (17.2)           | T.S. circuit       |
| E' <sub>H</sub> F <sub>H</sub> | 14 (17.2)           | T.S. circuit       |
| CC'                            | 8.2 (10.2)          | B.S. circuit       |
| KD                             | 8.2 (10.2)          | B.S. circuit       |
| CS                             | 18.1 (21.3)         | Cool down/warm-up  |
| CY                             | 10.3 (13.5)         | Driven by HEX size |
| XB                             | 60 (63)             | Pumping line       |



Hydraulic calculations showed no issues with proposed diameters