

# Review of heat to air for CLIC module thermal simulations

Markus Aicheler

28.10.2020




# Disclaimer

- Went back in Indico all the way to mid 2017 when we were starting to think about this
- Not once Pedro uploaded a presentation stating that he assumed this or that for his projections
- Hence only secondary information is available and we need to reverse engineer


# FEA thermal simulations for SAS

- ANSYS Thermal steady-state analysis
- Single SAS without loads
- Run time: ~5min
- Heating power 860 W
- Cooling water 27 °C, 1.3 l/min
- Ambient T = 20...40 °C
- Convection  $HTC_{air} = 7.5 \text{ W/m}^2\text{K}$
- Radiation to surrounding "space" (T = 18°C)  
(no surface-to-surface effect)

A: STEP 0 - SASambient20  
Temperature  
Type: Temperature  
Unit: °C  
Time: 1  
07/11/2017 10:24



# Domain



# Flow conditions

- Water in temperature 27 degC
- Water flow rate 1.3 L/min
- Air in temperature at 21, 25, 30 and 35 degC
- Air in speed 0.4 m/s

## Heat loads

Antti Moilanen  
01.06.2019

Components are heated with heat elements.



**Assume: increasing 50Hz to 100Hz doubles the heat generation in RF components**

Two cases studied here:

RF@50Hz, Unloaded

		Heating power (W)	
CL	16x	168	2688
PETS	4x	11	44
SAS	4x	780	3120
DBQ	2x	171	342
WG	4x	88	352
<b>Total</b>			<b>6546</b>



≈ 2.8 kW/m



RF@100Hz, Unloaded

		Heating power (W)	
CL	16x	336	5376
PETS	4x	22	88
SAS	4x	1560	6240
DBQ	2x	171	342
WG	4x	176	704
<b>Total</b>			<b>12750</b>

≈ 5.4 kW/m




\*simulation is done with 2m long model but results divided by 2.35m

Results: 50Hz vs 100Hz

Antti Moilanen  
01.06.2019

Heat to air: for different water flows




Markus:  
I am pretty sure Pedro  
chose "double nominal"  
hence blue

Results: 50Hz vs 100Hz

Antti Moilanen  
01.06.2019

Delta T: for different water flows





# Cooling and Ventilation Studies for CLIC

## P. Cabral, M. Nonis (CLIC - Note - 1164)

- 4.3. Demineralized Circuits

- The working temperature ranges between 27 degC at the equipment inlet and 35 degC at its outlet.

- Annex G - Cooling Heat Loads

- Main Tunnel - Two-Beam: Refrigeration Heat Load: 18563 kW

- Annex H - Cooling Water Circuits

The secondary demineralized water circuits are presented below.

Sector	Drive Beam-Based Machine							
	Circuit	Flow Rate	Cooling P.	DN	ΔP Linear	Piping L.	Delta P.	Pumps
		m <sup>3</sup> /h	kW	mm	Pa/m	m	bar	kW
1	Drive Beam Injector U	577	5356	300	125	5500	7	133
	Drive Beam Injector S	1529	14191	450	150	5500	6	325
	Frequency Multiplication Circuit a)	349	3238	250	150	1500	6	70
	Frequency Multiplication Circuit b), CR1 S, CR2 S and Transfer Line - CR2 to J.P.	1811	16811	450	200	4000	6	396
2	Accelerator - LINAC (Two-Beam Machine)	1000	9281	400	125	10000	4	121
		1000	9281	400	125	10000	4	121
	Main Tunnel (other equipment, Two-Beam Machine)	1847	17150	500	125	12000	4	225
		1847	17150	500	125	12000	4	225
	Drive Beam Dumps (Tertiary Circuits)	57	533	125	150	200	4	7,6
	Main Beam Dumps (Tertiary Circuits)	296	2746	200	250	200	4	41,1

# The Compact Linear Collider (CLIC) Project Implementation Plan

- "A total of 2976 modules are required for the two Main Linacs" (5.3.2. The Drive-Beam-based Module)
- "For each of the 2976 Main-Beam modules (380 GeV stage) ..." (5.15.4. Conclusions)
- (section 6.3.) 18.6 GW cooling power

With 2000m<sup>3</sup>/h

Table 6.2:

Sector	Structure	Two Beam Machine		Klystron Machine	
	Name	Cooling Power	Flow Rate	Cooling Power	Flow Rate
		MW	m <sup>3</sup> /h	MW	m <sup>3</sup> /h
1	Drive Beam Injector U	5.4	580		
	Drive Beam Injector S	14.2	1530		
	Frequency Multiplication Circuit a)	3.2	350		
	Frequency Multiplication Circuit b), CR1 S, CR2 S and Transfer Line - CR2 to J.P.	16.8	1820	—	—
	Chillers Refrigeration - Drive Beam Injector S/U, Frequency Multiplication Circuit 1, RF Distribution Circuit 1,2 and 3	9.9	1070		
	Chillers Refrigeration - CR1 S, CR2 S, Frequency Multiplication Circuit 2, 3, 4 and Transfer Line - CR2 to J.P.	1.8	200		
	Accelerator - Klystron	—	—	25	2670
Accelerator - LINAC	18.6	2000	27	2930	
Main Tunnel (other equipment)	34.3	3700	24	2610	
2/3	Injection Hall and Transfer Lines - e+/e- , Loop, J.P to S.P (P&ID Circuit B)	5.9	640	5.9	640
	Detectors S	0.9	100	0.9	100
	Detectors U	2.0	230	2.0	230
	Chillers Refrigeration - Buildings IP	1.7	190	1.7	190
	Chillers Refrigeration - Main tunnel	5.3	580	7.0	750
	Chillers Refrigeration - Detectors Hall S/U, Injection Hall, Transfer Lines - Loop and J.P. to S.P. (P&ID Circuit A)	2.2	240	2.2	240
	Main Tunnel Purge	1.2	130	3.6	390

# Available Water per Module

- 2000 m<sup>3</sup>/h demineralized water  
=  $2 \times 10^6$  L/h
- For each module:  
 $2 \times 10^6$  L/h / 2976 modules / 60 min/h  
= 11.2 L/min per module