



Power refrigeration at 4.5K & 1.8K for the LHC

S. Claudet, CERN AT-ACR




Content

- Introduction
- Required capacity and system architecture
- 4.5 K Refrigerators and 1.8 K Units
- Recent achievements
- Conclusion



Introduction

Long tradition and experience with cryogenics and refrigeration



LHC, the largest helium refrigeration system ever built





Basic choices, design criteria

- Re-use of ex-LEP refrigerators to be upgraded for LHC requirements
- Site constraints for infrastructure => 5 islands
- 1.8K Refrigeration units to be connected to all types of 4.5K refrigerators
- General features:
 - Cool-down & Warm-up: 600kW
 - No global redundancy but doubling critical items
 - Impurities: continuous capacity for 50 ppm(v) air, water



Layout of LHC Cryogenics





Content

- Introduction
- **Required capacity and system architecture**
- 4.5 K Refrigerators and 1.8 K Units
- Recent achievements
- Conclusion



Heat loads for a sector

Early heat load inventory and follow-up, periodic update of cryogenic architecture and distribution scheme

Qs: Static heat leaks
Qd1: Dynamic « current »
Qd2: Dynamic « beam »

Required capacity = $F_o \times (F_u \cdot Q_s + Q_d)$

- Fu: Uncertainty on static loads
- Fo: Overcapacity



Demands in refrigeration

- Evaluation of heat loads (static, dynamic)
- Required capacity with appropriate margins
- Conversion in Demands for Refrigeration
- Process studies to validate feasibility





Figure 2: Simplified cryogenic block diagram for a high-load sector including cryogenic interconnection box, 1.8 K refrigeration unit and refrigerator.



Possible cooling cycles




- Installed capacity:
125 g/s @ 15 mbar
(i.e. ~2,4 kW @ 1,8 K)
- Turn-down capability: **1 to 3**
- Return temperature at the 4.5 K Refrigerator:
 - Reduced mode: ≤ 30 K
 - Installed mode: ≤ 20 K
- 'Stand alone' capacity check (B interface closed)
- Process & components identified as a challenge
- Validation prior to series (1+n)




Cryogenic architecture

Typical LHC even point





Checking all modes





Content

- Introduction
- Required capacity and system architecture
- **4.5 K Refrigerators and 1.8 K Units**
- Recent achievements
- Conclusion



Procurement strategy

- Sub-systems by type of functionality:
 - CERN defined interfaces and required performance

- Great majority procured from industry:
 - Competitive performance based tendering (capital and operation cost)
 - Detailed studies, manufacturing, site installation, commissioning, performance assessment

- Separate management of general services:
 - Interconnecting piping, controls, site utilities




Construction phase

- **Industry available products:**
(storage tanks, piping, 4.5K refrigerators)
 - Functional technical specifications adapted => tests
- **Extension of existing products**
(1.8K units, cryogenic lines, superconducting links)
 - Complex performance & possible impacts
 - CERN add. design & support to fabrication
- **Totally new products**
(Rad. tol. cryo thermometry - electrical feed boxes)
 - CERN with full responsibility for developments and “built to print” fabrication contracts



LHC 18 kW @ 4.5 K Refrigerator Compressor stations




Identical installation for both suppliers, i.e. all new 4.5 K refrigerators



LHC 18 kW @ 4.5 K Refrigerator


Process cycle for Air Liquide





LHC 18 kW @ 4.5 K Refrigerator



Process cycle for Linde





18 kW @ 4.5 K Refrigerators


33 kW @ 50 K to 75 K - 23 kW @ 4.6 K to 20 K - 41 g/s liquefaction





1.8K Refrigeration units

1.8 K Refrigeration Unit Cycles






2400 W @ 1.8K Refrigeration units



Diam:
250mm






Content

- Introduction
- Required capacity and system architecture
- 4.5 K Refrigerators and 1.8 K Units
- **Recent achievements**
- **Conclusion**



Progress overview



Legend

Cryogenic
Distribution
Line
TTTTTTTT

QSC_(A,B,C): Warm Compressor Station
 QSR_(A,B): Surface 4.5 K Refrigerator Cold Box
 QURA: Underground 4.5 K Refrigerator Cold Box
 QURC: 1.8 K Refrigeration Unit Cold Box
 QUI_(A,B,C): Cryogenic Interconnection Box

Electrical Feed Box
 Superconducting Link

Commissioned & accepted

Delivered / Under installation

Ordered (Contract placed)



Under commissioning

Under fabrication

Under definition





LHC sector 78 - First cooldown







LHC sector 78 - First cooldown - Tuning 1.9 K conditions





LHC sector 78 - First cooldown - 1.9 K normal operation





Conclusion

- It has been possible to design, built, install and validate all LHC refrigeration sub-systems
- Within a few weeks (2 to 6), the tuning with the 1st LHC sector has been made to allow magnet powering tests
- Early indications have to be evaluated (heat loads, response time, controls, availability)
- LHC commissioning: We are confident, and aware that it represents an enormous challenge with learning process, efforts and surprises!