

Readout Electronics of the LHCb SciFi Tracker

Jahrestreffen der deutschen LHCb-Gruppen


Daniel Berninghoff
Physikalisches Institut Heidelberg

06.10.2020

Bonn




Phase-I



- Single-arm forward spectrometer $2 < \eta < 5$
- Instantaneous Luminosity $\mathcal{L}_{\text{inst}} = 4 \cdot 10^{32} \text{ cm}^{-2} \text{ s}^{-1}$
- Detector readout rate $R = 1 \text{ MHz}$

Phase-I Upgrade




- Single-arm forward spectrometer $2 < \eta < 5$
- Instantaneous Luminosity $\mathcal{L}_{\text{inst}} = \frac{4}{20} \cdot 10^{32} \text{ cm}^{-2} \text{ s}^{-1}$
- Detector readout rate $R = \frac{1}{40} \text{ MHz}$
- Replacement of
 - » Front- and back-end electronics
 - » Vertex Locator
 - » Tracking Stations
 - » SciFi
 - » Upstream Tracker

Core Characteristics

Detector performance

- » Hit efficiency $\approx 99\%$
- » Hit resolution $< 100\mu\text{m}$
- » Noise cluster rate $< 10\%$




Core Characteristics


Detector performance

- » Hit efficiency $\approx 99\%$ ✓
- » Hit resolution $< 100\mu\text{m}$ ($65\mu\text{m}$)
- » Noise cluster rate $< 10\%$

✓ Verified in test beams



C-Frame Design



- C-Frame \triangleq 1/12 of the final detector
- Assembly & Commissioning above ground
- Mechanical support for fibre modules & services
 - » Low-voltage for readout electronics
 - » High-voltage for SiPM readout
 - » Water cooling of readout electronics $\rightarrow 20^\circ\text{C}$
 - » NOVEC cooling of SiPMs $\rightarrow -40^\circ\text{C}$
 - » Vacuum, Dry-Gas
 - » Optical links for control and data transmission

C-Frame Design






Photo of first assembled C-Frame

- C-Frame \triangleq 1/12 of the final detector
- Assembly & Commissioning above ground
- Mechanical support for fibre modules & services
 - » Low-voltage for readout electronics
 - » High-voltage for SiPM readout
 - » Water cooling of readout electronics $\rightarrow 20^\circ\text{C}$
 - » NOVEC cooling of SiPMs $\rightarrow -40^\circ\text{C}$
 - » Vacuum, Dry-Gas
 - » Optical links for control and data transmission


Scintillating Fibre Tracker

Working Principle

- Cross-sectional view on scintillating fibre mat
- 6 staggered layers of 250 μ m scintillating fibres
- 2.5m long
- Mirror on the other end




- Hamamatsu H2017 SiPM array
- 128 channels
 - 104 pixels per channel
 - Cooled to -40°C



Readout Boxes




Readout Boxes assembled on C-Frame



Schematic Structure of a Module and Readout Box (w/o blue cover)


Readout Box Components




Open Readout Box consisting of two identical halves (*HalfROBs*)

Readout Box Components

- PACIFIC Board
 - » Carrier for 4 PACIFIC ASICs
- PACIFIC ASIC
 - » 64 channels (2 ASICs per SiPM)
 - » Analogue processing of SiPM signals
 - » Digitisation into 2 bits per channel
 - » 3 tuneable thresholds




PACIFIC ASIC Channel: Analog processing & digitisation




Readout Box Components

- Cluster Board
 - » Carrier for 2 Cluster FPGAs
 - » 1 GBT-SCA
- Cluster FPGA
 - » Hit reconstruction
 - » Noise suppression
- GBT-SCA
 - » Dedicated Slow Control Adapter
 - » Control of PACIFIC ASICs and Cluster FPGAs
 - » I²C, JTAG, GPIO
 - » ADC to monitor temperatures and voltages



Readout Box Components

- Master Board
 - » 1 GBT-SCA
 - » FEASTMP DC-DC converters
 - » 8 optical links for data transmission
 - » 1 bidirectional optical link for control
 - » 8+1 GBTx ASICs
- GBTx ASIC
 - » Implements 4.8 Gb/s optical links
 - » Usable as unidirectional transmitter (data) or bidirectional transceiver (control)
 - » Distribution of 40MHz reference clock



C-Frame Assembly



Assembly Hall



Assembly of the C-Frames in dedicated hall on the LHCb site (LHC Point 8)

Assembly Hall at night
4 C-Frames can be assembled at the same time



C-Frame Assembly



Status

C-Frame	C1	C2	C3	C4	C5	C6	C7
Mechanics	Completed	Completed	Completed	Completed	Completed	Completed	Completed
Water-Cooling	Completed	Completed	Completed	Completed	Completed	Open	Completed
NOVEC-Cooling	Completed	Completed	Completed	Completed	Open	Open	Open
Dry-Gas	Completed	Completed	Completed	Completed	Open	Open	Open
Cabling	Completed	Completed	Completed	Completed	Completed	Completed	Completed
Modules	Completed	Completed	Completed	Completed	Open	Open	Open
Heating Wires	Completed	Completed	Completed	Completed	Open	Open	Open
Electronics	Completed	Completed	Completed	Completed	Open	Open	Open
Optical Fibres	Completed	Completed	Completed	Completed	Open	Open	Open
Commissioning	Completed	In Progress	Completed	Completed	Open	Open	Open

Legend:

Completed

In Progress

Open



Status

C-Frame	C1	C2	C3	C4	C5	C6	C7
Mechanics	Completed	Completed	Completed	Completed	Completed	Completed	Completed
Water-Cooling	Completed	Completed	Completed	Completed	Completed	Open	Completed
NOVEC-Cooling	Completed	Completed	Completed	Completed	Open	Open	Open
Dry-Gas	Completed	Completed	Completed	Completed	Open	Open	Open
Cabling	Completed	Completed	Completed	Completed	Completed	Completed	Completed
Modules	Completed	Completed	Completed	Completed	Open	Open	Open
Heating Wires	Completed	Completed	Completed	Completed	Open	Open	Open
Electronics	Completed	Completed	Completed	Completed	Open	Open	Open
Optical Fibres	Completed	Completed	Completed	Completed	Open	Open	Open
Commissioning	Completed	In Progress	Completed	Completed	Open	Open	Open

- Electronics Commissioning**
- Step-by-step verification of each component
 - Ranges from basic functional to full system tests
 - Results are presented in *Commissioning Reports* and stored in database
 - Full procedure takes about 2 weeks per C-Frame

Legend:

Completed


In Progress

Open


C-Frame Commissioning



Test Setup



C-Frame to be commissioned




~ 15+60m optical fibres

DAQ Server





Optical Power Measurement

- Measure power of optical transmitters arriving at the DAQ server
- Crucial measurement to ensure stable connection in final setup underground with $\sim 300\text{m}$ optical fibres and additional patch panels
- Not much margin for some optical links
 - » Careful treatment and cleaning of fibres and lenses



Temperature Sensor Readings


- 82 temperature sensors per Readout Box
- Ensure functioning of all sensors
- Locate bad thermal connections



Full System Test


- Dedicated light injection system
 - » Illuminate SiPMs with pulsed light
- Commissioning: Test for dead channels without the need of particles

Schematic Layout of the SciFi Light Injection System




Full System Test

- Dedicated light injection system
 - » Illuminate SiPMs with pulsed light
- Commissioning: Test for dead channels without the need of particles
- PACIFIC: Can only measure **integrated ADC spectrum** by scanning thresholds through dynamic range
 - » Extract parameters like mean number of photons or gain by fitting the curve




Full System Test

- Verify that all $\sim 50k$ channels of a C-Frame detect light ($\mu > 0$)
- Structure originates from light distribution of the light injection system
 - » Light bars are handmade



Summary & Outlook

- 3 (out of 12) C-Frames have been fully assembled and commissioned to date
 - » Commissioning of 4th C-Frame ongoing
 - » Assembly of 3 other C-Frames ongoing
- Delayed due to pandemic
 - » Scientists and technicians from different countries involved in assembly and commissioning
 - » Commissioning can be continued remotely and with people already on site
 - » Situation in the near future unclear
- Gained a lot of experience along the way
 - » Developing tools and software
 - » Operate the detector and process the large amount of data



C-Frame test transport to the LHCb cavern

BACKUP

Setup


SPS north area H8 beam line

- 180GeV protons/pions
- 1cm beam width
 - Needed large translation table for module ($50 \times 250 \text{cm}^2$) scans
- Beam asynchronous to our 40MHz readout
 - Required additional timestamps to select in-time events offline
- Recorded $\sim 500\text{k}$ events/spill, only need 2 spills to get enough statistics
 - Short runs, nice for shifters

TimePix3 telescope


- Tracks for efficiency & resolution measurements
- Provided trigger + fine timestamps for offline selection
 - Synchronised to our DAQ

Setup



July 2018 @ SPS


- First time
 - » Putting all detector components of 2 ROBs together
 - » Reading out 32 data links @ 40 MHz
 - » Calibrating 4k channels
 - » 12k configurable thresholds



Test Beam Setup
with 2 Readout Boxes

July 2018 @ SPS


- First time
 - » Putting all detector components of 2 ROBs together
 - » Reading out 32 data links @ 40 MHz
 - » Calibrating 4k channels
 - » 12k configurable thresholds
- Target performance parameters fulfilled!
 - » Hit efficiency: 99.47%
 - » Correlated noise cluster rate: 2%
 - » Hit resolution: 65 μ m
- Online clustering verified



More details from my colleague Lukas Witola:

[Tomorrow at 17:45 in S01 \(T 90.8\)](#)

Spatial Resolution



- Resolution $\sim 65\mu\text{m}$ for both modules
- ✓ Better than required ($\leq 100\mu\text{m}$)


Spillover = Correlated Noise Clusters

Probability to find a cluster from BX_n in BX_{n+1} at the same position

- Shaper settings have great influence
- Two settings:
 1. More undershoot
 2. Less undershoot & wider


Setting 1: 24%

Setting 2: 2%





Spillover with production version PACIFIC

In Numbers



- 256 Readout Boxes
 - 524k channels
 - 1.6M configurable PACIFIC thresholds
 - 4k data links
 - Data rate $\approx 20\text{Tb/s}$
- } More than any other LHCb subsystem

Scintillating Fibres



PS: Polystyrene
 PMMA: Polymethylmethacrylate
 FP: Fluorinated polymer

Spectrum of a scintillating fibre
 $\tau = 2.8ns$
 Attenuation length: $\sim 5m$

- 8 fibre mats per module
- Light yield:
 - » Unirradiated: 20pe
 - » After 10 years in hottest area: 12pe
- Support structure
 - » 200 μ m carbon
 - » 20mm honeycomb
- Alignment precision of 50 μ m over 5m
- Production finished







Photo detection efficiency for different over-voltages




Dark count rate for irradiated detector for different over-voltages


DCR was shown to be the only parameter affected by radiation!

- Low Power ASIC for Scintillating Fibre Tracker
 - » < 12mW per channel


- Hamming encoding of configuration registers
 - » Correct single bit flip on the fly
 - » Detect multi bit flip and raise error



35 kGy in the hottest region around the beam pipe




$6 \cdot 10^{11} \text{ n}_{\text{eq}} \text{ cm}^{-2}$ at the SiPM location (2.5m)



Algorithm

- Making use of 3 comparators
 1. Low threshold
 - » Just above dark noise rate
 2. Middle threshold ("seed")
 - » Slightly above low threshold
 - » Starting point for a cluster
 3. High threshold
 - » Significantly larger
 - » Accept high signal single channel clusters




Cluster FPGA building clusters from 128 SiPM channels




PCIe40 card (so-called TELL40)
Up to 48 optical links



SuperMicro 4029GP-TRT server with 8 TELL40 cards
and optical fibres connected






C-Frame Assembly




Module Installation




Readout Box Installation




Cabling





Electronics Commissioning Procedure


- Step-by-step verification of each component
- Ranges from basic functional to full system tests
- Results are stored in *Commissioning Reports*
- Full procedure takes about 2 weeks per C-Frame



Bit-Error-Rate Test (WIP)

Difficulty: **6 clock phases** have to be synchronised to each other to ensure a stable data transmission


- > optical connections →
- > Data →
- > Fast control commands + clock →
- > clocks →



4. PACIFIC Clock Scan



Using work-arounds



- No more interrupted intervals
- Common interval width = 1.3ns

