

## WP15 Report Upgrade of beam and irradiation test infrastructure

Federico Ravotti (CERN) & Marcel Stanitzki (DESY)

AIDA-2020 Final Annual Meeting Vidyo, 29 April 2020



### WP 15 Structure, Lab's & Facilities

- Task 15.1: Scientific coordination (CERN, DESY)
- Task 15.2: Improvements of test beam infrastructure for high precision tracking (CERN, DESY)
- Task 15.3: Improvements of the DESY test beam infrastructure (DESY)
- Task 15.4: Improvements of the test beam infrastructure at LNF (INFN)
- Task 15.5: Improvements of the infrastructure for irradiation tests (CERN, INFN, VU, INRNE, JSI, USFD\*)





Test Beam Facility
 Irradiation Facility



### WP15.1 Scientific Coordination

• Chasing people for slides, Milestone & Deliverable reports and publications

#### • WP15 Satellite Meetings @ BTTBs

- large overlap of activities and participants, moreover facilities upgrade activities were driven by user requirements ...
- Barcelona, 2017: <u>https://indico.cern.ch/event/591285/</u>
- Zurich, 2018: <u>https://indico.cern.ch/event/683891</u>
- Geneva, 2019: <u>https://indico.cern.ch/event/731649/</u>



 From 2019: gather, give consistency and formalize community ideas for AIDAinnova proposal!





### WP15 Status @ M60

- Milestones:
  - all achieved!
- Deliverables:
  - all achieved!
  - INFN-LNF (D15.5) and GIF++ upgrade (D15.11) reports being reviewed
- Publications:
  - 81 records in CDS (including 21 official reports)
  - <u>http://cds.cern.ch/collection/AIDA-2020?ln=en</u>
  - several other in the pipeline



### WP15 Structure

WP	15.2	WP15.3	WP15.4		WP	15.5	
J. Dreyling DE	-Eschweiler ESY	<i>M. Wu</i> DESY	<i>P. Valente</i> Frascati	<i>F. Ravotti et al.</i> CERN, INFN, VU, INRNE, JSI, USFD			
DESY-II Test Beam Facility	CERN PS & SPS Test Beam Areas	DESY II Test Beam Facility	BTF @ LNF	IRRAD	GIF++	JSI Triga Reactor	U.o.B. Cyclotron Facility



### WP15.2: Azalea is coming home...



Testing in TB22 DESY, July 2016



Packed and shipped from CERN to DESY, in Dec. 2018/Jan. 2019



#### Flying through the DESY Test Beam hall





### WP15.2: Telescopes at DESY in 2019





WP15.2 follow-up: Common Beam Telescopes 2025

- Current Status
  - We have 7 telescopes operating
  - In operation since approximately a decade: AZALEA is the youngster being already four years old!
  - We will keep them running for as long as possible, but we'll reach end-of-life

### Active Discussion also with WP5

- Improve timing information,
- Maintain spatial resolution,
- Keep material budget low, etc.
- Many of our ideas went into the AIDAinnova proposal
  - Stay tuned!



### WP15 Structure

WP:	15.2	WP15.3	WP15.4		WP	15.5		
J. Dreyling DE	-Eschweiler ESY	<i>M. Wu</i> DESY	<i>P. Valente</i> Frascati	<i>F. Ravotti et al.</i> CERN, INFN, VU, INRNE, JSI, USFD				
DESY-II Test Beam Facility	CERN PS & SPS Test Beam Areas	DESY II Test Beam Facility	BTF @ LNF	IRRAD	GIF++	JSI Triga Reactor	U.o.B. Cyclotron Facility	



# WP15.3: Improvements of the DESY test beam infrastructure

## Task 15.3.1: External silicon tracker for 1T magnet in the DESY test beam

- Delivered a 6-layer large active area (10x10cm<sup>2</sup>) telescope of novel hybrid-less sensor
  - with better spatial resolution than required: dy~7.4 um (< 10 um), dx~0.17 mm (< 1 mm)</li>
- Highlight milestones:

M. Wu

- July 2017 sensor arrived
- Oct 2018 assembly quality validated
- Feb 2019 prototype's first beam commissioning test succeeded
- May 2019 production's first beam commissioning succeeded
- July 2019, Mar 2020 production performance measurements with EUDET telescope done





# WP15.3: Improvements of the DESY test beam infrastructure

- A full telescope package: integrated to EUDAQ2 + AIDA TLU, providing a full chain data analysis framework;
- Well documented as a long-life project: numerical manuals available online.
- Publications: Journal paper progressing (first draft exp. May 2020), 2 IEEE proceedings, 1 VCI proceeding (doi:10.1016/j.nima.2019.162864)
- Status: waiting for the first "benevolent" user.

#### Task 15.3.2: Environmental slow control system

- Commercial rack-based data logger, polling by EUDAQ2 via MySQL database – <u>simple plugin for user</u>
- Delivered on time: MS33 and D15.3
- Documentation: 2 user manuals available online as AIDA tech reports.
- **Status**: Available for all users at DESY , full system now upgraded to Win10.









### WP15 Structure

WP15.2		WP15.3	WP15.4	WP15.5					
J. Dreyling DE	Eschweiler SY	<i>M. Wu</i> DESY	<i>P. Valente</i> Frascati	<i>F. Ravotti et al.</i> CERN, INFN, VU, INRNE, JSI, USFD					
DESY-II Test Beam Facility	CERN PS & SPS Test Beam Areas	DESY II Test Beam Facility		IRRAD	GIF++	JSI Triga Reactor	U.o.B. Cyclotron Facility		



WP15.4: External Constraints

- Delay of project start
  - LNF MAC recommended shift of priorities
  - Delay of procurement of essential components
- Major Vacuum Incident in Early Fall 2019
  - Beam pipe broke
  - Beryllium contamination
  - Major effort required for clean-up

#### Latest Plan (pre COVID-19)

- April 2020: beam for Padme
- November 2020: test beam for users
- 2021: installation of photon tagging

#### From a AIDA WP15 perspective

Really beyond our control ...



### WP15.4: BTF-1 & BTF-2 beam-lines ready

- Old beam-line dismantling
- Cables re-routing
- BTF-1 and BTF-2 branches installation
- New experimental hall control room
- New power supply hall
- Cooling, power, controls connection operative













### WP15.4: BTF-1 & BTF-2 beam-lines ready

- Commissioning with secondary electron beam (450 MeV): July 2018
- Commissioning with secondary positron beam (545 MeV): Sep. 2018
- First user on new BTF-1 line, PADME (dark photon searches) experiment: Oct. 2018 Feb. 2019
- First users call for beam time: Jan. 2019
- User Beam Time open in June 2019: Pixel and Gas detectors tests.
- 2018/2019 Good publication number of BTF related activities (>50)





WP15.4: Photon Tagging

- BTF2 Extension to second hall delayed after COVID and PADME data taking
- Time scale now 2021
- BTF2 components (Magnets, vacuum pipes, mechanics, pumps scrapers...) in final test/shipping (5%) or ready to be mounted (95%)

D15.5 – New Frascati photon tag components installed, due to vacuum event now moved off, next installation after PADME users run and COVID19 delay → achieved (report submitted)





#### WP15 Structure

WP:	15.2	WP15.3	WP15.4	WP15.5						
J. Dreyling- DE	Eschweiler SY	<i>M. Wu</i> DESY	<i>P. Valente</i> Frascati	<i>F. Ravotti et al.</i> CERN, INFN, VU, INRNE, JSI, USFD						
DESY-II Test Beam Facility	CERN PS & SPS Test Beam Areas	DESY II Test Beam Facility	BTF @ LNF	IRRAD	GIF++	JSI Triga Reactor	U.o.B. Cyclotron Facility			



# Task 15.5: Improvements of the infrastructure for irradiation tests







- Testing components of the HEP experiments
- Beam of 24 GeV/c and size of 12×12 mm<sup>2</sup>
- Spills of 400 ms every ~10 sec

- Fluence of 1×10<sup>16</sup> p/cm<sup>2</sup> in 14 days
- Scanning also in dimensions of 10×10 cm<sup>2</sup>
- Low temperature irradiation (-25°C)







Task 15.5:

1E+18

792

1E+17

d

POT

1E+16

227

**∠21** 

2018

1E+15

L 224

2017

201

days HI

2016

188

2015

5.39E+17





Contactless Fluence Monitor



Variations of the predominant TR-PL spectral peaks with neutron irradiation fluence. In the inset (*i*) variations of TR-PL spectra are depicted.

within AIDA-2020: improvement of characterization techniques for irradiated semiconductor materials: GaN, a-Si



D15.6 (M24)

300

200

100

0

2012

291

223

objects

days p<sup>+</sup>

2013

**177** 

31

2014

(commissioning)

### Task 15.5: CERN IRRAD Task -IRRAD Data Manager (IDM)



D15.6 (M24)





### Task 15.5: CERN IRRAD Task -Beyond the IDM Tool ...



#### during Y5 ...



### Task 15.5: CERN IRRAD Task -Irradiation Facilities Database





### Task 15.5: CERN IRRAD Task -**Test-beam** Facilities Database

- A unified database and platform for test beam facilities at CERN, in EU and worldwide
- 16 facilities, 27 beamlines
- presented at BTTB in 2020; user guide: <u>http://cds.cern.ch/record/2706474</u>
- to fooility o

- au	ton			iuei	s to facili	Ly COU	Junat		N Test-Beam Fac ot secure   te	lities Database - Google Chrome t-beam-facilities.web.cern.ch/facilityDetailsO	it.php?ID=2		×				
	20					HOME CERN DIREC	TORY ADA 2021 TA DATABASE USER GUD	CONTACT		Conve	t to PDF		1 Alexandre				
	•	The second		CERN FA	CILITIES	-	an a	N: E- Al	Facility c ame: mail*: Iternative mail:	wordinator contact information Wiles scoordistr@an.d	Institute Name: Facility Name: Address:	Institute/Organizatio CERN CERN PS Roote de Meyrin, 1217, Meyrin,	on Details				
C	ERN PS			CERN	N SPS	<u>(</u>	cl <del>e</del> ar	Pt	hone:		City:	Genera					_
The Proton Synchrotron (PS) is a ke suality accelerates either protons do ons from the Low Energy Ion Ring (Li pol General	y component in CERN's elivered by the Proton 5 EIR).	accelerator complex, where it synchrotron Booster or heavy	The Super Proton Syn complex. It takes parts the NA61/SHINE and I	nchrotron (SPS) is the s clas from the PS and ac NA62 experiments, the 0	econd-largest machine in CERN's accelerator T collective them to provide beams for the LHC, COMPASS expertment.	te primary focus for CLEAR is ising and possible future machine mmunity.	general accelerator R&D and component stu is at CERN, based on a broad internal and exter	des for hai user		Source Data	Countr	) Not secure   test-bea	m-facilities.web.cem.ch/beamli	neDetails.php?ID=2&BL=1 vert to PDF			
			THE OWNER OF					N	ame:	PS East Area	FORA	Beamli	ne Characteristics	Infr	astructu	re	
← → C	🕯 test-beam-fa	cilities.web.cern.ch/public[	OB.php				ବ 🖈 🚭	Incognito : Ni	umber of	2	Is a Me required	Name:	Т9	FORM FIELD	YES 1	NO N/A	See
CERN CERN Acceleration	ng science				HOME CERN DIRECTORY	AIDA-2020 TA	DATABASE USER GUIDE	CONTACT (H	ser ommunity IEP R&D,	HEP, CR, RAD	Mandati certifica Should I CERN D	Particle type: Particle polarity:	electrons, hadrons, muons	Trigger signal & system Tracker & Telescopes	0		0
T			Tes	st Bear	mlines Database			ex ph sci	operiments, noton ience,):		Comm	Particle type details:		Geometer service Magnets Slow Control	0		0
IN ALL	Th	is database contains	a list of severa	al different To	est-Beam Facilities available at 0	ERN, in Europe a	nd Worldwide.		atus:	Accessibility Atlas	H	Particle intensity: Particle Momentum/Energy: Particle	0.5 - 10 GeV/c	Vacuum pipe Handling service(cranes,) Movable stages	•	0 0 0 0	0
		Switzerland	,		protons		•	Bo	ooking ots:	Typically Wednesday to Wednesday	Comm	Momentum/Energy Resolution: Experiments per		Gas Cabling infrastructure	0 0		0
M			100 m		Show All			IN (C	lection & rocedure Committee, ):	SPSC or LHCC if more than 2 weeks	_	beamline: Experiments per beamline details:		Particle ID instrumentations IT services	0	0 0	0
111	T	3				1		Av Uj sh	vailability: p-time & utdowns:	No beam in 2019 and 2020		Beam Generation (Direct Extraction, Secondary Generation	Slow extraction on target	Comments:			
				L	og In to Edit Data			A	greements: greement etails:			parasitic,): Beam size:					
30G	Facility Name‡		Beamline Nameț			Particle Energy‡	Coordinator:	Fu pr	anding rograms:			Bunch clock:	Debunched				
	CERN SPS	CERN	H2	Switzerland	electrons, protons, hadrons, muons, ions	10-400GeV/c	sps.coordinator@cern.ch		omments:			Spill length: Spill rate:	400ms		GKC	otse	
	CERN SPS	CERN	H8	Switzerland	primary protons, hadrons, muons, electrons, ions	10-400GeV/c	sps.coordinator@cern.ch	- 3				Particles per spill:	100-10000	В.		201	
K	piE1, piM1	Paul Scherrer Institute (PSI)	Beamline	Switzerland	pions, muons, positrons, protons	50-450 MeV/c	davide.reggiani@psi.ch					Effective flux: Beam line physicist:	5000/day Johannes Bernhard		CEF		-
8 2	PIF	Paul Scherrer Institute	Beamline	Switzerland	1 protons	5 - 230 MeV/c	wojtek.hajdas@psi.ch					Comments:					



<u>http://www.cern.ch/tbdb</u>



### Task 15.5: CERN IRRAD Task -**RadHard instrumentation**

- **Sample Holder Material** 
  - Carbon Fibre and ULTEM good candidates after assessment of various materials
- **Beam Profile Monitor (BPM):** 
  - detailed performance analysis with different beam conditions
  - engineering of BPM detectors with different patterns/granularity
  - proof of concept of a RadHard  $\mu$ -BPM based on microfabrication technologies  $\succ$



F. Ravotti (CERN) & M. Stanitzki (DESY) - AIDA-2020 Final Annual Meeting - 29 April 2020

FPFI Center of MicroNanoTechnology



### Task 15.5: Cold Irradiations at Birmingham Facility – LN<sub>2</sub> Cooling

- Aims of WP15.5: Improvements to infrastructure for Irradiation tests
- Milestones and deliverables required and achieved for WP15.5 MS: 15.8. Concept of cold box to be evaluated and a design fixed DEL: 15.8. Cold irradiations at Birmingham cyclotron enabled



2014-2017 system Small window, Flimsy pillar.

- Improvements made in new design
- Greater thermal performance
- Sensor annealing well understood / avoided
- Larger sample capacity
- Reduced fan and heatsink size
  proportional to box
- Reduction of internal heat-load from fan.
- Cooling stable to operational (measured) irradiation temperatures at Birmingham
- Reduced service channel count
- Simplified control system
- Increased scan area
- New improved support (Z) pillar for better movement control (new).
- Robust robotic communication



The University Of Sheffield.

Installed U.o.B. Sept. 2018, very positive feedback from OP team!

To be installed in IRRAD (2 boxes, STD cooling) before end of 2020!

2017-2020 system Large window, Robust pillar



### Task 15.5: Transport System for Large Objects at TRIGA Reactor (JSI)

- new irradiation facility at JSI reactor installed and commissioned in 2016
- allows irradiation of ~ 12 x 25 cm<sup>2</sup> samples
  - services possible
- 10<sup>15</sup> n<sub>eq</sub>cm<sup>-2</sup> in less than one hour
- 8 irradiation projects completed (electronics, sensors), 3 during last year
- ATLAS pixel module 10<sup>16</sup> n<sub>eq</sub>
- CMS calorimeter, 7 irradiations up to 10<sup>16</sup> n<sub>eq</sub> cm<sup>-2</sup>
- ATLAS full size sensor
- AIDA funds exhausted by end of 2018
- limited amount of irradiations offered for half price





D15.9 (M18)



Task 15.5:



- > Typically for muon systems of HEP experiments
- $E_{\gamma} = 0.66$  MeV; max. dose-rate ~0.5 Gy/h @ 1m from source (±37<sup>o</sup> angle) and 2.5 Gy/h @ glass contact
- Several attenuation factors available (up to ~50'000)
- >  $\mu$ -beam from T2 on H4 beam-line (100 GeV; ~10<sup>4</sup> /spill)

EN ENGINEERING DEPARTMENT



EP-DT Detector Technologies





Task 15.5:



**Removable Roof** 

**H4** 



#### Bunker area contains :

- Gas panels
- Electricity outlets
- Network sockets
- Environmental monitoring
- Gas/smoke detection
- Radiation monitoring
- Air conditioning

#### Irradiation Fields :

- Downstream ≈ 30 m<sup>2</sup>
- Upstream ≈ 75 m<sup>2</sup>



2 x Irradiation Area



### Task 15.5: GIF++ Facility Upgrade (Gas System)

The gas system infrastructure is a key element of the successful R&D programs performed at the GIF++





Mixing units, gas recirculation systems and gas analysis module are used for detector R&D studies

Wide range of available gases available Possibility to use pre-mixed bottles (local gas point)



Mixture distribution Monitoring of pressure,

O2/H2O, temperature, atmospheric pressure

Additional software controlled pressure regulation for very low flow regimes

Gas mixing unit





CERN technical students

Partial funding of the gas system equipment and two

	Gas o	hromatogram
	Argon	
_		Signal area is proportional to gas concentration
ulani.		C02

R. Guida (CERN)

Gas chromatographic analysis : allows monitoring gas mixture composition and presence of impurities on return from detectors under test



#### Task 15.5: GIF++ Facility Upgrade (Instantaneous Dose-Rate Monitor)

#### Instantaneous DRM for GIF++ and test of SiPM + scintillator as a DRM for Gif++





DRM with a NaI(Tl) scintillator and photomultiplier FEU-35 was assembled at INRNE for the test. The spectra of Caesium-137 measured with it is shown on the plot:



during Y5 ...

Comparison for NaI(Tl) and plastic scintillators for two attenuations at GIF++

The light yield and decay time for NaI and plastic scintillators differ significantly. The test and comparison between these 2 DRM's at Gif++ (from 10 to 10000 mGy/h) could give an information for the possible use of the DRM's at substantially

> P. laydjiev, L. Dimitrov, I. Vankov, G. Mitev, L. Ratchev



32

Test of the Berthold LB 6500 Geiger-Mueller Dose Rate **Probes at several attenuations at Gif++** 



### Task 15.5: GIF++ Facility Upgrade (Cosmic-ray Tracker Upgrade)

#### **Project description**

Extension of the present GIF++ cosmic tracker

via installation of new RPC chambers on the bunker endcap walls Benefits:

- Extended coverage
- Selection of harder momentum muons
- Triggering on beam-halo muons

#### **Project deliverable**

#### 4 RPC chambers have been constructed

mechanics + front-end electronics + gas volumes

#### Chambers positioning:

- defined for the downstream region
- upstream region under discussion taking into account:

Upstream positions

(under discussion)

- bunker extension
- improved muon beam proposal (new pion dump)



D. Boscherini



### Task 15.5: GIF++ Facility Upgrade (Augmented Reality Event-display)

DAQ and monitoring system



#### AR visualization of chamber status



#### This application has been developed for demonstrating the concept

#### For a real use:

- Port the software on an android system
- Enable the possibility to orient the system in a complex environment using multiple markers
- Enable the possibility to increase the precision of the information localization
- Making the tracking interactive
- Making the detector interactive
- Making the DCS interactive



#### Cosmic-ray test setup at BB5

AR visualization

of Cosmic Rays

• RPC detector



• Marker and AR reference frame

#### Software Platforms:

- ARToolKit 5.4 for AR
- WinCC for DCS

D15.11 (M54)

- Qt (for porting AR on Android)
- Data acquisition & monitoring custom application



### WP15 Deliverables Summary

WP 15.2	WP:	15.3	WP:	15.4	WP15.5						
DESY-II & CERN Test Beam Facility	DESY-II Test Beam Facility		BTF		CERN IRRAD		JSI Triga	CERN GIF++		U.o.B Cyclotr. Facility	
D15.1	D15.2 (M36) (M45)	D15.3	D15.4 (M30) (M44)	D15.5 (M42) (M52)	D15.6	D15.7	D15.9	D15.10	D15.11 (M48) (M54)	D15.8	



## Summary & Outlook

- WP15 has delivered improvements to Test Beam and Irradiation Facilities
  - people working together, meeting & exchanging ideas, providing common infrastructures and services for the community, ...
  - all Milestones completed
  - all Deliverables completed (D15.5 and D15.11 reports on-line soon)
  - several of our activities continued in Y5 beyond the Deliverables with good results!
- We'd like to thank our task leaders and all contributors for making it really a pleasure to lead WP15. As in any large projects, we went through ups and downs, but at the end we all achieved everything we aimed for, and more!

#### ... and beyond AIDA-2020?

- WP15 has <u>build bridges and communities</u> and this network will probably "stay alive" beyond AIDA-2020
- several <u>ideas born within WP15 evolved into full</u> <u>AIDAinnova Eol's</u> in key areas (development of new common tools, beam telescopes upgrade, etc.)
- "crossing fingers" for the new proposal and looking forward to restart working together soon!

