

HL-LHC IP and Ring BPMs: Read-out Technology and expected Performance

Manfred Wendt (BE-BI-BP) for the LHC BPM team:

Manoel Barros Marin, Douglas Bett, Andrea Boccardi, Irene Degl'Innocenti, Michal Krupa, and many other colleagues





176th WP2 meeting, 6/2/2020

Outline

Overview on LHC BPM activities
The LHC BPM status quo
The LHC ring BPM consolidation project
The HL-LHC IR BPM system
Summary



Overview of LHC BPM Activities


Interlock BPM consolidation

- 8 stripline BPMs left & right of point 6
- New read-out electronics consolidation
 - initially triggered by operational problems with doublet-bunches
- Prototype tested with beam during run 2
 - on BPMS.4L5v
 - Time-multiplexed BPM electrode signals
 - Band-pass comb filter allows doublet bunch signal processing
 - However, with reduced performance
 - VFC-based commercial 14-bit FMC ADC operating at 2.6 GB/s
- Final prototype to be installed end of LS2
 - Details have been worked out in close collaboration with MPP
- Deployment of the entire system during an upcoming YETS...



Overview of LHC BPM Activities (cont.)

- Integrated Collimator BPMs
 - Buttons embedded in collimator jaws to speed up set up since 2013
 - Uses high-precision DOROS BPM acquisition system
 - Collimator jaw position now interlocked on BPM readings
 - Challenging integration and component procurement: coaxial SiO₂ RF cables
 - All HL-LHC collimators will be equipped with BPMs



- **HEL Stripline BPM**
 - Needs to monitor the hollow-electron beam and the LHC proton / ion beams



Overview of LHC BPM Activities (cont.)

HL-BPMs (IR BPMs)

- 32 new BPMs
 - "cold" BPMs inside the cryostat
 - 24 stripline BPMs to monitor of both beams in the same beam pipe
 - 8 button BPMs in separate beam pipes (D2)
- Requires a new read-out system
 - Final prototyping with beam before LS3!
 - Deployment of the entire system by end of LS3!


Ring BPM consolidation

- New read-out electronics for ~1100 LHC BPMs
 - Based on the given infrastructure
 - Radiation tolerant tunnel electronics
 - Prototyping during run 3
 - Deployment LS3/LS4?






LHC BPM Read-out Systems: Status Quo in LS2





- WBTN BPM System
 - Time encoded bunch-by-bunch signal processing
 - 2 optical fibers per BPM
- DOROS BPMs
 - Narrowband electronics
 - Collimator & IR BPMs


LHC BPM Wide-Band Time-Normalizer (WBTN) Functional Principle





7

WBTN BPM Performance and Limitations



- > Still fulfills most requirements, BUT:
 - Residual temperature sensitivity
 - Despite temperature controlled racks for the VME-based analog integrators
 - Aging effects, e.g. "electronic" offset drifts
 - Analog electronics components
 - Sensitive to signal reflections between BPM pickup and read-out electronics
 - Dynamic range limitations
 - Defined by the dual analog comparator circuit
 - Long-term maintainability, spares, calibration, etc.
 - Complex analog signal conditioning circuit
 - Will be 20 years in operation after LS3





- 70 MHz LPF & AD96687 analog comparator define the core performance of the LHC BPMs
 - <=46 dB dynamic range (single bunch intensity)</p>
 - Vref set to
 - 2mV: HI sensitivity
 - 67mV: LO sensitivity
 - **50...100 μm single-bunch resolution**
 - Adaptive orbit-mode IIR filter BW: 20...40 Hz, typically few μm resolution in orbit-mode

M. Wendt, HL-LHC BPMs, WP2 presentation

LHC Ring BPM Consolidation

Requirements


- Should meet ALL requirements of the present LHC BPM read-out system
- PLUS some improvements, e.g.
 - Resolution, reproducibility over long time periods, additional flexibility through gateware-based signal processing
- Two main "customers":
 - LHC OP: pilot, but mostly full machine with nominals, beam orbit mode, OFB, stability, reproducibility
 - ABP: (fat) pilot, TbT mode, SB resolution

Boundaries


- Keep the existing infrastructure
 - BPM pickups, optical fibers
- Requires radiation tolerant components!



Concept: Time-multiplexed BPM signal processing



LHC Ring BPM Consolidation: Proposed Layout





LHC Ring BPM Consolidation (cont.)


Challenges

Radiation tolerant components for the in-tunnel hardware

- Space-grade, radiation-tolerant 12 or 14-bit multi GB/s ADCs
 - Teledyne e2v EV12AQ600 12-bit, 6.4 GS/s, 4-cores, ~8.7 ENOB
 - TI ADC12DJ3200QML-SP 12-bit, 6.4 GB/s, 2-cores, ~8.7 ENOB
- Low-jitter clock generator & PLL
- VTRx transceiver
 - Currently under development
- Maximum raw data throughput limited by existing fiber installation
 - With 4x coarse wavelength division multiplexer ≤40.96 GB/s


Expected Performance

- Single bunch resolution 10...15 µm
 - Depending on ADC ENOB and CLK rate, and 2-in-1 or 4-in-1 time multiplexing schema
 - "fat" pilot bunch, ~2e10 cpb





BPMs for Interaction Regions



HL-LHC BPM overview


Code	Location	Distance to IP [m]	Aperture [mm]	Туре	Tungsten shielding	Electrode position	Beam time separation [ns]
BPMQSTZA	Q1 (IP side)	21.853	Octagonal 101.7 / 99.7	Stripline	No	0° / 90°	3.92
BPMQSTZB	Q2A (IP side)	33.073	Octagonal 112.7 / 119.7	Stripline	Yes	45° / 135°	3.92
BPMQSTZB	Q2B (IP side)	43.858	Octagonal 112.7 / 119.7	Stripline	Yes	45° / 135°	6.82
BPMQSTZB	Q3 (IP side)	54.643	Octagonal 112.7 / 119.7	Stripline	Yes	45° / 135°	9.72
BPMQSTZB	CP (IP side)	65.743	Octagonal 112.7 / 119.7	Stripline	Yes	45° / 135°	10.52
BPMQSTZB	D1 (IP side)	73.697	Octagonal 112.7 / 119.7	Stripline	Yes	45° / 135°	7.36
BPMQBCZA BPMQBCZB	D2 (arc side)	151.930	Round Ø 90	Button	No	0° / 90°	N/A




"Cold" Directional-Coupler BPMs

Technology


- 125 mm long stripline electrodes, "45^o rotated" installation (type B BPMs)
- ~26 dB directivity to improve the disentanglement of the B1/B2 signals
- Tungsten shielding: lower TID on Q2B magnet by ~15 %
- Amorphous carbon coating: Electron cloud effects decreased by 40x
- Active cooling with liquid He: To evacuate up to 6 W of head load
- Status / Milestones
 - BPM prototype production launched
 - Started procurement of tungsten absorbers (with WP12) and cryogenic RF feedthroughs
 - Qualification of RF feedthroughs in 2020 (?!)
 - In-kind contribution of BPM body manufacturing
 - Collaboration agreement with Russia finalized
 - Coaxial SiO₂ RF cables
 - Market survey and procurement start for mid 2020
 - In combination with cables required for the collimator BPMs







Impact of large aperture, rotated BPMs

Reduced coupling, 7.5 % for a centered beam
 Reduced BPM sensitivity, 0.4 dB/mm at the BPM center
 Increased position non-linearities











Directivity

- Directivity the ratio of the upstream (wanted) signal to the downstream (unwanted) signal
- > Ways of improving the directivity:
 - Careful RF design of the BPM (constant 50 Ω impedance)
 - Operating at lower frequencies
 - Installing the BPM in a location where the two beams are separated in time
- HL-LHC BPM directivity: ~ 26 dB






IR BPM Signal Processing






Candidate Digital Signal Processor



Digital Signal Processing Simulation Framework






21


Simulation Methodology

- Calculate the signals expected on the stripline ports for a given pair of beam bunches, characterized by their:
 - Positions in the BPM plane
 - Bunch crossing timing
 - Intensities
 - (Gaussian) bunch lengths
- > Also include the effects of:
 - Iong coaxial cables
 - filter stage
 - variable attenuator (given step size)
- The resulting signals are used as the basis for an ensemble of waveforms generated from a digitizer with an asynchronous clock with given:
 - sample frequency
 - random noise amplitude






Typical Results – Relative Accuracy Errors




CERM


HI-IHC PROJEC



IR1 – injection orbit
 i₀ = i₉ = 3 · 10¹¹cpb
 σ₀ = σ₉ = 75 mm



Typical Results – Relative Accuracy Errors




HI-IHC PROJEC

- IR1 injection orbit
 - $i_0 = 3 \cdot 10^{11} cpb$

•
$$i_9 = 3 \cdot 10^{10} cpb$$


- $\sigma_0 = \sigma_9 = 100 mm$
 - However, bunch lengthening effect not considered

Typical Results – Absolute Position Errors



25

Typical Results – Absolute Position Errors



Summary

- Various LHC BPM activities are underway
 - Collimator BPMs, interlock BPM CONS, HL-LHC IR BPMs, LHC ring BPM CONS
 - An (incomplete) snapshot of the ongoing R&D efforts was presented
- > Digital signal processing is a key element for any future LHC BPM read-out system
 - Reproducibility and performance improvements
 - Signal processing schema assumes 25 ns bunch spacing
 - Except interlock BPM consolidation can also handle doublet bunches
- Expected performance
 - Single bunch resolution 10...15 μm, orbit resolution <1 μm
 - Sampling in the 1st Nyquist passband, >8.7 ENOB, slow AGC
 - IR BPM accuracy:

~7 μ m for compensation of same intensity counterrotating bunch ~70 μ m for compensation of 10x lower intensity counterrotating bunch (assuming 2D 5th order polynomial for correcting non-linearities)

- During run 3…
 - Parasitic and dedicated beam studies with prototype hardware
 - Xilinx Zynq RFSoC evaluation-board with modified input stage
 - Dedicated MD on stripline BPMS.4L5
 - Single bunch in B1 and B2 with cogging between them

