

CLEX Two Beam Module lessons learned



- > Two module reviews in the past 2013 and 2015
- > Review of experience with the CLEX module
- Regular presentations and updates in workshops and project meetings
- > Numerous findings, clear recommendation > work on a new generation module concept



CLEX Two Beam Module lessons learned



- > Superstructure SAS
- > Installation
- > Integration
- > Alignment
- > Experimental Program in CLEX



CLEX experience review



Summary of the CLEX module production and installation review Review held the 25.2.2015 in the module working group Presentation can be found at: http://indico.cern.ch/event/366835/


- Superstructure SAS too complicated and fragile object, design issues identified
 → SAS design needs to be reviewed fundamentally, taking into account rf design
 changes; will be followed by Nuria's team
- Improve and integrate cooling system design of modules, fix BPM to quad, how to align the structures longitudinally, better integration of subsystems (BLM's, cables other sensors)
- Alignment issues identified, placing of fiducials, link between girder and cradles lost, motor failures, coupling of main and drive beam, BPM and Quad have o be linked
 - → improve integrated design, follow up with more measurements
- Compact loads needed
- General communication issues, more exchange needed between rf-design, mechanical design, experimental team, diagnostics and magnets.
 Several waveguides had the wrong phase



Final leak check CLEX Module experience review



Localisation principale des fuites




Attention au serrage des brides un gros risque de vriller les guides d'onde, risque de fissures en dessous des brides Prévoir un outillage pour bloquer les guide et WFM



History Chart








First CLIC prototype module completely installed in CLEX







Many compromises to use the module in CLEX!

RF network





Needs fundamental redesign! Less flanges, lower losses, lower centre of mass








CLEX Alignement

Component Drive Beam		Radial (µm)	Vertical (µm)	Error budget (µm)
PETS1	Enter	65	37	100
PEISI	Exit	-27	15	100
DD04	Enter	-9	-4	20
DBQ1	Exit	-2	19	20
DETCO	Enter	28	78	100
PETS2	Exit	-51	58	100
DBQ2	Enter	8	11	20
	Exit	-3	-14	20

Component Main Beam		Radial (µm)	Vertical (µm)	Error budget (µm)
AS1	Enter	-51	-59	10
ASI	Exit	-161	-16	10
AS2	Enter	-68	-85	10
	Exit	-139	-103	10



Component Main Beam		Radial (µm)	Vertical (µm)	Error budget (µm)
AS1	Enter	29	-24	10
ASI	Exit	-65	39	10
A.C.	Enter	46	-8	10
AS2	Exit	-10	-7	10



590

560

Roll (µrad)

470

440

Drive Beam

Roll

(µrad)

Radial

(µm)

Vertical

(µm)

2014-10-10

The

ory

571

232

0

+/- 2 µrad

CLEX



+/- 11

µrad

 $2 \, \mu m$

theory

2



573

237

0

449

173



124 µrad

64 µm

1 µm

Support

120

90

60

30

Vertical

(µm)


0


Roll (Main Beam)

-30 2014-	-10-10 <i>Wijij</i>		2018	5-02-25
Main Beam	The // ory			
Roll (µrad)	0	Without constraints	End of installation	Differe nce
Radial	0	0	56	56 µrad
(µm)		0	43	43 µm

0

CLEX constraints





Constraints due to:

- Connection to the waveguide
- Connection to the vacuum network
- Support



Experimental program for the CLEX module



List of ideas

- > Two beam acceleration, rf signal consistency, power transfer, acceleration, phasing, breakdown handling, ...
- Alignment studies, with and w/o beam, girder coupling, beam based alignment using WFM and BPM data, perturbation by accelerator noise, precision, reproducibility, fiducialisation, reliability
- > BPM studies, resolution, performance
- Wake Field Monitor studies, electronics, resolution
- > Temperature management, control flow rates, temperatures, measure changes in beam environment
- Find, understand and possibly solve shortfalls of present systems

These studies have not been completed!



Conclusions



- Huge piece of work but finally successfully installed
- Very valuable experience because much closer to the real requirements, vacuum, integration into a real machine, real rf structures which need right phase and calibration
- A big step towards a realistic module even if it is quite different then the CDR module
- > First results with beam and from alignment confirm the importance of that module



List of changes and improvements for the next generation CLIC module



Some documentation exist already: See Module review, lessons learned review CLEX installation, Critical item compendium

Let's assume we go away from a tolerance based design to a adjustable design: Enough evidence found in existing module experience

Necessary Improvements:

- Support of rf structures and PETS:
 adjustability, two point support, longitudinal adjustability, fixations, alignment references
- Vacuum system: separate or manifold, number of pumps, mechanical design of system (force free), cost ?
- Coupling between girders:
 Need to be solved if we stay with independent girders, not good enough right now
- Phasing of the structures:
 No clear tolerances and strategy, probably needs to be designed into the module
- BPM fixation in DB Quad:
 New mechanical concept needed, couple fix or adjust, depends on PACMAN as well, current solution insufficient
- Cooling system integration: system has to be designed in from the beginning. Too many pipes right now



List of changes and improvements for the next generation CLIC module



Necessary Improvements:

- Articulation point, girder support and regulations:
 Simply not practical in the current design, should we keep it or better independent girders
- WPS supports and reference to girder:
 Reference get's lost in current design and setup, integration with girder needed

New features or concepts investigated:

- New girder design, made of cast concrete, one piece including cradle and WPS
- How about putting WPS on object which should be aligned? RF-unit, numbers?
- One support for both beams, less movers, less sensors
- Longer support, less movers, less sensors
- DB- Quad support separate, beam dynamics requirements
- Relative orientation of the two beams
- Vacuum sectors
- New waveguide system, can we simplify, do we need the hybrid (save one load)
- Thermal handling of the module, operating temperature vs alignment temperature Compensate with water cooling
- Breakdown response in terms of temperature management
- Tunnel cooling and temperature stabilisation overall
- New force free vacuum system design
- New waveguide concept, no choke mode flange



List of changes and improvements for the next generation CLIC module



RF-unit:

Currently double PETS + 2 superstructures, no flanges, is this really feasible, reasonable?

SAS-design:

Mechanical design of outer part should be driven by module requirements:

Support interfaces, deformability, alignment features, simplify vacuum and water cooling interfaces,

Integrate double feed coupler to have only one rf flange, can we integrate high power load as well. High power load needs urgent validation in any case.

Superstructure concept, valid ?, How long can we go

Structure straightness not validated





4x this!!





Some visionary sketches from the module crew












Alex, Markus, Petri



More detailed analysis is needed, large potential for improvements







How could a new concept look like? Not worked out yet, more a design goal



☐ Precise pre-alignment in the tunnel after transport, laser tracker (PACMAN)
☐ Steel girder with WPS support integrated, adjustable supports for SAS Stiffness and vibration considerations, likely less costly
□ Introduce shorter vacuum sectors, 900 m unrealistic
□ Rough pre-alignment and assembly on surface in dedicated facility, 'clean area'. Main point of quality control and acceptance test, likely at CERN
□ Produce, measure, test, fiducialise components, Quads, PETS*, SAS* possibly already integrated in a module (PACMAN)
□ Rf high power test would be best on assembled module, how ? Define better rf-unit
☐ Re design structures ,PETS and waveguide system for future assembly into the modules
☐ Integrate vacuum system and cooling system




Conclusions



- A large number of shortfalls/mistakes or possible improvements have been identified in the past Many related to integration of module components and manufacturability of the module but significant beam dynamics requirements are missing as well
- New concepts have been studied and a vision of a new module is shaping up
- Up to know we built PETS, Accelerating structures, cooling systems, vacuum systems, waveguide systems for single structure high power tests. Very little has been done towards a full module integration







High Power system: Maybe most specific to CLIC, high power handling, thermal stability, efficiency

Waveguide system:

Relevant for all projects, compact, low loss, assembly friendly, cost, phasing, stability
Cooling and vacuum:
Relevant for most projects, cost assembly, performance, integration

Supporting system:

Relevant for all projects, small cost,
Has to meet beam dynamics requirements

Begin to the projects of the project of the projects of the project of the

All parts can be worked on separately but each time we combine we gain a lot towards a real CLIC module



References



- Module reviews:
 https://indico.cern.ch/category/5216/
- Module meetings:
 https://indico.cern.ch/category/2630/
- > LAB activities summary 2015-2018, EDMS 2054219
- Critical design items, EDMS 2086287
- > R&D since CDR, EDMS 2054199
- > Thermal behavior of XBOX structure, EDMS 2086457
- > Thermal tunnel studies, EDMS 2224093