



LH2 System

Progress and Future Plans

M Hills
T Bradshaw
M Courthold
I Mullacrane
P Warburton



Science & Technology
Facilities Council



Outline



1. R&D System Manufacture
2. Control System
3. Hall Infrastructure
4. Safety Update
5. AFC Integration Issues
6. Plans for 2010/11





R&D System Manufacture (1)

- Buffer Volume, Transfer Line and Test Cryostat all complete
- Gas Panel assembly 95% complete
- Design of enclosure is being detailed




R&D System Manufacture (2)

- Gas Panel manufacturing
 - Weld inspection and pipe cleaning complete
 - Flow meters (final item of instrumentation) procured and installed in the gas panel
 - Relief valves assembled into dedicated mounting frames
 - Pressure transmitters integrated





R&D System Manufacture (3)



- Final assembly of pipework now complete
- Pneumatic lines fitted and valve operation tested
- Only remaining mechanical work is to fit solenoids for control of pneumatic actuators (to be mounted on temporary plate until enclosure is constructed)
- When these are in place, GP will be ready for electrical wiring (by DL)







Acceptance Testing

- Cryostat currently assembled with Buffer Tank and Gas Panel
- Temporary transfer lines fitted between Buffer and Cryostat (due to limited space at AS Scientific)
- This allows:
 - Leak testing
 - Pressure testing (and possibly certification)
 - Full system cool-down
 - Some testing of control sequences for helium
- Next step is then to install in the MICE Hall and repeat these steps with the transfer line and other infrastructure



Control System



- Control Panel assembled with (almost) all components needed for He testing
- PLC programmed
 - Temperature logging
 - Valve control tested
 - Example control sequence tested
- Sequences for gas panel operation currently being written (only He sequences needed for acceptance tests)
- Design work underway for ventilation system and vacuum system control




Hall Infrastructure

To install the R&D system in the MICE Hall requires:

- Bottle store
- Vacuum system with roughing pumps sited externally
- Ventilation system to exhaust any leaks in Gas Panel, Buffer Volume or Hydride Bed.





Hall Infrastructure





Ventilation System




Basis of safety

- Eliminate sources of ignition
- ➡ ATEX rated fans
- Fans are specified such that one fan only is capable of providing sufficient flow to exhaust all three systems
 - An explosive atmosphere from a small release in the gas panel would only persist for a matter of minutes
 - Fans have been purchased and are ready to install




Vacuum System

- Dedicated pump enclosure to be sited on MICE Hall roof
 - Will house backing pumps required for all 3 hydrogen systems
 - Will also have capacity to house backing pumps required for other cooling channel modules
 - Designated Hydrogen Zone 2 (same as Gas Panel Enclosures) for DSEAR purposes
- Turbo pumps for AFC modules' safety vacuum shown on South Wall (must be behind magnetic shield wall)




Backing pump



Turbo pumps



Safety – DSEAR Zoning



- Test Cryostat (or AFC absorber vacuum space)
- Gas Panel Enclosure
- Pump Enclosure
- Connecting ductwork

...are Zone 2.

(“A place in which an explosive atmosphere...is not likely to occur in normal operation, but, if it does occur, will persist for a short period only.”)

The MICE Hall is not





Safety – UPS Requirements


- Recent discussions held amongst the Hydrogen System team on the UPS requirements for the system
- Document currently being drafted for submission to Technical Board
- Key conclusions
 - In the event of a mains failure:
 - System will fail to its pre-defined ‘safe-state’
 - Instrumentation and valve position information will continue to be available from the control system
 - The hydrogen detection system will continue to function






Integration with the AFC

- Working with Oxford, KEK and Tesla to ensure that the R&D system is compatible with the AFC module
 - Instrumentation (i.e. level sensors, pressure sensors and thermometry) which must be compatible with UK regulations (i.e. DSEAR – we can ‘self-certify’)
 - Process line connections
- Aim to test absorber in R&D test cryostat to check interfaces and instrumentation



Schedule





Summary and Future Plans

- R&D System manufacture in final stages with acceptance testing imminent.
- Control system work is more than keeping pace with the mechanical hardware and in good shape for initial testing.
- Safety principles of system well established, but implementation and documentation of these are still ongoing. Results from helium testing will be an important input to a pre-operation safety review.
- Design work underway for hall infrastructure requirements, but lots to do.
- Need to continue to work closely with KEK, Oxford and Tesla to ensure compatibility with AFC.
- Aim to take advantage of the long ISIS shutdown and delays to the Spectrometer Solenoids to install as much infrastructure as possible in the rest of this financial year.
- Several tasks:
 - Install R&D system components on south mezzanine
 - Build pumping enclosure and install vacuum system
 - Position fans, install ductwork and construct access platforms
 - Route vent lines outside hall
 - Install hydrogen detection system
 - Route cabling and install control racks in H2 Control Room

