
SEEIIST Drawings Next Steps

Yiota Foka, Dimitris Kaprinis et al CERN, 15 oct 2020

SEEIIST 2D Drawings Starting Point for Modifications

INCOMENT ON COMPANY

A lot of work and iterations on 2D Still many items to optimise



AREA: 6.500 M2

SEEIIST 3D Drawings Starting Point for Modifications

The rest of the buildings/layout were done hastily **for the ESFRI application**, with the guidance of HP and SD, having in mind the "Medical CERN" and the ENLIGHT Virtual Therapy centre ("do something that looks nice").



SEEIIST Drawings Material in indico

Indico Fri 9 oct 2020 https://indico.cern.ch/event/963348/

• HIT Visit

https://indico.cern.ch/event/963348/contributions/4052419/attachments/21194 49/3566621/YF-HDvisit-8oct2020.pdf

Indico Fri 25 sep 2020 https://indico.cern.ch/event/958330/

SEEIIST 3D Drawings Collection

https://indico.cern.ch/event/958330/contributions/4028497/attachments/210945 5/3548146/SEEIST_Presentation1.pdf

• SEEIIST 3D Drawings Next Steps

https://indico.cern.ch/event/958330/contributions/4028497/attachments/21094 55/3548235/Drawings_NEXT_STEPS.pdf

Link google doc : to insert comments https://docs.google.com/document/d/1dtZSWsF3NBSggOt 71e2a3tKTYBd2Ymt2k3Dquev9bvk/edit?usp=sharing


Link google folders : SEEIIST Drawings and PHOTOS https://drive.google.com/drive/folders/1ESrfc1o8YZPPv5tV xwnLXwF7TmyD5DsY?usp=sharing

Aims: all in one....

- To add some "users requirements" and "reality"
- To prepare the document for governments of SEEIIST member/countries
- To prepare for the SEEIIST Brochure
- **Priorities:**
- **Deadlines:**

Some Considerations:

- Free space next to gantry room, extension of beam line and dump for future addition of 4rth room, possibly with gantry
- Free space at the extension of Linac/LEExp
 - for future addition of radioisotope production unit
- Free space for future connection to Hospital
- Free space next to V/H room for crane operations through the roof
- Easy access via direct/straight ramps to main entrance/service areas



Transfer lines: extra 2-3 meters between H and V/H lines


In order to make an access corridor between the H and H/V rooms

for accessing H room at the level of bean entrance to the room (as in MIT)

Storage Area: for cooling down of material

Accelerator Control Room

Technical rooms for equipment, workshops: extra floor over synchrotron and HEBT?



Heights:

- The gantry and H/V rooms are almost of same height (order 10 m) there is a common roof on the whole complex of treatment rooms
- The Experimental Hall will be configurable and therefore enough height is necessary for crane to be able to more concrete blocks for the walls and the ceiling of the experimental rooms

Suggestion:

For uniformity reasons the suggestion is to have a complete block of high buildings from the scientists building corner to the treatment rooms corner

of the same height (10-15 m)





Scientists Building: see CERN building 40

- It is on the way to the entrance ramp to the sources/linac area

- It is too big, 100 m long (building 40 is 60 m long)

Social Building: see CERN main building

It can start with wings and complement later according to needs

- Reception
- Offices for Personnel
- Administration
- Directorate
- Auditorium, Library etc
- PR and Conferences Space
- Events/Restaurant Area and Roof Garden
- Restaurant/Terrasse at ground level (where ?)

Area over synchrotron? Flat ? Floor over it ? Block it (no people sitting there?)





Treatment Preparation Area: To be optimised for best patient flow

- Paediatrics preparation area including anaesthesia (see MedAustron)
- Dedicated preparation areas in front of each individual treatment room









- Heights of ceilings: to be optimized
 - H = 6 m net plus 2 m roof shielding for Linac, Sources, Synchrotron (transfer lines)
 - H = 10 m net plus 2 m or 3 m roof shielding for Experimental Hall
 (at GSI 10 m at North Hall 15-20 m)
 - EXP Hall same height with Gantry/VH rooms
 - does it make sense to have same height for the HEBT lines also ?

Experimental Hall

- Configurable EXP walls and ceiling: see P2 and North Area

- External walls of EXP as for the Linac (to add concrete blocks inside according to the needs (at GSI cleaning personnel goes for cleaning with dosimeter even in the caves)

Technical Rooms

- Extra floor over synchrotron (for power converters etc) ?
- Extra rooms over the HEBT (for workshops, exp rooms as at GSI ?)

Storage Rooms: cooling down of equipment

Cranes

Control room for whole accelerator complex

- MV in the bunker, at same level (use service area)
- MS et al NOT in the bunker (noise etc)
 - Better at the scientists building
 - (at the edge closer to main entrance of the bunker

Connection to Hospital

PR, Exhibitions/Projections, Visitors path... School Visits.... "teaching rooms"

SEEIIST Drawings: Measurements

Measurements Ramps: 30m length 10.00m wide from elevation 0.00 to -2.50m at the entrance

Building 40 rectangles : 60.00m x 12.00m = 720m2 x 2 rectangles = 1440m2 area of the circle = radius 20.00m = 1256.00m area of the building footprint 1440.00m2 + 1256.00 m2 (circle) = 2696.00 m2 Office area: 1440.00m2 x 5 floors Offices space : about 15m2

Science building: $100.00m2 \times 20.00m2 = 2156.00m2$ (including the circle) area for offices : $1720.00m2 \times 2$ floors = 3440.00m2 (excluding the circle) Total area : 5596.00m2