



RFD Prototype Cryomodule update


Thomas Jones on behalf of CERN-UK Team
23/10/2020



Content

- Schedule
- Cavity + ancillary update
- CM design update
- Tooling update
- Infrastructure update
- Documentation update

UK Plan for 2021/22



Expect all design and drawings complete by end of March 2021

All manufacturing complete by end of July 2021

Cleanroom ready in March 2021

Cleanroom Pre assembly mid-March to mid April 2021


Cavity Delivery end of April 2021 followed by 2 weeks Acceptance Tests

Cavity String Assembly May to Aug '21

Cryomodule Assembly end Aug '21 to end Jan '22



DL outgoing acceptance tests (LN2) in Feb to March 2022

CERN-RFD, Cold Test Results




RFD cavity jacketing assembly

- Cold magnetic shields from UK-collaboration
- He-tank assembly very efficient (~1.5 mons) after the experience from DQW
- Frequency shift during He-tank assembly $\sim \pm 15$ kHz (negligible)



RFD1 & 2 Jacketing




RFD1 welding to start mid-Oct and on track

RFD2 Helium tank welded and pressure tested successfully

Final metrology and cold test in the next weeks

Cryomodule Design


RFD module fully compatible with HL-LHC, to be tested in SM18 (2022) and SPS (2023)




Joint design between CERN & UK (STFC)

Cryomodule Design Progress (CERN/UK-STFC)

OVC and Cryolines (longest lead time)




Vacuum vessel – Tender complete, order placed
Some drawings still to be released.



- Cryolines - Initial discussions taken place between STFC and suppliers who gave 6 month lead time.
- waiting on final drawings to launch procurement

Cryomodule Design Progress (CERN/UK-STFC) FPC and Tuner (Provided by CERN)





- FPC - Will be delivered to UK in April/May 2021.
- Currently finalising details of delivery configuration.

- Tuner Frame and Tuner Actuation drawings released and two frames in manufacture.
- Other tuner components with shorter lead times are in advanced phase of design.

Cryomodule Design Progress (UK-STFC/CERN)

Thermal and Outer Magnetic shielding



- Outer magnetic shielding – 3D model complete, STFC negotiations with UK supplier regarding spring contacts.
- Drawings being produced aim to complete by end of November and place order by end of January.

- Thermal shield – **Design Report complete** including analysis for full range of scenarios including ‘shock cooldown’ and transportation loads etc.
- Stainless Steel pipework to Aluminium Alloy Panels (clamp weld block connection)
- To be manufactured by CERN for Prototype

Cryomodule Design Progress (CERN/UK-STFC)

Beamline vacuum chambers





Beam lines & vacuum layout – Decisions to be made on exact configuration of items arriving from CERN to UK which effect assembly procedures and tooling designs.

Cryomodule Design Progress (UK-STFC/CERN)

Tooling




- Cleanroom trolley accepted and on site.
- Design of Cleanroom positioning tooling ongoing.



- Manufacture of Cavity String Lifting tooling almost complete. Testing to take place at manufacturer's premises by end of October, then install at DL after this.
- Kinematics assembly to be ordered (design complete).

Cryomodule Design Progress (UK-STFC/CERN)

Transport Frame




Transport Frame – **Design report and Manufacturing drawings complete.** Currently out for quotations. Testing in Spring 2021.

Isolators checked by supplier and on order.




Test Block has been cast

Cryomodule Design Progress (UK-STFC/CERN) Infrastructure



- Cleanroom lifter for FPC insertion will be procured by Lancaster.
- Currently working on the specification.

Cleanroom for Cavity String assembly



ISO4 area to be increased in length.

- ESS Beam Transport Module Project currently using this cleanroom – Mitigation to build another Clean area for them.

Cryomodule Progress (UK-STFC/CERN)

Assembly procedures and QA

ASSEMBLY PROCEDURE

EN-MME

DQW CRYOMODULE – SPS PROTOTYPE : ASSEMBLY STEP 1

Abstract
This document describes the step 1 of the assembly procedure for the DQW crab cavity cryomodule for SPS.

TRACEABILITY

Prepared by: T. Capelli [EN-MME/EDM], A. Krawczyk [EN-MME/FS] Date: 2017-07-25
 Verified by: M. Garlaschi [EN-MME/FS] Date: 2017-08-02
 Approved by: O. Capatina [EN-MME/EDM], K. Brodzinski [TE-CRG/OP], M. Therresse [BE-RF/SRF] Date: 20YY-MM-DD
 Distribution: HL-LHC WP4

Rev. No.	Date	Description of Changes (major changes only, minor changes in EDMS)

This document is uncontrolled when printed. Check the EDMS to verify that this is the correct version before use

MTF Equipment Management Folder

Assembly Tree: Bending Magnet, transfer line, Type B340, horizontal

Assembly Folder : Main Info

Assembly Identifier: HCMBIAHHWP-01000005
 Other Identifier: MBIAH05
 Description: Bending Magnet, transfer line, Type B340, horizontal

Manufacturer: ALSTOM FLUIDES (SAPAG)
 Resp. Technique: Installed
 Status: MBIAH05
 Parent Equipment: MRC MTF1
 Location: Good
 State: MRC MTF1

3 CHECK LIST

Table 1: Executive assembly check list

Step	Description	Reference/picture/drawing	Notes / Acceptance Responsible		Time & people needed for operation
			Cavity 1	Cavity 2	
0	Step 0 – preparation stage				
1	All actions should be done wearing the surgical gloves.				
2	All used materials and components should be degreased before assembly.				
3	Prepare work space and clean surface.				
1	Step 1 – removal of the clean room equipment.		Design contact: Pierre Minginette, Teddy Capelli Step responsible: Matthieu Therasse		
4	Remove a clean room equipment: - Nitrogen filling valve; - Pumping ports. Note: Keep all clean room equipment clean (stored in clean plastic bags).				
4a	Were all the ports of the cavity (HOMS feedthrough pick up feedthrough) checked for visible damage?		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	Person:

- Work just starting on assembly procedure and MTF development
- Have a good starting point from the documentation produced for DQW build.

Overview


- Cavities and ancillaries are well on track for the April '21 delivery to DL.
- Cryomodule Design well advanced, long lead items have drawings released/in approval.
- Long lead Tooling on schedule. Cavity string cleanroom tooling to be on order by end of December.
- Transport frame drawings out for quote, preparations in place for testing.
- Infrastructure upgrades to be completed (some mitigation required for CV-19 and ESS project delays which use the cleanroom)
- Detailed planning for assembly steps and Quality Assurance to begin as of next week (W/C 26/10/2020)

Other news



New working from home colleague

Marla Jones
15/09/2020



DQW Series Cold magnetic shield, first Hardware of HL-LHC-UK2.

Two have been delivered to CERN and tested successfully.