#### **Detector Moving System**

From Tertiary to Secondary beam Inside T9

24.11.20

### Oliver Jeremy

o.jeremy@imperial.ac.uk

# Imperial College London




# **Outline:**

- What is being moved?
- Where is this taking place?
- Possible Moving Systems Initial Concepts
- FEA
- What's Next?




#### The WCTE Detector Dimensions:






### The Main Components:

Component	Mass Kg
Tank	2400
Base	3100
Lid	750
Water	52,500
mPMT Array	10,000
CDS	120
Total	68,870



# **WCTE**Segmented View





CERN East Area


**Experimental Area** 



• Inside T9

Images from M. Hartz / M. Pavin






#### Water Tank Move – Inside T9

#### **Conceptual Methods:**

- Pneumatic Air Skate
- Hydraulic Rail




#### Air Skate

#### **General Specifications for Concrete Floors**

The floor is part of the air film technology and certain floor qualities must apply to ensure efficient operation of the air film equipment. The most important qualities are flatness, free of steps, airtight (non-porous) and smoothness of the surface.


When in operation the air bearing is floating on a thin film of air, the thickness of this air film is about 0,1 mm.




Floor needs to have a max deviation of around 5mm

If T9 floor is not flat, then we can generate a flat surface ourselves





# Air Skate Water Tank Move – Inside T9



X4 air skate shown in yellow

Each skate connects back to a manifold and then onto a compressor

Underside of tank base designed to locate air pad permanently during the experiment

Air Skate Size mm	Lift Capacity Kg	Factor of Safety
□ 1070	120,000	<b>1.7:1</b> 10

#### Imperial College London

#### **Air Skate**







4 Bar/60 PSI of pressure



Winch at each end – to pull tank along and provide a counter force 11

#### **Air Skate**

The Floor, how we control the tank during the move:




Steel rail to guide and retain mass in X

Axis	Degree of Freedom
X	Captive due to rail
Υ	Wire Rope at each end of axis
Z	+ ~40mm lift on air skate

# **Hydraulic Rail**



**Rail Module** 








**Push / Pull Unit** 

# **Hydraulic Rail**


Using a 2 track system		Factor of Safety
	363,018	5:1





# **Hydraulic Rail**








700 Bar / 10,000 PSI (max) of Hydraulic pressure


Axis	Degree of Freedom	
X	Captive across 2 rail	
Υ	Captive along rail	
Z	No Lift, gravity acting on tank	15




# **Water Tank Lifting - Analysis**

FEA carried out on tank full of water


 Initial assessment to understand the tank deformation when lifted










#### **AIR SKATES – TANK AT 6mm THK**








#### **AIR SKATES – TANK AT 6mm THK**





- CERN Transport Group have become involved in past month.
- CERN assessing what equipment they could provide.
- Meetings upcoming to review and progress this part of the project.

