



# SIS100 Superconducting Magnet Series Production

MT 27, TUE-OR1-102-02

***T. Winkler, P. Bartholome Aguar, M. Becker, A. Bleile, R. Blümel, W. Freisleben, M. Janke, F. Kaether, J. Ketter, P. Kosek, F. Kurian, S. Lindner, V. Marusov, F. Marzouki, J.P. Meier, S. Mohite, V. Raginel, C. Roux, K. Sugita, A. Szwangruber, P. Szwangruber, A. Waldt, A. Warth, H. Weiss, N. Pyka, P. Spiller***

Helmholtzzentrum für Schwerionenforschung GmbH

special thanks to: CRY, VAC, SSI, TRI, EPS, RII

## Introduction

- SIS100 Superconducting Cable
- SIS100 Cooling Scheme


## SIS100 Dipole Module

- Design
- Mechanical Accuracy
- Magnetic Field
- Quench Performance

## SIS100 Quadrupole Unit

- Design & Production
- QP Alignment

## Summary and Outlook



## FAIR project member states



High intensity ion and antiproton beams for experiments in nuclear, atomic, plasma physics and material science.



## Compared to the existing GSI facility

- Primary beam intensity: **x100**
- Secondary beam intensities: **x10000**
- Primary beam energies for  $U^{28+}$ : **x10**
- Antiproton production

## SIS100 Magnet Types

In total SIS100 has 415 fast-ramped sc-magnets mounted in 193 modules. There are:

- 108 Dipole Modules
- 83 Quadrupole Doublet Modules
  - 83 Focusing Quadrupole
  - 83 Defocusing Quadrupole
  - 83 Nested Steerer
  - 42 Chromaticity Sextupole
  - 12 Multipole Corrector
  - 4 Low Current Quadrupole for injection and extraktion



## SIS100 Cable

- 1 CuNi cooling tube
- 2 NbTi strand
- 3 CrNi wire
- 4 Kapton tape
- 5 Fibreglas tape


## Helium Cooling Path

All magnets are connected in parallel to one supply line:

- 1 Helium is sub-cooled at Magnet entrance,
- 2 Helium exits coil in two-phase region,
- 2' Helium passes through re-cooler of supply line,
- 3 Helium exits the yoke.


The beam pipe is cooled with a independent circuit, using a similar approach.

Magnet cooling and beam pipe cooling use the same common return line.



Cooling scheme of SIS100 dipole:

- 1 – coil inlet, 2 – coil outlet,
- 2' – re-cooler outlet / yoke inlet, 3 – yoke outlet




## Dipole Timeline

- First dipol delivered: Q3-2017
- Last dipol delivered: Q4-2020
- Last dipol tested: Q1-2021

## SIS100 Dipol Functional Requirements



- $B_{max} = 1.9 \text{ T}$
- $dB/dt = 4 \text{ T s}^{-1}$
- $\Delta B/B < \pm 6 \text{ units}$
- Bending angle  $1\frac{1}{3} \text{ deg}$
- Magnetic length  $3.062 \text{ m}$




## Dipole Gap Geometry

- Required precision:  $68.13^{+0.10}_{-0.0}$  mm,
- Manufacturing precision well within specification,
- Tilt of pole shoes negligible.

$$B \approx \frac{IN\mu_0}{h}$$








## Aperture-Profile - Series Overview



## Test Results





- Magnetic field data have been measured for all 110 dipoles
- Data shows good agreement with simulations, except for  $b_3$  and  $a_2$ ,
- $b_3$  and  $a_2$  deviations are systematic and can be compensated,
- no need for magnet sorting for accelerator installation,
- Magnetic data used for beam dynamic model of SIS100.






## Quench Performance

- Excellent quench performance: 80%, 97%, 99% out of 111 tested magnets exceeded the  $I_n$  at the 1<sup>st</sup>, 2<sup>nd</sup> and 3<sup>rd</sup> training quench, respectively.
- 65% of all dipoles withstood an applied current of 16.9 kA without quenching,
- Very stable DC and AC (2-28 kA s<sup>-1</sup>) operation of all tested dipoles.





## SIS100 QP Unit Functional Requirements

- $B_{max} = 27.77 \text{ T m}^{-1}$
- $dB/dt = 58 \text{ T m}^{-1} \text{ s}^{-1}$
- $\Delta B/B < \pm 6 \text{ units}$
- Magnetic length 1.264 m

## QDM Timeline

- FoS units delivered: Q3-18
- FoS module delivered: Q4-19
- Series production released: Q1-21
- 1st Module delivered: Q3-21
- End of module production: Q2-24

## Delivery Status

- 18 QP-Units delivered
- 1 QDM delivered
- 2 more QDM in 21

## From Production to Installation

- QP unit production at JINR, Russia
- QP unit testing at JINR, Russia
- QDM integration at Bilfinger Noell, Germany
- QDM testing at INFN/Salerno
- QDM installation at GSI


## Other Major Components

- Cryo Collimator from Pfeiffer, Germany
- Beam Pipe from Research Instruments, Germany
- Beam Position Monitor from Kyocera, Germany




# SIS100 Quadrupole Unit Alignment


- One QDM contains two QP Units on one common girder,
- The two QP units can be adjusted independently in steps of 0.2 mrad for yaw and pitch;
- The common girder is positioned in the cryostat such that lateral translation errors are corrected.




Calculation of ideal setup of shims.



Measurement on mounted girder



Calculation of "best" girder positioning



## Summary

- All 108 dipole modules have been successfully manufactured and tested.
- The mechanical and electrical quality of the dipole modules is very good.
- Series production of quadrupole units is well under way.
- QDM series production has started and the first modules have been delivered.
- QP unit alignment on common girder is non-trivial, proof of principle successful

## Outlook

- Current planning foresees the production of QDMs until Q2-24.
- Manufacturing rates of QDMs will have to increase considerably to meet this date.
- Logistics and timing around the QDM involves multiple partners and will be the challenge to solve.
- QDM test program has started and will be the final quality milestone.

Thank you very much for your attention!