

The Canadian Contribution to the ATLAS New Small Wheels


Tony Kwan
McGill University

CAP 2021




June 9, 2021


Path to the High Luminosity LHC





- ▶ **Long shutdown 2 (2019–2021):**
 $\mathcal{L} = 2 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$ for the entirety Run-3
- ▶ **Long shutdown 3 (2025–2027):**
 $\mathcal{L} = 2 \times 10^{34} \rightarrow 5 \text{ to } 7.5 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$
- ▶ Such an intense environment presents challenges for the experiments that use the collisions provided by the LHC.
- ▶ During long shutdown 2, improvements – called Phase-1 upgrades – to the ATLAS detector are ongoing.



ATLAS Muon Spectrometer and High Luminosity



- ▶ At high luminosities, the trigger rate would exceed the readout bandwidth of the ATLAS data acquisition system.
- ▶ In the end-caps, most “muons” firing the trigger would in fact be background hits from particles created in the material between the inner and middle stations.
- ▶ To solve this problem, the plan is to use the inner station to distinguish muons from these fake “muons”.
- ▶ The current small wheel is unable to perform tracking efficiently.





The ATLAS New Small Wheel

- ▶ The New Small Wheel (NSW) will use two different gas detector technologies: **sTGCs** primarily for triggering and **Micromegas** (MM) primarily for precision tracking.

Design/Requirements:

- ▶ Substantially reduce the fakes trigger rate at L1;
- ▶ Reconstruct online muon tracks with 95% efficiency;
- ▶ Excellent spatial and angular resolutions: $< 50 \mu\text{m}$ for offline momentum reconstruction and $< 1 \text{ mrad}$ for online matching with Big Wheel;
- ▶ Operate for the entirety of the HL-LHC.



- ▶ Canada is contributing to the construction of 54 (of 216) sTGC modules (“quadruplets”).
- ▶ Other sTGC construction site countries are Chile, China, Israel, and Russia.

Small-Strip Thin Gap Chamber Technology

sTGC Chambers:

- ▶ Multiwire ionization chambers operated with a pentane-CO₂ gas mixture;
- ▶ Operating voltage of 2.8 kV.

Wires:

- ▶ Acting as our anode, wires provides a coarse measurement of the trajectory in the ϕ - or azimuthal-direction.
- ▶ Sandwiched between two cathode planes with a distance of 1.4 mm between the anode and cathode.

Strips:

- ▶ On one of the cathode planes, strips have a pitch of 3.2 mm;
- ▶ Used to provide precision measurements of muon trajectory in the η -direction.

Pads:

- ▶ On the other cathode plane are pads, which are used to trigger readout of the strip in a localized region of the detector.

→ Each *quadruplet* module consists of 4 pad-wire-strip planes.





Fig: L. Guan

The Canadian sTGC Construction Project



- Commercially made circuit boards etched with copper strips and pads are coated with graphite.
- Boards are then shipped to Carleton University, Ottawa.



Carleton
UNIVERSITY

- Anode wires are strung, and gaps and quadruplets are assembled.
- Adapter boards are mounted.
- Finished modules are sent to McGill University, Montreal.






McGill
UNIVERSITY

- Detectors are characterized and tested for quality and performance using cosmic muons.
- They are then shipped to CERN, Geneva, where they are formed into wedges that will make up the NSW.



Construction



Graphite spraying

Half-gap production


Wire winding

Gap closing

Doublet assembling

Quadruplet assembling

Cosmics testing





QA/QC

Quality assurance / quality control tests are performed throughout the construction process. Tests include:


- ▶ High voltage tests at the singlet, doublet, quadruplet stages to check for sparks, shorts, and leakage currents;
- ▶ X-ray scans to measure gain uniformity of single gaps and to probe internal structure;
- ▶ Electrical connectivity checks of the readout channels;
- ▶ Gas leakage checks to ensure no leaks, e.g. from a crack, are present;
- ▶ Readout noise using prototype front-end boards;
- ▶ Cosmics testing to measure efficiency and resolution of finished quadruplets, and the relative misalignment of individual gaps.

→ Detectors that pass all tests are shipped to CERN where they are assembled into wedges then sectors to be installed into the NSW.



NSW Public Results






Canadian Production



sTGC Performance

CERN Test Beam:

- ▶ Pad charge distribution studies at H8 beam-test area (top left).
- ▶ Pad charge distribution studies in GIF++ using a muon beam in the presence of high rate photon background (top right).
- ▶ Residual distributions of reconstructed perpendicular tracks (bottom left). For more details, see [poster by Lia Formenti](#).
- ▶ In-situ measurement of the sTGC strip spatial resolution as a function of the applied high-voltage using a low-rate muon beam in the H8 beam-test area (bottom right).




NSW Public Results

Sector Installation and Commissioning

- ▶ Construction of sTGC and Micromegas modules for both NSW-A and C is nearing completion.
- ▶ Sector assembly, installation, and commissioning well underway (with major contributions from Canadians).

Sector	Type	Date of installation	Commissioning status
A14	Small	11/12/2020	Ongoing
A12	Small	16/12/2020	Complete
A16	Small	11/01/2021	Complete
A10	Small	17/12/2020	Complete
A08	Small	18/01/2021	Complete
A02	Small	25/01/2021	Complete
A06	Small	11/09/2020	Complete
A04	Small	08/02/2021	Complete
A13	Large	27/04/2021	Complete
A11	Large	19/04/2021	Complete
A15	Large	13/05/2021	Complete
A09	Large	05/05/2021	Ongoing
A01	Large	19/05/2021	Ongoing
A07	Large	25/05/2021	To be started
A03	Large	26/05/2021	To be started
A05	Large	28/05/2021	To be started



Commissioning of NSW-A expected to be completed by June 17.

Conclusions

- ▶ Inclusion of the NSW into the ATLAS detector is imperative in order to maintain high trigger efficiency and momentum resolution in the high luminosity environment of the LHC and HL-LHC for years to come.
- ▶ Production of both sTGC and Micromegas modules is nearly complete while sector assembly at CERN has kept pace.
- ▶ Canada has played a key role in the NSW project, from construction of sTGC modules to contributing to vital NSW operations at CERN.



Status of NSW-A:

- ▶ All 8 small sectors installed; all 8 large sectors installed.
- ▶ Commissioning well underway.
- ▶ Expected to be completed by 29/07/2021.
- ▶ **NEWS:** ATLAS has given the green light for installation.

Status of NSW-C:

- ▶ Three small sectors installed; large sectors yet to be assembled.
- ▶ With the experience gained from NSW-A, commissioning expected to be streamlined.
- ▶ Must be completed by 21/10/2021 to be installed during this shutdown.