


# ELENA Status and Recent Progress



C. Carli on behalf of the AD/ELENA team


AD Users Committee 19<sup>th</sup> January 2021



- ❑ Ion Source
- ❑ Transfer Line Commissioning
- ❑ ELENA Ring Studies
- ❑ Profile Monitors
- ❑ Summary and Outlook

# Transfer line commissioning

## General





- Main target for 2020
- Some delay with preparations mainly related to Covid
- Preparations (source, ring, LLRF, profile acquisitions ...) end of August and September
- Proper start of transfer line commissioning towards end of September

# Transfer Line Commissioning LNE50 (GBAR Experiment)





Studies done and material provided by SY/ABT team

- Quad scan using LNE50.QD10 and LNE50.QF11 and observing on LNE50.BSGW60



LNE50 Start	$\epsilon_x$	$\alpha_x$	$\beta_x$	$D_x$	$\epsilon_y$	$\alpha_y$	$\beta_y$	$D_y$
Design	NA	2.63	4.22 m	0.90 m	NA	0.52	5.39 m	0
Measurement	$2.78 \mu\text{m}$	7.44	11.2 m	1.56 m	$1.52 \mu\text{m}$	-0.08	2.68 m	0.43 m





# Transfer Line Commissioning LNE50 (GBAR Experiment)



- Average results of several quad scans used for rematching (three different cases)

LNE50 Start	$\epsilon_x$ ( $\mu\text{m}$ )	$\alpha_x$	$\beta_x$ (m)	$D_x$	$\epsilon_y$ ( $\mu\text{m}$ )	$\alpha_y$	$\beta_y$ (m)	$D_y$
Design	NA	2.63	4.22	0.90	NA	0.52	5.39	0
Avg. Measurement	$3.89 \pm 0.69$	$5.37 \pm 1.21$	$8.67 \pm 1.65$	1.58	$1.55 \pm 0.18$	$-0.09 \pm 0.24$	$2.55 \pm 0.72$	0.43 m





Studies done and materiel provided by SY/ABT team

# Transfer Line Commissioning LNE50 (GBAR Experiment)



- Observation of Coupling
  - Tilt of beam seen by the experiment on MCPs images (taken with different optics settings)
  - Should not be an issue provided emittances are small enough?
  - Systematic investigations?




- Vertical dispersion measured in lines (and as well in ring)

# Transfer Line Commissioning ALPHA Line



- Beam on all monitors between ELENA extraction and the ALPHA experiment






# Transfer Line Commissioning ALPHA Line





- Quad scan at beginning of line using observing on LNE00.BSGW15



Studies done and material provided by SY/ABT team

LNE00 Start	$\epsilon_x$	$\alpha_x$	$\beta_x$	$D_x$	$\epsilon_y$	$\alpha_y$	$\beta_y$	$D_y$
Design	NA	2.63	4.22 m	0.90 m	NA	0.52	5.39 m	0
A Measurement	3.44 $\mu\text{m}$	1.21	3.31 m	1.37 m	1.88 $\mu\text{m}$	0.54	3.95 m	- 0.37 m




# Transfer Line Commissioning ALPHA Line




- Beam observed by ALPHA on MCP on 9<sup>th</sup> December
- Rematching to make beam round


- Vertical dispersion (small) measurement



- Horizontal dispersion measured along line close to expectations



First  $H^-$  Beam seen by ALPHA on MCP




After rematching with last three quads  
(to obtain round beam)



# Transfer Line Commissioning BASE Line




- Last of the available lines tested
- “Long” section with two bendings and without monitors
- End of line again reached quickly
- Beam not well centered in region between bendings
- Quadrupole setting variations and observation on downstream monitor used to improve



# Transfer Line Commissioning BASE Line





- Quad scan “close” to end of line
- Static bend between quads used and monitor for vertical measurement



Studies done and materiel provided by SY/ABT team

LNE00 Start	$\epsilon_x$	$\alpha_x$	$\beta_x$	$D_x$	$\epsilon_y$	$\alpha_y$	$\beta_y$	$D_y$
Design	NA	2.63	4.22 m	0.90 m	NA	0.52	5.39 m	0
A Measurement	$3.04 \mu\text{m}$	2.77	4.50 m	1.40 m	$1.47 \mu\text{m}$	0.83	3.55 m	- 0.23 m



# Ion Source Status



## ■ New (August 2020) insulation transformer

- Proven to be fine in **DC at 100 kV** for  $H^-$  operation
  - no partial discharge audible
  - no tests done for p operation
- Decided to **run anyway in pulsed mode**
  - from  $\sim 60\text{kV}$  to  $100\text{kV}$  in about 1 second before each beam

## ■ Consolidation of control and diagnostics

- Integration of **timing** with CERN control system
- Single shot **beam intensity measurement** at the source now permanently available on Oasis
- Added a viewport to allow for the installation of **beam screen** just in front of the source for diagnostic purposes

## ■ Still open issues:

1.  $H^-$  pulse intensity stability
2. Beam position drift over time

■ **Note:** many details documented in *NIBS2020 proceedings*

Slides by Davide Gamba  
on behalf of team working on source



# Ion Source

## H<sup>-</sup> pulse intensity stability



- Already identified in the past as **intra-pulse intensity fluctuation** of extracted H<sup>-</sup>



- Two possible **workaround** found:

- **Injecting more gas** (x5 more than usual)
- **Working at low “arc” voltage:**
  - limited beam intensity
  - From experience, this mode seems to keep orbit stability for longer periods
  - Setting used for line commissioning => lower intensity fine with excellent profile monitor performance

- Issue **not observed on p** production:

- This seems to exclude problems on the plasma generation and/or on the extraction system
- Something is perturbing the delicate H<sup>-</sup> production mechanisms
  - **Poor quality of used H<sub>2</sub> source?**  
Hypothesis under investigation

Slides by Davide Gamba








# Ion Source

## Beam position drift over time



- Source of the orbit drift **tracked back into the ion source assembly**
  - **Profile monitor** installed in LNS showed the orbit drift starting already right after the ion source
  - Movement could be observed on a **dedicated screen** installed in front of the ion source
- Movement (charging up) can be **triggered by higher negative puller voltage** settings
- Several observations points in the direction of **charging up happening in the puller region**
  - Proper investigation/fix may require to **disassemble the source: lengthy and risky manipulation!**
- Present **workarounds**:
  - B. Lefort working on **automatic steering** looking at turn-by-turn data in ring BPMs
  - New **beam screen with 10mm diameter hole** will be installed in February to ease operation






# ELENA Ring Studies

## Hysteresis Effects - Quadrupoles



### Measurements

- Initial settings:  $Q_H \approx 2.435$  and  $Q_V \approx 1.412$
- With +5 A bump on QFNS circuit before injection



$Q_H \approx 2.442$  and  $Q_V \approx 1.408$

- $\Delta Q_H \approx 0.007$  and  $\Delta Q_V \approx -0.004$

### Expectations

- Change of integrated gradient due to hysteresis (based on magnetic measurements)



$$\Delta k_l \approx 4G/457 \text{ Gm} \approx \pm 0.008 \text{ m}^{-1}$$

- With  $\beta_H \approx 7.8 \text{ m}$  and  $\beta_V \approx 3.4 \text{ m}$  at QFNS location

$$\Delta Q_H \approx 4 \Delta k_l \beta_H / (4\pi) = 0.020 \text{ and}$$

$$\Delta Q_V \approx 4 \Delta k_l \beta_V / (4\pi) = -0.009$$

- Observed effect smaller than expected





# ELENA Ring Studies

## Electron Cooler Studies



- Compensation of perturbations caused by the magnetic system of cooler
  - Orbit correction (and optimization of trajectory in cooler with circulating beam)
  - Compensation of coupling (between horizontal and vertical motion) introduced by longitudinal field
    - Tunes (fractional parts) programmed to cross
    - Signature of coupling is that measured tunes do not cross (left image)




- Adjustment of working point
  - Focusing in both planes introduced by cooler and compensation solenoid

# ELENA Ring Studies

## Electron Cooler Studies



- Measurement of electron beam position inside cooler
  - With pick-ups used as well for circulating beam
    - Electron beam current modulation to generate pick-up signal (at revolution frequency for acquisition with electronics for circulating beam)



Horizontal position of electron beam seen by two pick-ups in cooler



- Will help to adjust overlap between circulating and electron beam and speed up electron setting-up with antiprotons (and, in principle any other ion with appropriate life-time)
- Aim for next weeks: keep (magnetic system of) cooler on during  $H^-$  operation to gain experience with more complicated machine
  - Test effect of electron beam on circulating  $H^-$ : low life-time? Any chance to see cooling effect? ..

# ELENA Ring Studies

## Extraction Timing Tests for h=4



- Only one out of four “buckets” filled with H<sup>-</sup> (nominal: all buckets filled with identical antiproton bunches)
- Fast deflectors to extract beam out of ring pulse correctly (e.g. GBAR extraction quarter of turn later for case on right side with three experiments in “old” zone expecting beam)
  - Fast deflectors in line (see below deflection towards ALPHA/ATRAP) did not pulse correctly (corrected in between)



Programmed destinations: ALPHA and GBAR

- Both deflectors pulse simultaneously
- Bunch #3 seen in LNE50 (GBAR) line


Programmed destinations: AEGIS, ALPHA, ASACUSA and GBAR

- LNE00 extraction later than LNE00 extraction
- Bunch #4 seen in LNE50 (GBAR) line


# Broken BTV Screen



- BTV118 luminescent screen between injection septum and kicker and observed with camera
  - Heavily used to observe H<sup>-</sup> beam from source tending to “move around”
  - Movement system damaged probably related to heavy use (regular in/out movements)
  - Screen now blocked in out position since 15<sup>th</sup> October



One of the last BTV118 acquisition (now blocked in “OUT” position)




Reliable operation possible with last profile monitor LNI.0060 in front of injection septum (despite many missing channels)!!

- Strategy for antiproton run(s)
  - Spares and/or upgraded mechanics not available on time for 2021 run
  - Replacement of profile monitor just before injection septum instead in spring/early summer



- Tremendous progress since about a year with acquisition electronics etc.
  - Lines towards GBAR, ALPHA and BASE and one of ASACUSA lines fully equipped with monitors
  - All installed monitors equipped with front-end electronics
  - Good results so far despite missing channel problem
    - ◆ Clear information on beam position and most profiles good enough for optics studies
    - ◆ Working well with low  $H^-$  intensities
  
- Completion of installation and long-term
  - Availability of pieces to complete lines about fine
  - Concerns on long-term reliability
    - ◆ Leaks of DN50 feed-throughs on “bellow units”
    - ◆ Missing channel problem probably related to bake-outs
    - ◆ Attempt to exchange of feedthrough by CERN workshop
  - Electronics handed over to CERN engineer
  - Investigations by SY/BI on CERN made solutions for electrodes and bellow units





- Preparations for transfer line commissioning (details see talk by Francois)
  - Impact of COVID19 “limited”
    - Installations (in particular transfer line cabling) resumed soon after restart of on-site activities
  - Ready to start work with beam (other than source tests) in ring by second half of August
  
- Commissioning activities
  - Transfer line commissioning in full swing
    - Beam reached end of all available lines with moderate effort, including the longest ALPHA line
    - Matching looks reasonable everywhere
      - => congratulations to the team doing the solid design!
    - Systematic investigations (quad-scans ...), possibly followed by some rematching on-going
  - In parallel, many studies to better understand ELENA ring and speed up antiproton restart
  - Improved understanding of source vital – now excellent reproducibility of ring and lines
  - Availability and good performance of profile monitors!
  - Concern: test of perturbations of AEGIS solenoid on transfer line possible only soon before restart
    - Steerers strong enough to correct, may require some coordination between experiments
  
- **On track for first 100 keV antiproton physics run for all experiments from August 2021!** (for details see next talk by Laurette)