

# PT status and planning

Michael Pešek  
Charles University, Prague


# Outline

- Magnet commissioning and dry-run outcome
- Gunn diode status
- Planning

# Magnet timeline

- 29/10 magnet at 4K
- 3/11 cryostat full with lHe
- 3/11 start MSS commissioning
- 11/11 dipole at full current
- 16/11 solenoid at full current
- 23/11 NMR communication test
- 24/11 safety region for field rotation check,  
dipole + to solenoid + to dipole +

# Field rotation



# Magnet summary

- Magnet cooling test successful!
- Very efficient work with EP-DT
- Few minor hiccups due to upgraded power convertor system
- To be done before next cool-down:
  - exchange LN2 turret o-ring
  - clean power cables connection at magnet turret
  - check IHe level gauge

# Gunn diode test

- Gunn diode delivered in October
- 1/12 First test in “laboratory conditions”



Gunn diode  
Power supply

Control PC

Oscilloscope

10 MHz  
reference

Gunn diode

# Gunn diode test

- 3/12 move the test setup to 888
- Successful generation without magnetic field
- Generation stopped in magnetic field ( $\sim 30\text{mT}$ )
- Fuse exchanged in the PS
- 7/12 measure cooling fan consumption in magnetic field
- Exchange 5 A fuse for 10 A
- 8/12 USB connection problem → fix USB connection in the synthesizer box
- 9/12 successful generation with and without field


# Gunn diode test

- Full system sent back to manufacturer for modifications:
  - improve the cooling system (fans)
  - frequency modulation
  - larger frequency range (currently 69.8-70.2 GHz)
  - fuse holder (for easier fuse exchange)
  - heat protection and temperature monitoring (via DCS)



# Gunn diode installation


- New support table needed (about 1 m from DR)
- New air blower to be installed (cooling)
- Long wave guides needed



# General

- LHe stopped on 8/12 → warming up
- Diffusion pump stopped on 16/12
- $^3\text{He}$  circuit to be reconnected

# Planning



# Manpower

- Nori, Christophe, MP
- Jaakko:available
- Gerhard R., Kaori, Stefan R., others: tbc

# Spare

# Safety region for field rotation

MSS for field rotation

