

# 04.05.2021 TB Report of H1 status


Benjamin Moritz Veit

4. Mai 2021



# H1 PMTs Intervention and new PMTs

- **Long time tests in dark box with old XP2980**  
Until now ( $\approx$  3 Month with 1850V)  $\rightarrow$  No failures - beam related or luck?!
- **Two new (ET Enterprise 9128B) PMTs are equipped with modified bases and under testing now:**





Setup for teststand for characterization is under preparation.  
(LED source and ADC read-out is working)

We plan to buy 12+2 new ones still before the run!



# H1 Discriminator (Week15)

HI04 Orsay Discriminator installed in Veto barracks




Orsay Discriminator have superior performance in respect to CAEN (double pulse resolution).  
Infrastructure installed (Modified Crate, CPU, Signal Splitter).


Discriminator tested → One channel on one connector is broken!



# Cyanacrylat glue tests (Measurement of 07.04.2021 Optical Lab)



# Cyanacrylat glue tests (CERN Optical Lab)



Loctite 406 is suitable for optical gluing of scintillators!

## Begin of Work - disassembly of modules



- Johannes G., Johannes M. and Livio R. arrived in Week 16  
→ start of main work.
- Disassembly of modules started  
- lot of work - everything glued together.
- All slabs are inspected and in case of need re-packed.
- 8 out of 52 lightguides are broken - not clear if it happen during movement or before.

# Polishing old Lightguides




- 12+8 Lightguides had to be reused

# Gluing of slabs





- All lightguides are glued with help of a gluing rack
- Process was optimized to allow to glue in a 2 h rhythm
- Success rate about 80% → remaining were re-glued

# Mechanics



- Small modifications of the rohacell dimensions were needed.
- Central hole was cut out.
- Mechanics for rotation is prepared.
- Modules are not glued to the rohacell to allow for final alignment with minimal gaps.

# Assembly of Modules




Two Modules are already fully assembled and made light tight!



# Air Light Guide

High reflective foil Enhanced Specular Reflector (3M ESR) was bought (according to COMPASS Note 2011-5) - turned out to be the wrong one (thicker, no adhesive layer).




Investigation was performed: 3M Specular Film DF2000MA seems to be a good replacement (used by many experiments for this purpose).

Supplier was identify which has 2 lm on shelf - registration is pending at the procurement office at the moment!

# Air Light Guide stack

It was decided to sandwich air-light-guide with two plates of 0.5 mm G10-FR4 material.



2 · 0.5mm G10-FR4 will add a lot of stiffness and a plane surface for the reflector foil - costs in terms of radiations length: 0.5%

Material	Radiation length /cm	Thickness /cm	X/X0 /%
G10	19.4	0.05	0.257731959
PVC	19.63	0.015	0.076413653
<u>Rhoacell</u>	760.43	1	0.131504543
<u>PMMA</u>	34.07	1	2.935133549
BC408	42.54	1	2.350728726

# Summary



- Mechanical modifications of rohocell finished after test fitting of scintillators.
- All modules are disassembled and checked → Total of 8 broken LG
- All slabs are inspected and if needed repacked.
- All new and broken slabs are re-glued.
- Waiting for material for central module.
- Testing in clean-area foreseen.
- Electronics / PMT well progressing.
- **2 out of 5 Modules completed!**

**Some delay due to missing reflective foil for the central air-lightguides. Going vertical → end May / begin June - still possible!**

# Thanks a lot to the Team!

Johannes Giarra, Johannes Merz, Stefano Levorato, Livio Rinaldi

+ support of Triloki and Daniele D'Ago

+ all future help by colleagues to get finish in time!