



# Beam induced heat load measured during Run2 in LSS

Benjamin Bradu, *on behalf of HiLumi WP9*  
*TE-CRG*

*Special Joint HiLumi WP2/WP5 Meeting – 26<sup>th</sup> January 2021*

# Summary


- Introduction
- LSS BS heat load measurements method
- LSS BS heat load measurements in Run 2
- a-C coating in LSS : Cryo priorities

# Introduction

- Cryogenic cooling power is limited for beam screens
  - Locally in each loop (hydraulic limitation → ~120W/SAM )
  - On the global cryoplants (cooling power limitation → ~10kW/sector)
- Beam Screen heat loads applied on the existing refrigerators will evolve for HL-LHC
  - Some magnets in LSS1&5 will be removed 😊
  - BS heat loads will increase in ARC and LSS from Run 3 😞  
due to the intensity/energy increase (sync. rad + image current + e-cloud)
- One possible mitigation is the a-C coating in some LSS magnets to suppress the e-cloud component
- Superconducting magnets concerned in LSS:
  - Inner Triplets (+D1)
  - SAM: D2,D3,Q4,Q5,Q6


# LSS BS heat load measurement method

- BS Heat loads are measured over a cryo cooling loop
  - A cryo cooling loop embeds several magnets
  - It passes through one aperture and then by the other (for SAM)
  - Use the valve aperture, the  $\Delta P$  and the  $\Delta T$  over the loop to deduce the corresponding heat load
- Example of one SAM cooling loop (*D2Q4-L2*) :




# Calibration of measurements

- One parameter was not well known (valve rangeability) to estimate the heat loads precisely
- In YETS 2017/2018, a calibration campaign was done to estimate this parameter precisely
- Following this calibration, an error <15% is assumed on the heat load calculations



# LSS heat load measurements in Run 2


- Heat loads computed from fill #6675 (May 2018)
  - Inj. scheme: 25ns\_2556b\_2544\_2215\_2332\_144bpi\_20injV2 @ 6.5 TeV
- Reminder: BS heat load in a sector is between 4 kW and 8 kW
  - LSS heat loads represent less than 10% of total beam screen heat load in a sector during Run2



# SAM heat load estimation for HL-LHC



- **Very complicated to estimate the SAM heat loads for HL-LHC era**
  - Several magnets over a cooling loop
  - Large zoo of magnets/chambers
  - Large spread of SEY in each magnet/aperture can be imagined
  - SEY dependency is very different between quad, dip and drift (and non-linear)
  - Between SEY = 1.1 and 1.3, a factor 25 on heat loads is observed on simulations !

See [CERN-ACC-2016-0112](#) *Beam induced heat loads on the beam-screens of the twin-bore magnets in the IRs of the HL-LHC.*



# What we can learn from Run 2 ?

- Make some hypothesis / simplifications (worst case)
  - All heat loads are coming from e-cloud (sync. rad. + impedance neglected)
  - All the e-cloud are coming from the quad in Q4/Q5/Q6 and from the dip in D2&D3
- Estimate the average SEY from heat loads observed in Run 2
  - It seems that we have SEY < 1.2 in all SAM (even <1.15 for many of them)
- Replay e-cloud simulations with SEY=1.15 & 1.2 to refine heat loads for HL-LHC





# Cryo Priorities for a-C coatings

- **a-C coating is interesting for cryo:**
  - If the refrigeration capacity margin of the sector is limited (like in S23&S78)
  - If the beam screen heat loads are significant in a specific SAM (SAM valve apertures were doubled during LS2 to allow a max extraction of ~120 W)
  
- **Cryo priorities for LS3:**
  1. All new magnets around IP1&5: current baseline
  2. All IT around IP2&8: current baseline
  3. SAM in LSS 23 & 78 (weak sectors)
    - D2Q4R2 + D2Q4L8 + Q5R2 + Q6R2 + Q6L3 + Q6R7+ Q6L8 (Q5L8 already done)
  4. SAM with significant heat loads approaching the 120W in HL-LHC
    - To be checked with simulations at SEY=1.15 & 1.2

# Conclusion

- LSS heat loads have been assessed during Run 2
  - SEY in SAM seems  $< 1.15$  or  $< 1.2$
- LSS heat loads estimations for HL-LHC should be re-assessed with appropriate SEY
- BS heat loads in SAM will be confirmed (or not) during Run3
  - Refinement of observed SEY at higher intensities
  - Final validation of needed coating during LS3

# SAM heat loads during Run2 at a glance

