

INTEGRATION OF FCC-EE/HH

Released work

- Integration of FCC-ee machine elements at Point A and G
 - *FCC-ee/hh Underground Structure*
 - *FCC-ee/hh enlargement*
 - *FCC-ee/hh Experiment Cavern*
 - *FCC-ee/hh Service Cavern*
 - *FCC-ee/hh Connection Tunnel*
 - *FCC-ee/hh Transport Tunnel*
 - *FCC-ee Machine Tunnel Section 1 at Tunnel A*
- FCC-ee/hh Underground Structure and Surface at Point B
- FCC-ee/hh Underground Structure at Point C
- Integration of FCC-ee machine elements in SSS (Short Straight Section) Point A, B, G and L
 - *FCC-ee main ring machine elements*
 - *FCC-ee booster ring machine elements*
- Integration of FCC-ee RF machine elements at Point D and J
 - *FCC-ee RF machine elements (H)*
 - *FCC-ee RF cross section (ttbar2)*

What's next


- Integration FCC-ee Underground Structure at Point A and G
- Integration of FCC-ee machine elements at Point A
- Integration of FCC-ee machine elements in SSS (Short Straight Section) Point A, B, G and L
- Integration FCC-ee Underground Structure at Point D
- Integration of FCC-ee RF machine elements at Point D
- FCC-ee extraction areas
- FCC-ee injection areas
- Outlines of surface sites (Experiment and Technical surface sites), determine the size of buildings for the needs of services.





RELEASED WORK

Remind : All studies take into account
both requirements from
ee AND ***hh*** Colliders


FCC-ee/hh Underground Structure at Point A and G




Collider Center





FCC-ee/hh Underground Structure at Point A and G



- FCC-ee/hh Experiment Cavern




- FCC-ee/hh Services Cavern







- FCC-ee/hh Connection Tunnel

FCC-ee/hh Underground Structure at Point A and G






- FCC-ee/hh Transport Tunnel



- FCC-ee Machine elements at Section 1 Tunnel



FCC-ee/hh enlargement




	Length of the tunnel (m)	ee ring and booster ring separation (m)
Section 1	700	13.5
Section 2	200	11
Section 3	200	6.6
Section 4	200	2.1

Data: K. Oide (FCC-ee), A. Langner (FCC-hh = FCC-ee booster); enlargement steps: M. J. Stuart

FCC-ee/hh Underground Structure at Point B (L)





FCC-ee Underground Structure at Point B



FCC-hh Underground Structure at Point B

FCC-ee/hh Underground Structure at Point C (E,F,H,I,K)






Standard Access point Configuration

Integration of FCC-ee machine elements in SSS (Short Straight Section) Point A, B, G and L

FCC-ee main ring

D: dipole, Q: quadrupole, S: sextupole

Spacing Between Magnets (m)

D-Q	0.3	(A)	
Q-S	0.3	(B)	
S-S	0.1		
S-D	0.3	(C)	


Case	Arrange	Numbers	Length of D (m)
(A)	Dx-Q-Dx	492	24.432
(B)	Dx-Q-S-Dx	1256	22.732
(C)	Dx-Q-S-S-Dx	1152	21.232

Length (m)


Q	2.9 twin aperture
S	1.4 single aperture

Table provided by Katsunobu Oide on 24.7.2018

Circumference: 97749.3853618 m
 Length LSS: 1400.00012067 m
 Length ESS: 2800.00001315 m
 Length LARC: 15539.1945862 m
 Length SARC: 3183.45094234 m
 Length DS_{hh}: 553.675156092 m
 Cell length in LSS: 50.0000043098 m
 Cell length in ESS: 100.000000526 m
 Cell length in SARCs: 54.8870852127 m
 Cell length in LARCs: 53.9555367575 m
 Cell length in DS_{hh}s: 55.3675156092 m
 Number of cells per LSS: 28
 Number of cells per ESS: 29
 Number of cells per SARC: 58
 Number of cells per LARC: 288
 Number of cells per DS_{hh}: 10
 Length of dipoles: 11.1 m
 Length of quadrupoles: 1.5 m
 Length of sextupoles: 0.5 m
 Distance quad-sext: 0.15 m
 Distance sext-bend (SARC): 0.896771303179 m
 Distance sext-bend (LARC): 0.663884189371 m
 Distance bend-bend: 0.65 m



FCC-ee booster ring



Data and diagram provided by Bastian Harer on 27.7.2018

Integration of FCC-ee machine elements in SSS

Main ring magnet information

(if half-cell length reserved for a single – long – dipole is distributed over 3 – shorter – dipoles):

Case A:

Magnet	Length	Weight	Number of magnets
Dipole	7.94	~2000	8700
Quadrupole	2.9	~4500	3480

Case B:

Magnet	Length	Weight	Number of magnets
Dipole	7.37	~1840	8700
Quadrupole	2.9	~4500	3480
Sextupole	1.4		832


Case C :

Magnet	Length	Weight	Number of magnets
Dipole	7.21	~1800	8700
Quadrupole	2.9	~4500	3480
Sextupole	1.4		2336

Booster magnet information

(if half-cell length reserved for 2 dipoles is distributed over 3 dipoles):


Magnet	Length/m	Weight	Number of magnets
Dipole	7.4		9020
Quadrupole	1.5		3540
Sextupole	0.5		1568



Metallic structure:

Profile	Dimension in mm	kN m	Weight kg/m
	120x60x6	625	15.6


Integration of FCC-ee machine elements in SSS



Layout cross section:


Space reservations for Survey elements

- 3 x WPS sensors + Wire Space (vertical arrangement)
height x width → 0.3 x 0.3 (m)
- WPS Wire Replacement System: mechanics
height x width → 0.5 x 0.3 (m)
- WPS Wire Replacement System: suction
height x width → 0.3 x 0.3 (m)
- HLS Pipe (curved in horizontal plane)
Slope = 1.4%, length 38 m
height x width → 0.65 x 0.1 (m)
- HLS Refill System
height x width → 0.3 x 0.4 (m)
- HLS sensor
height x width → 0.2 x 0.15 (m)
- Element Girder
- Survey Equipment Support



Alternative cross section

Absorber cooling circuit



Busbar cooling circuit




Collider Center

Alignment space reservation



Integration of FCC-ee machine elements in SSS


Perspective view




Collider Center
→

Integration of FCC-ee machine elements in SSS


"Case A": main ring SSS without sextupole; followed by 24.432 m for dipole(s)



Side view





Integration of FCC-ee machine elements in SSS



Robot positions in the tunnel

Integration of FCC-ee RF machine elements at Point D and J

	Z		WW		ZH		$\bar{t}\bar{t}_1$		$\bar{t}\bar{t}_2$	
	per beam	booster	per beam	booster	per beam	booster	2 beams	booster	2 beams	booster
Total RF voltage [MV]	100	140	750	750	2000	2000	9500	9500	10 930	10 930
Frequency (MHz)	400									
RF voltage [MV]	100	140	750	750	2000	2000	4000	2000	4000	2000
E_{acc} (MV/m)	5.1	8	9.6	9.6	9.8	9.8	10		10	
# cell / cav	1	4	4	4	4	4	4		4	
V_{cavity} (MV)	1.92	12	14.4	14.4	14.7	14.7	15		15	
# cavities	52	12	52	52	136	136	272	136	272	136
# CM	13	3	13	13	34	34	68	34	68	34
T operation (K)	4.5		4.5		4.5		4.5		4.5	
Dyn losses/cav (W)	14	11	210	26	202	29	210	30	210	30
Stat losses/cav (W)	8		8		8		8		8	
Q_{ext}	4.4×10^4		6.6×10^5		1.9×10^6		4×10^6		4.7×10^6	
P_{cav} (kW)	962		962		368		175		149	
Frequency (MHz)	800									
RF voltage (MV)							5500	7500	6930	8930
E_{acc} (MV/m)							19.8	20	19.8	19.8
# cell/cav							5		5	
V_{cavity} (MV)							18.6	18.75	18.6	18.6
# cavities							296	400	372	480
# CM							74	100	93	120
T operation (K)							2		2	
Dyn losses/cav (W)							66	10	66	10
Stat losses/cav (W)							8		8	
Q_{ext}							3.9×10^6		5.6×10^6	
P_{cav} (kW)							176		155	





Detailed RF configuration of each machine and booster ring


Courtesy O. Brunner

Integration of FCC-ee RF machine elements at Point D and J (H)

- 400 MHz cryomodules (ø 1.14 m x 12 m), half LSS
- 17 e⁺e⁻ CM + 9 booster CM = 26 CM (476.2 m)
 - 68 klystrons



Machine tunnel



Waveguide

Transport/klystron gallery

Transport vehicle

Klystron, circulator & rack

Safety passage

Faraday cage

Collider Center




Integration of FCC-ee RF machine elements at Point D and J (H)

QRL \emptyset along 400 MHz section 0.65 m.


Preliminary length of half LSS 400 MHz 476.2 m (H machine)
 (nota: inner 2 x 645.7 m left empty for later ttbar installation)

Distance between e^+e^- quadrupoles 40 m, length 3.5 m.

Distance between booster quadrupoles 50 m, length 1.5 m.





Integration of FCC-ee RF machine elements at Point D and J (ttbar2)




800 MHz cryomodule (ø 1.09 m x 9 m), half LSS

- 24 e⁺e⁻ CM + 30 booster CM = 54 CM (645.7 m)






400 MHz cryomodules (ø 1.14 m x 12 m), half LSS

- 17 e⁺e⁻ CM + 9 booster CM = 26 CM (476.2 m)






Integration of FCC-ee RF machine elements at Point D and J (ttbar2, 400 MHz)



QRL ϕ along 400 MHz section 0.65 m.
 Preliminary length of 400 MHz section 476.2 m.
 Distance between e^+e^- quadrupoles 40 m, length 3.5 m.
 Distance between booster quadrupoles 50 m, length 1.5 m.


Integration of FCC-ee RF machine elements at Point D and J (ttbar2, 800 MHz)



QRL \emptyset along 800 MHz section 0.85 m.
 Preliminary length of 800 MHz section 645.7 m.
 Distance between e^+e^- quadrupoles 40 m, length 3.5 m.
 Distance between booster quadrupoles 50 m, length 1.5 m.

Integration of FCC-ee RF machine elements at Point D and J

Courtesy L. Taviani



Working point	Luminosity ($10^{34} \text{ cm}^{-2} \text{ s}^{-1}$)	Tot. lum./year ($\text{ab}^{-1}/\text{year}$)	Goal (ab^{-1})	Run time (years)
Z first two years	100	24	150	4
Z other years	200	48	10	1-2
W	25	6	5	3
H	7.0	1.7	5	3
RF reconfiguration				1
tt 350 GeV (first year)	0.8	0.20	0.2	1
tt 365 GeV	1.4	0.34	1.5	4





Peak luminosity per IP, total luminosity per year (two IPs), luminosity target, and run time for each FCC-ee working point.

Shutdown	No. cryomodules	Length of shutdown
Shutdown 1	-	12 weeks
Shutdown 2	-	12 weeks
Shutdown 3	10 CM	12 weeks
Shutdown 4	26 CM	20 weeks
Shutdown 5	21 CM	14 weeks
Shutdown 6	42 CM	18 weeks
Shutdown 7	30 CM	15 weeks
Shutdown 8	30 CM	15 weeks
Long shutdown	104 CM	1 year
Shutdown 11	39 CM	17 weeks
Shutdown 12	-	-
Shutdown 13	-	-
Shutdown 14	-	-

Minimum lengths of FCC-ee extended shutdowns based on the number of cryomodules (CMs) to be installed and a special 12 week margin for the first three years; shutdown no. 1 refers to the first shutdown after one year running on the Z pole.

Total length without kickers: 2212.3 m


FCC ArcGIS database





WHAT'S NEXT

Main topics and milestones for Integration activities





Thank you
for your attention.