

# ***EXPERIENCE WITH THE VACUUM SYSTEM IN SuperKEKB***


## Contents

- Vacuum system in SuperKEKB
  - New components, with some points to note
- Results and problems so far
  - Status of components, Electron cloud effect, Pressure bursts, etc.

Y. Suetsugu  
Accelerator Laboratory, KEK

## SuperKEKB

- An electron – positron collider with asymmetric energies.
  - Located at KEK Tsukuba campus
- Upgrade project of KEKB B-factory, which had been successfully in operation during 1998~2010.
- Mission: Quest new theories beyond the standard model at B-meson regime.




# Configuration

- Main ring (MR)
  - Circumference ~ 3016 m
  - 7 GeV Electron ring (HER)
  - 4 GeV Positron ring (LER)



MR tunnel



Collision point

- Belle II Detector



Belle II


- Positron damping ring (DR)
  - Circumference ~ 136m
  - Energy 1.1 GeV

- Injector (Linac)
  - Length ~ 700 m
  - Generate electron and positron
  - Accelerate up to final energy



MR tunnel


# Project timeline



- 2010~2016 Construction (Upgrade from KEKB)
- 2016/2~6 Phase-1: Test operation (Beam tuning)
- 2018/3~7 Phase-2: Commissioning operation (Collision tuning)  
(Installation of final focusing SC magnets and Belle II Detector)
- 2019/3~ Phase-3: Physics operation

# Vacuum system

- The vacuum system was a key upgrade point.
- **LER:** Approximately **93%** of beam pipes and bellows chambers in length were renewed.
- **HER:** Approximately **82 %** were reused.




- Sub systems, such as cooling water system, compressed air system, were basically reutilized, with necessary upgrades.
- Control system is also reused, but the antique components were updated.

## Requirements to vacuum system




- **Ultra-high vacuum** to ensure long beam lifetime, keep small beam emittance, reduce background noise to detector, and avoid ion instability (HER)
  - Target pressure :  $\sim 10^{-7}$  Pa with beams
- High tolerance against **high current beams** for stable operation
  - New RF shields for bellows chambers and gate valves
- **Suppression of electron cloud effect (ECE)** to avoid emittance growth and beam size blow up in LER
  - Beam pipe with antechamber, solenoid field, coating of TiN film, clearing electrodes, groove structure, and external magnetic field
- **Low beam impedance** to keep small beam emittance and short bunch length, and to avoid beam instabilities
  - Beam pipe with antechamber, step-less connection flange, new collimators with low impedance
- **Reliable and stable system**
  - Large scale vacuum system: Several thousands control points.
  - Cost performance

# Main components



- New beam pipes with antechambers.
  - Realize low beam impedance by putting SR masks and pump ports in antechambers
  - Effective to reduce photo electron effect
  - LER arcs: Aluminum alloy (A6063)
  - HER and Wigglers: OFC (C1011)



Beam pipe with antechambers



- New bellows chambers and gate valves with comb-type RF shield
  - High thermal strength
  - Applicable to cross sections with antechambers




Gate valve



# Main components -2


- Step-less connection flange: MO-type flanges
  - Little step inside and low beam impedance
  - Adaptable to various types of cross sections
  - Various types of copper (C18200) and aluminum-alloy (A2219) flanges were developed.



Al flange (test model)




Al gasket




- Beam collimator
  - Key component to suppress beam background of Belle II.
  - New type collimators, which have low impedances and fit antechamber scheme, were developed.


Horizontal type




Horizontal type in tunnel



Collimator head (jaw)





Inside view





# Main components -3

- Main pump: Three layers of NEG strips ST707 (arc)
  - Installed into an antechamber: provide effective pumping system
  - Activation by micro-heaters (sheath heaters) inserted between strips
  - Screens between pump and beam
  - Average pumping speed of 0.14  $\text{m}^3\text{s}^{-1}\text{m}^{-1}$  for CO




- Auxiliary pump: Sputter ion pumps
  - Almost every 10 m, RF shield on the port
  - Official pumping speed of 0.4  $\text{m}^3\text{s}^{-1}$




# Main components -4

- Countermeasures against electron cloud effect (ECE)
  - ECE: A critical issue for the SuperKEKB positron ring (LER)
  - Based on various R&D results in KEKB and other institutes, various countermeasures were prepared.




Summary of countermeasures for LER

Sections	L [m]	L [%]	Countermeasure	Material
Drift space (arc)	1629	54	TiN coating + Mag. field	Al (arc)
Steering mag.	316	10	TiN coating + Mag. field	Al
Bending mag.	519	17	TiN coating + Grooved surface	Al
Wiggler mag.	154	5	Clearing Electrode	Cu
Q & SX mag.	254	9	TiN coating	Al (arc)
RF section	124	4	(TiN coating +) Mag. Field	Cu
IR section	20	0.7	(TiN coating +) Mag. field	Cu
<b>Total</b>	<b>3016</b>	<b>100</b>		




Grooved surface




- Expected average  $e^-$  density  $\sim 2 \times 10^{10} e^- m^{-3}$
- Less than the threshold estimated by simulations

## Points to note -1

- Beam pipes with antechambers
  - Welding lines (Tig welding) of aluminum beam pipes cracked just after starting evacuation in the tunnel (3 pieces).
  - Structural simulation indicated a high stress at top and bottom of the beam channel due to
    - Atmospheric pressure
    - Weight of bellows chamber at end, if not supported.
  - Be careful with non-circular beam pipes.
- Bellows chambers with com-type shield
  - Heavy (especially for Cu bellows chambers)
    - Robust support for each bellows chamber.
  - Small transvers/longitudinal tolerance
    - Careful alignment of components adjacent to the bellows chamber.



Cracked beam pipe (Al)



Support for each bellows chambers




Installation of bellows chamber using crane




# Points to note -2

- MO-type flange
  - Need careful bolt tightening
    - Uniform bot tightening is important.
    - A manual was prepared for workers.
  - Weak against scratches on sealing surface
    - Polishing is available using “Scotch-bright”.




Manual for bolt tightening



- Air leaks were detected when the connection between Al and Cu (or SS) flanges were baked up to 150°C.
  - Regardless of gasket materials (Cu or Al)
  - Big difference of thermal expansion rates between these flanges should be a cause.
  - Use Cu-Al transition bellows chamber to connect Cu and Al beam pipe.



Cu-Al bellows chamber for GV (SS)



	Stainless-steel bolt (for Cu/Cu, SS flange)	Aluminum-alloy bolt (for Aluminum flange)
Order of fastening	Fasten the bolts using a torque-wrench in the order specified above 1-2. The order of [5-8] and [9-12, [15-20] and [21-28] can be exchanged, respectively.	Fasten the bolts using a torque-wrench in the order specified above 1-2. The order of [5-8] and [9-12, [15-20] and [21-28] can be exchanged, respectively.
Fastening torque	Start from 50-100-150 [kg cm] - 1 set for one torque value (1 set = 1 fastening for all bolts) - Finally, 3 sets at 160 [kg cm]	Start from 50-100-125 [kg cm] - 1 set for one torque value (1 set = 1 fastening for all bolts) - Finally, 3 sets at 140 [kg cm]
If leaked	Increase the fastening torque every 10 [kg cm] step, up to less than 200 [kg cm]. If unsuccessful, exchange gasket	Increase the fastening torque every 10 [kg cm] step, up to less than 170 [kg cm]. If unsuccessful, exchange gasket
Gap control	- Almost uniform usually - As a measure: <math>\pm 0.3\text{mm}</math> at (1)-(8)	- Not uniform usually - As a measure: <math>\pm 0.03\text{ mm}</math> at (1) and (5), and <math>\pm 0.15\text{ mm}</math> at (3) and (7).
Gasket	Copper: OFC/Acid cleaning, Annealed Hv = 40-50 Aluminum: A5052(H34) (Acid cleaning, Chemical polish, Annealed Hv=50 - 60) No scratches	Copper: OFC/Acid cleaning, Annealed Hv = 40-50 Aluminum: A5052(H34) (Acid cleaning, Chemical polish, Annealed Hv=50 - 60) No scratches
Note	- Lubricant (such as molybdenum paste) should be used	- Lubricant (such as molybdenum paste) should be used - Each time used - Gap control is very useful


# Present operation status

- Phase-3 operation (Physics run)
  - Physics Operation is continuing steadily.
  - No break due to COVID-19!



$$L = 3.12 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$$

(world record)



- We are now exploring uncharted territory!

- Recent beam currents:


- HER  $\sim 700 \text{ mA}$ ,
- LER  $\sim 800 \text{ mA}$
- 1174 bunches

- $\beta_y^*$  (ver. Beta function at IP) =  $1 \text{ mm}$  (Min.  $0.8 \text{ mm}$ )

- Max. luminosity =  $3.12 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$
- Total integrated luminosity (recorded)  $\sim 200 \text{ fb}^{-1}$



## Vacuum scrubbing

- Vacuum scrubbing ( $dP/dI$  vs beam dose,  $\eta$  vs photon dose)
  - LER:  $\eta$  decreased to less than  $1 \times 10^{-6}$  molecules photon $^{-1}$ , at a photon dose of  $2.5 \times 10^{25}$  photons  $m^{-1}$ , here the pumping speed of  $0.06 \text{ m}^3\text{s}^{-1}\text{m}^{-1}$  is assumed.
  - HER:  $\eta$  is lower than that in LER. For arc section, where the beam pipes was reused,  $\eta$  decreased to less than  $1 \times 10^{-7}$  molecules photon $^{-1}$ , at a photon dose of  $3.7 \times 10^{25}$  photons  $m^{-1}$ . → Memory effect




## Temperatures of new components

- Status of new vacuum components
  - Confirming the stability of the new vacuum components was a major subject for the Phase-1 beam commissioning.
  - No extra heating or abnormal pressure rise in these components was observed.
  - The temperature rises in the bellows chambers, gate valves and flanges are 2~4 °C at 1010 mA, for example.




## Air leak from MO-type flange

- We experienced air leak two times in wiggler sections, where the beam snakes and the intense synchrotron radiation (SR) is emitted horizontally.
  - **Case 1:** SR hit the antechamber part of the flange due to vertical COD.
    - The vertical COD at upstream side was corrected to be flat as much as possible.




- **Case-2:** A cooling-water pump has broken suddenly during beam operation, and the flange was locally heated up rapidly.
  - The temperature of beam pipe rapidly rose over 100°C.
  - The temperature of flanges at antechamber part should be more.
- Local heating should be avoided.

Temperatures after stopping cooling water



## Electron cloud effect


- Non-linear behavior of pressure against beam current due to ECE was observed at a beam current of  $\sim 900$  mA during Phase-1 (w/o mag. fields).
  - EC  $\rightarrow$  Electron multipactoring  $\rightarrow$  Non-linear behavior of pressure
- TiN-coated beam pipes with antechambers at drift spaces were the source of EC.
  - Measured electron density is near to the threshold of the instability,  $\sim 3 \times 10^{11} \text{ e}^- \text{ m}^{-3}$
  - Permanent magnets around the beam pipes suppressed the non-linear pressure rise.
- This ECE was cured by permanent magnets around beam pipes after Phase-2.
  - Magnetic field of  $\sim 50$  G in the beam direction.
- At present, any obvious signs of EC are not observed.



Permanent magnets for beam pipes at drift spaces







Magnetic fields inside of units




## Electron cloud effect

- In a beam study, the ECE (vertical beam size blowup) was not observed until a current linear density of  $0.4 \text{ mA bunch}^{-1} \text{ RF bucket}^{-1}$  (line charge density) with magnetic fields.
- Beam pipes with antechamber and TiN coating were found to be effective to suppress EC compared to a round Cu beam pipe (KEKB type). [ $0.04 \rightarrow 0.2 \text{ mA bunch}^{-1} \text{ RF bucket}^{-1}$ ]
- However, the threshold of ECE w/o magnetic fields was lower than expected, although the  $\delta_{\text{max}}$  of TiN coating seems low ( $1.2 \sim 1.0$ ).
- The most plausible reason is that the irradiation of photons in the beam channel is stronger than expected due to the vertical spread or scattering of SR.
- These results indicates that **photoelectrons is very important for the ECE in the real machine.**




## Beam losses accompanied by pressure bursts


- Beam aborts (losses) accompanied by local pressure bursts have been frequently observed in especially LER during Phase-1.
  - The locations of the pressure bursts have spread to more than 20 points along the ring.
  - In most cases, the bursts were observed near aluminum beam pipes in dipole magnets, with groove structure (a measure against ECE).
  - The beam-loss monitors at collimators triggered the beam aborts.
  - Beam loss lasted a few ms before the beam abort.



Typical abort log for the case pressure burst was observed. (H. Ikeda, KEK)




Groove in the beam pipe



## Beam losses accompanied by pressure bursts

- A possible cause: **Collision of “dusts” with circulating beams.**
  - Groove structure is likely to catch dusts.
  - Aluminum grooves were formed at the first stage of beam pipe fabrication, before cutting.
  - Lots of large dusts were gathered from a beam pipe after the knocking.
  - A “**knocker**” was set at a beam pipe in a bending magnet, where the burst had been observed frequently, and we could reproduce the phenomena by knocking it.
- As a countermeasure, we knocked most of beam pipes in bending magnets (with groove) around the ring before Phase-2.
  - The reduction of the frequency of bursts was observed after Phase-2.
  - **Continue to be careful at higher beam currents.**


Dusts gathered from a beam pipe



Knocker




History of beam aborts accompanied by pressure bursts



## Rapid heavy beam loss


- Recently, rapid (in  $20\sim 30\ \mu\text{s} = 2 \sim 3$  turns) heavy beam losses have been observed in (mostly) LER and HER.
  - Sometimes, it resulted in damage of collimator head and QCS (SCC final focus magnets) quench, and also damage of detectors.
  - No clear transvers oscillation has not been observed by BOR (Bunch Oscillation monitor)
- The cause has not been clarified yet.
  - Possible causes will be “dust event” and/or beam instability.
  - However, the beam loss is so fast, and simulations so far have not been able to explain the phenomena.
  - Preparation of more loss monitors around ring is planned to identify the origin points of these losses.
- An urgent issue to be solved to increase beam current further.




# Beam collimator

- New collimators of 3 horizontal and 1 vertical type, and 7 horizontal and 3 vertical type have been installed in HER and LER, respectively.
  - 16 KEKB-type collimators have been installed in HER.
- These collimator is working well so far to suppress the background.
- Problems
  - Excitation of transvers mode coupling instability (TMCI) due to their high-beam impedance. (Narrower aperture than expected in the design phase.)
  - Damage of collimator head due to beam hitting.
- Details will be reported by T. Ishibashi (KEK) in the impedance session.


Vertical-type collimator in tunnel



Layout of collimators in MR



Examples of damages (Ta head)



## Summaries



- The SuperKEKB vacuum system has been working mostly well.
  - No abnormal temperature increase or vacuum pressure was observed for the new vacuum components up to beam currents around 1 A.
    - Air leak from MO-type flange happened in wiggler sections due to localized heating by SR.
  - Vacuum scrubbing progressed steadily.
  - The effects of the antechambers and TiN coating against ECE were confirmed.
  - No clear indication of ECE has not been observed with permanent magnets.
    - Effect of photons hitting in the beam channel seems larger than expected.
  - Beam aborts (losses) accompanied by local pressure bursts have been frequently observed in the LER during Phase-1.
    - Knocking of beam pipes seems working to some extent after Phase-2.
  - Very rapid heavy beam losses are now frequently observed.
    - The analysis is ongoing.
  - Beam collimator has been working well for suppressing background.
    - Damage of head is now a serious problem. → See Ishibashi's talk.
- We will continue the operation aiming at further higher luminosity by increasing beam currents and squeezing  $\beta_y^*$ . It is very challenging and exciting.
- The vacuum system must be monitored closely and carefully.

*Thank you for your attention.*

# Backup



## Pre-installation work

- Basically all beam pipes are baked at 150°C for ~24 hours including NEG activation before installing them into the tunnel.
- Inside of LER beam pipes are coated with thin TiN to mitigate ECE.



## Construction period


- Fabrication of components
- Pre-installation works (TiN coating and pre-baking).
- Installation of components into the tunnel
- Update of sub-systems
- Baking of ion pumps and NEG activation in the tunnel are on going.




# NEG activation in tunnel

- NEG activation in the tunnel
  - Regions between gate valves in the tunnel were evacuated in series after installing beam pipes and bellows chambers
  - After rough pumping and He leak check, ion pumps were baked and NEG pumps are finally activated.
  - No baking of beam pipes in the tunnel
  - After NEG activation, average pressures of less than  $1 \times 10^{-7}$  Pa were obtained for most cases.

NEG activation pattern



A typical trend of pressures during activation




## Installation into tunnel

- Installation of beam pipes is in progress in the tunnel.
- Approximately 95 % of pipes have been installed (2015/2/6).




## Installation into tunnel

- Installation of bellows chambers follows the beam pipes.



## Residual gases

- Residual gases during the beam operation have been monitored with a quadrupole mass analyzer (QMA) at an arc section.
- The QMA is located just above a sputter ion pump.
  - The main gases are hydrogen ( $m/e = 2$ ), carbon monoxide ( $m/e = 28$ ), methane ( $m/e = 16$ ), water ( $m/e = 18$ ), and carbon dioxide ( $m/e = 44$ ).
    - The high partial pressure of methane should be due to the pumping system using NEG as a main pump.
    - Because the beam pipes were not baked in the tunnel, water vapor still remains in the beam pipe.



## Main parameters (Design)

- The main ring consists of 4.0 GeV positron ring (Low energy ring, LER) and 7.0 GeV electron ring (High energy ring, HER).
- Aiming a peak luminosity of  $\sim 8 \times 10^{35} \text{ cm}^{-2}\text{s}^{-1}$ ,  $\sim 40$  times higher than that of KEKB.

	LER (positron)	HER (electron)	Unit
Beam energy	4.0	7.0	GeV
Beam current	3.6	2.6	A
Circumference	3016		m
Number of bunches	2500 (Bunch interval = 1.2m)		
Bunch current	1.44	1.06	mA
Bunch length	6.0	5.0	mm
$\epsilon_x/\epsilon_y$	3.2/8.64	4.6/11.5	nm/pm
$\beta_x^*/\beta_y^*$	32/0.27	25/0.3	mm
Crossing angle	83		mrad
Luminosity	$8 \times 10^{35}$		$\text{cm}^{-2}\text{s}^{-1}$
Bending radius (Arc)	74.68 (arc)	105.98 (arc)	m


## Main parameters related to vacuum system

	LER (positron)	HER (electron)	Unit
Material of new beam pipe	Al-alloy (arc) OFC (wiggler)	OFC (arc), OFC (wiggler)	
Cross section of new beam pipe	φ90 + Antechambers	Racetrack (50×104) φ50 + Antechambers	
Main pumps	NEG (strip)	NEG (strip + cartridge)	
Total Power of SR	1.1 (arc:2200 m) 6.3 (wiggler:300 m)	5.2 (arc: 2200 m) 1.1 (wiggler:100 m)	MW
Critical Energy of SR	1.9 (arc) 9.2 (wiggler)	7.2 (arc) 17 (wiggler)	keV
Max. SR power line density	2.6 (arc) 13 (wiggler)	7.7 (arc) 9 (wiggler)	kW m <sup>-1</sup>
Avg. photon flux line density	~5.5×10 <sup>18</sup> (arc) ~4.7×10 <sup>19</sup> (wiggler)	~6.8×10 <sup>18</sup> (arc) ~1.3×10 <sup>19</sup> (wiggler)	photons s <sup>-1</sup> m <sup>-1</sup>
Linear pumping speed	~0.1 (arc)	~0.06 (arc)	m <sup>3</sup> s <sup>-1</sup> m <sup>-1</sup>
Ave. pressure with beam		~10 <sup>-7</sup>	Pa
Ave. base pressure		~10 <sup>-8</sup>	Pa

# Number of main components

Types of beam pipes

Type	HER	LER	Total
Q-type	86	421	507
B-type	24	152	176
S-type	100	415	515
T-type	19	14	33
<b>Total</b>	<b>229</b>	<b>1002</b>	<b>1231</b>



Types of NEG pumps

Type	Length[mm]	LER	HER	Total
Type-1	700	21	9	30
Type-2	1000	53	12	65
Type-3	1300	60	18	78
Type-4	1600	227	19	246
Type-5	1900	163	32	195
Type-6	2200	389	30	419
Type-7	2500	66	2	68
Type-8	2800	6	2	8
Type-9	3100	0	17	17
<b>Total</b>		<b>985</b>	<b>141</b>	<b>1126</b>

Types of bellows chambers

Type	Material	Total
Bell_104x50-Cu	Cu	42
Bell_122x50-Al	Al	4
Bell_60x40	Al, Cu	19
Bell_f50x190-Ar	Cu	35
Bell_f80-Cu	Cu	31
Bell_f80x220-Ar	Cu	84
Bell_f90	Al, Cu, Al-Cu	19
Bell_f90x220	Al, Cu, Al-Cu	991
Bell_f90x220H24-Al_E	Al	16
<b>Total</b>		<b>1241</b>