Update from TISD and Beam manipulation

S.Rothe for SY-STI-RBS







Outline

- FE11 (3)
- Targets for 2021 (3)
- TISD : Molecular beams and Materials (8)
- Gas systems (new and old) (2)
- The Tapestation (1)
- Beam switching (1)



FE11 Extended High Voltage Tests

- FE11 commissioning in OL2 revealed occasional dropout of the line heating.
- With the addition of TIMBER to OL2 clear evidence for discharging was found.
- Systematic disassembly of FE11 down to the main high-voltage insulator to rule out other components.
- Hand polishing of closest metal surfaces.
- > Discharges persist





- Remounting of FE 8 at OL2 reveals rate of discharge is identical
- Timber data demonstrates the **same behaviour from previous online frontends**
- All evidence points to no worsening of this issue with the latest frontends.
- Must consider amelioration strategies in the design of the next generation of frontends
- Budget allocated to install new FE in LS3



Slide: M.Bissell, (Y.Gracia, J.Cruikshank, S.Marzari)





FE11 (Frontend for HRS)



- FE11 was transported to the ISOLDE Target Area on the 19 January 2021
- Final installation and Commissioning for the FE11 HRS is ongoing:
 - Alignment completed
 - Vacuum connection and testing ongoing
 - Cabling HV/LV, controls and service connections to begin this week



CERN SY STI

Slide: J.Cruikshank

Frontend 11 installation at ISOLDE

PLANNING - EDMS 2339464					juin 2020				janvier 202.				février 2021			mars 2021					
update 26.1.2021			1	8	15	22	11	18	25	1	8	15	22	1	8	15	22	29			
	FE11 sur HRS (impact 123487)	Resp.	Inve	stig	atio	ns HT	terr	niné !													
	Installation FE11 : (pour information)						terr	ninké !					Par	noncabilité					1		
80	mettre le robot GPS en position	FR+JLG		Terminé Coordination: S.Marzari (SM)								SM))								
81	remontage des BI (wire grid, faraday cup)	WA+MD		Terminé Vide: J.Ferreira (JF)+ A.Gutierrez (AG									J.Aubert								
82	déplacer le FE dans la Faraday cage	SM+JLG						Τe	er mir	۱é		1	Test Con	Controle FE: C.Mitifiot (CM)							
83	alignement grossier +/- 2mm	SM+JC						Te	rmir	né			Bea Cab	am Instrumentation: W.Andreazza (WA) + M.Duraffour (MD) Iblage: P.Harwood PH) + S.Rothe (SR) + P.Lelong							
84	alignement fin +/- 0.1mm	AB						Те	ermir	۱é			Alig Rob	Alignements: A.Behrens (AB), A.Beynel (AB) Robot et camera: Francesco Riccardi (FR) + JL.Grenard (JLG)							
85	Raccordement chambre à vide et autres hardwares	JF										1	HT : Rad	HT : Thierry Gharsa (TG) Redionestection: A Deschamps + A Aubert							
86	connections diverses vide (controls, cablings)	AG										1	Gen	General Safety: AP.Bernardes							
87	connecter la partie HT (puissance, contrôle, air, eau)	SM+JC										ļ	-								
88	connecter la partie contrôle (swiches, potentiomètres)	CM										i									
89	connecter la partie beam optics (quads, déflecteurs)	JC										i									
90	connecter la partie BI (wire grid, faraday cup)	MD										i									
91	optimiser longueur cables (retirer vers séparateur) et connect.	tous										ļ									
92	changement du vérin de la porte	JC						Te	rmin	né		ļ									
93	vérification des trajectoires robot	FR+JLG																			
94	tests mécaniques	SM+CM																			
95	tests vacuum	JF+AG																			
96	installation de la nouvelle coiffe	JC+SM										¥									
97	Scan 3D de la Faraday Cage GPS avec FE11	AB																			
	Tests on-line en mode off-line	SR																			

Beam commissioning at **HRS** begin in **early March**

Targets for 2021

5 UC target units produced 2020 and stored

• Pre-production of all UC units due to upgrade of nuclear ventilation (till mid 2021)



#709-UC-Ta #711-UC-Ta #713-UC-VD5 #715-UC-Ta

#717-UC-Ta

~15 target units for production 2021



10 target units recuperated from Run 2

- For **online operation**: #654 UC-W | n.conv. | K MM #635 UC-Ta | Be MM #534 Sn | VD #619 Pb | VD #653 UC-Ta | n.conv | In, Cu MM #641 UC-Ta | Mn, In MM
- Molecular / Actinide beam dev. (M.Au, B.Reich, ISOLTRAP MR-ToF)

#637 UC-Ta | CF4, NF3 #638 UC-Re | Li, Sm MM #659 UC-VD7 #668 UC-VD5





New Supplier Contract for vacuum vessels for the ISOLDE target



(Image credit ALCA, previous supplier)

CERN Rules

- Contracts over 750K CHF follow full invitation to tender process;
 - Market Survey
 - Invitation to Tender
 - Contract award
- Contract put out to tender every 5 years

M.Owen







The Development Team:





Molecular beams : Why ?





Studying molecular beam formation

Concept for a dedicated development unit for molecular beams (pre LS2)



Collaboration with MIRACLS experiment launched





Heated reaction

volume

Solid Samples (mass markers)

Molecular beam development @ Offline 1





 Dedicated target/ion source for molecular beams Offline gas injection and reaction studies





Comparison of four mass scans in the same region of interest

-> showing changing peak intensities in response to changing target and ion source conditions

M.Au



High resolution mass spectrometry for TISD

- Offline developments at MIRACLS PoP MR-ToF (Bat.508)
 - Negative ion beams for electron affinity study
 - From mid 2021: Molecular beams



The MIRACLS proof-of-principle setup, featuring an ISOLDE target and ion source coupled to a Paul trap before an MR-ToF.

- Offline/Online developments at ISOLDE
 - Study of beam composition from pre-irradiated targets using ISOLTRAP MR-ToF planned for spring 2021
 - High mass resolution required for identification
 - Development of actinide beams
 - LISA (Laser Ionization and Spectroscopy of Actinides)*

*This Marie Sklodowska-Curie Action (MSCA) Innovative Training Network (ITN) receives funding from the European Union's H2020 Framework Programme under grant agreement no. 861198



https://miracls.web.cern.ch/experiment.html





M.Au

Target material development (nano)

Nano-UC_x target

- Process development focused on nanometric UO₂ mixed with Multiwalled Carbon NanoTubes (MWCNTs)
 - Transfer of existing procedures to glove box confinement
 - **Optimization of reaction conditions** (solvents, temperature, surfactants, mixing, grinding, pressing, etc)
- **Development** of alternative processes (bottom up)
- Production will be carried out in the new Nanolab



SEM of MWCNT-based $\ensuremath{\mathsf{UC}_{\mathsf{x}}}$



Surfactant micelles around MWCNTs

SEM imaging required for successful development

Nano-LaC_x target

- Development of a LaOH + MWCNT based target material
- Acts as a surrogate for nano-Uc_x
- Development phase already ongoing in the chemical lab
- Outcome will be directly translatable to nano-UC_x!



Prototype chemical reactor in (to be) refurbished glove box to optimize reaction conditions



Planetary ball for powder particle size reduction.

S.Stegemann, E.Reis



Target material development

SiC target

- Previous supplier sold their SiC business
- Procurement or development of an equivalent raw material to produce targets that meet previous performances



Particle diameter [µm]

Ta-foil target

- Supplier stopped offering 6 μm thick foils
- Looking for new supplier
- > Alternatives considered:
 - Postprocessing of thicker foils



Foil rolling mill

Micrometric Ta-wires





PM 100

(New) development and characterization equipment

Planetary ball mill – Powder particle size reduction



Laser diffraction particle size analyzer



Gas sorption - Pore size distribution





Carburization pumpstand w. new control software

Target development, target sintering

studies,...





TGA-MS – Reaction kinetics







S.Stegemann, E.Reis, Y.Gracia

ISOLDE Gas Systems Update

PLANNING	Resp.		Jan. 2021				Feb	. 2021			Marc	April 2021				
		4	11	18	25	1	8	15	22	1	8	15	22	5	12	19
Arrival Hardware Test	YV	finished														
Device Electronics Test	CM	finished														
GPS FE																
Design	FJ + YV	finished														
Mark, Drill Pletine	FJ + YV			finished												
Build tubing + System	FJ + YV															
Leak Tests	YV															
Final Electronics Check	CM + YV															
Arrival New EVR116	YV															
Implementation FC	FJ + YV															
HRS FE																
Arrival Components	YV															
Mark, Drill Pletine	FJ + YV															
Build tubing + System	FJ + YV															
Leak Tests	YV															
Final Electronics Check	CM + YV															
Implementation FC	FJ + YV															

Specifications

Implementation modes:

- Calibrated leak.
- Leak valve.
- Loop.

Ready for 3 inlet lines and 3 output lines (to FE)

Gases: Ar, N2, NF3, O2, SF6, CF4, Air, H2 (2% in Ar), CO (after upgrade)







- Control system tested w. hardware (C.Mitifiot, BE/CEM)
- Assembly ongoing
- Installation foreseen end of FEB

Y.Gracia, F.Josa



ISCOOL He Gas Injection



Motorized needle valve installed in 2007 was removed in 2012 and replaced with a hand operated valve.

- Significant difficulty to set correct flow rate (2 people communicating via mobile).
- No possibility to tune He flow based on ion beam transmission.

2 alternative systems investigated in 2012 and 2018 found to be unsuitable.

Meanwhile, the new ISOLDE target gas injection employs the same valves as previously used on ISCOOL.

Move back to the original specification maintaining commonality of spare parts and universality of controls infrastructure.

M.Bissell, Y.Gracia



The Tape Station (TS1)

IFIN-HH 3x3 SiPM array





• Beam instrumentation and low level control:

• Beam scanner to be installed by SY-BI, design phase

Beta detectors:

- 2 prototypes (3x3 SiPM array) tested at CERN, noise at tapestation position is absent, **ready for production**.
- Same design can be used for all the positions.
- Updating drawings and producing new parts, collaboration with SY-STI-TCD.

HPGe detector:

- Preliminary tests at GSI show a fully recovered resolution
- noise from cooling system was identified and currently addressed.
- Data acquisition:
 - CAEN DT5725 purchased, all-in-one solution
- Top level Controls (GUI)
 - Basic version by BE-OP (Java)
 - Expert interface via STI-RBS (LabVIEW)
- Future
 - Final tests to be performed by March with all detectors in place
 - Once TS1 ready launching TS2 installation





Old Tapestation HPGe detector



(R.Lica)



ISOLDE beamlines: Alternating and Switching operation

More details see presentation in EPIC Workshop 2020

Alternating mode



[[]TG06] <u>M. Lindroos and T. Nilsson, "HIE-ISOLDE: the technical options,"</u> <u>CERN-2006-003, (2006).</u> (Chapter 7 by T. Giles)

- Requires proof of concept + prototype (100kCHF, looking for funding)
- Final design can be installed during a winter shutdown

Sharing mode



[srr16a] S.Rothe, "Proposal - Introducing Fast Beam Multiplexing at ISOLDE", <u>EDMS1509964</u> [srr16b] S.Rothe et al., "Advances in surface ion suppression from RILIS: Towards the Time-of-Flight Laser Ion Source (ToF-LIS)" <u>NIMB, 376 (2016) 86-90</u>

- Tested at ISOLDE, used already for experiments
- Can be set up on request
- to be integrated in ISOLDE timing system





